

Fiber-Optic Monitoring of a Twin Circular Shaft Excavation: Development of Circumferential Forces and Bending Moments in Diaphragm Walls

by

Shao-Qun LIN

PhD Student

Department of Civil and Environmental Engineering
The Hong Kong Polytechnic University, Hong Kong SAR, China
Email: shaoqun.lin@connect.polyu.hk

Dao-Yuan TAN (corresponding author)

Associate Professor

School of Earth Sciences and Engineering
Nanjing University, Nanjing, China
Email: dytan@nju.edu.cn

formerly,

Department of Civil and Environmental Engineering
The Hong Kong Polytechnic University, Hong Kong SAR, China

Yat Fai LEUNG

Associate Professor

Department of Civil and Environmental Engineering
The Hong Kong Polytechnic University, Hong Kong SAR, China
Email: andy.yf.leung@polyu.edu.hk

Jian-Hua YIN^{1,2}

Chair Professor of Soil Mechanics

¹: Department of Civil and Environmental Engineering

²: Research Institute for Land and Space

The Hong Kong Polytechnic University, Hong Kong SAR, China
Email: cejhyin@polyu.edu.hk

Ivan LI

Geotechnical Engineer

Geotechnical Engineering Office

Civil Engineering and Development Department, Hong Kong SAR, China

Email: ivanli@cedd.gov.hk

Eric H.Y. SZE

Senior Geotechnical Engineer

Geotechnical Engineering Office

Civil Engineering and Development Department, Hong Kong SAR, China

Email: erichysze@cedd.gov.hk

Frankie L.C. LO

Senior Geotechnical Engineer

Geotechnical Engineering Office

Civil Engineering and Development Department, Hong Kong SAR, China

Email: frankielclo@cedd.gov.hk

Hon-Shing KAN

Deputy Project Manager

East Development Office

Civil Engineering and Development Department, Hong Kong SAR, China

Tommy C. W. WONG

Senior Engineer

East Development Office

Civil Engineering and Development Department, Hong Kong SAR, China

Eric Y. M. CHAN

Geotechnical Engineer

East Development Office

Civil Engineering and Development Department, Hong Kong SAR, China

1 **Abstract:** This study investigates the behaviour of a 38-m deep twin-circular ‘peanut-shaped’
2 cofferdam interconnected with a rectangular section for cut-and-cover tunnel construction, using
3 distributed fibre optic sensors (DFOS) based on optical frequency domain reflectometry (OFDR). The
4 distributed sensors revealed that temperature changes on the two sides of the diaphragm wall were
5 different upon its exposure by excavation, while the measured strains were used to evaluate the wall
6 deflection and bending moments. The high spatial resolution achieved by DFOS measurements revealed
7 unique aspects of the wall response, which are difficult to be obtained by conventional types of
8 instrumentation. In particular, the strains along vertical and lateral directions of the wall panels were
9 measured, the latter of which indicated eccentric compression in the concrete panels that arise from the
10 distinctive peanut-shaped geometry. Developments of hoop forces and circumferential bending
11 moments in the panels at various construction stages are discussed, with particular focus on the release
12 of such during partial demolition of a temporary crosswall to facilitate the assembly and launching of
13 tunnel boring machines. The mechanisms of stress developments and release are simulated using three-
14 dimensional finite element models which, together with the field measurements, enhance the
15 understanding of the behaviour of multi-cell cofferdams.

16

17

18

19 **Keywords:** Circular cofferdam; Deep excavation; Diaphragm walls; Hoop strain; Distributed fibre
20 optic sensors

21

22 Introduction

23 The design and construction of circular cofferdams are becoming common around the world, as they
24 entail more working space within the excavation compared with multi-propped walls where the struts
25 may obstruct the works. In some cases, wall toe stability could be enhanced by the circular geometry,
26 reducing the needs for ground treatment below the excavation level. Therefore, the design of circular
27 shafts often leads to more efficient and safer construction processes. Recently, Schwob et al. (2019)
28 reported the construction of a 15-cell caterpillar-shaped cofferdam as part of a sub-sea road project in
29 Hong Kong. Some cases of circular cofferdams have also been reported in the past. For example,
30 Kumagai et al. (1999) measured the displacements and vertical and circumferential stresses of the
31 retaining wall supporting a circular excavation with a diameter of 144 m. Parashar et al. (2007) reported
32 the measurements of wall deflections and the circumferential stresses in three circular shafts with
33 diameters of 30-40 m, while Tan & Wang (2013; 2015) studied the behaviour of a 100-m diameter
34 circular cofferdam. Apart from circular shafts, elliptical or multi-cell excavations were adopted in some
35 recent projects to facilitate the launching of tunnel boring machines (TBM). Gomes et al. (2008)
36 reported the settlements and wall deflections for an elliptical excavation for Porto Light Metro, which
37 was composed of two 22-m deep elliptic shafts (81 m × 40 m).

38

39 While it has been well established that the retaining structures of circular cofferdams depend on the
40 hoop action to support the excavations, there is still considerable uncertainty regarding their behaviours,
41 particularly the developments of circumferential (hoop) and bending stresses in the wall, and their
42 relationships with the geomaterial properties and shaft geometry, especially in the case of imperfect
43 circles such as elliptical or multi-cell caterpillar-shaped excavations. Despite the advances in numerical
44 modelling software and design tools, there remains a need to monitor the various aspects of their
45 performances, in order to enhance the understanding of such complex systems, ensure serviceability of
46 nearby facilities and reduce conservatism in the design practice for similar project scenarios in the future.
47 While ground settlements and vertical bending moments can be monitored through conventional
48 instruments such as settlement markers or inclinometers, the measurements of circumferential forces or

49 bending moments pose unique challenges. Diaphragm wall panels are usually around 2-3 m in width,
50 and vibrating wire strain gauges only produce discrete measurements which may not be representative
51 of the hoop stress distributions along the width of the panel. Under these conditions, distributed fibre
52 optic sensors may prove to be the ideal technique. It has become increasingly popular for geotechnical
53 and structural monitoring (Pelecanos et al., 2017; Nejjar et al., 2021; Sui et al., 2021), since they can
54 achieve fully continuous sensing along the entire length of the sensing cable, without being disturbed
55 by electromagnetic field and/or moisture. Successful applications of DFOS on excavation monitoring
56 have been reported extensively. Li et al. (2018) utilized DFOS embedded in wall panels to investigate
57 wall behaviour due to deep excavation, with the DFOS measurements in agreement with those by
58 conventional inclinometers. Zhu et al. (2022) studied the deformation patterns of curved shield tunnels
59 induced by adjacent excavations, based on the monitoring results by the DFOS. A summary of case
60 studies of excavation monitoring using fibre optic sensing is presented in Table 1. Schwamb et al. (2014)
61 and Torisu et al. (2019) presented the performance monitoring of circular excavations using distributed
62 fibre optic sensors based on Brillouin optical time-domain reflectometry (BOTDR), but the spatial
63 resolution was 1 m in their studies. The accuracy might therefore be compromised for the
64 abovementioned range of wall panel widths. The lack of well-established instrumentation techniques
65 for circumferential actions in these structures may have been an obstacle for the development of
66 standards or guidelines regarding the alarm thresholds of such quantities during construction monitoring.

67

68 In this study, the behaviour of a “peanut-shaped” cofferdam comprising two connected circular
69 excavations is investigated using distributed fibre optic sensors based on the optical frequency domain
70 reflectometry (OFDR). The OFDR technology with a high spatial resolution of 5 cm was employed to
71 improve the quality of the strain and temperature data, which is particularly important along the width
72 of wall panel. The vertical curvatures, hoop forces and circumferential bending moments are
73 investigated during various construction phases including dewatering, bulk excavation, installation of
74 lateral supports, and partial structure demolition between the two circular sections. Three-dimensional
75 numerical modelling shed further insights into the unique features of wall behaviour under these

76 processes, further highlighting the importance of monitoring the developments of circumferential forces
77 and bending moments in walls supporting circular or multi-cell excavations.

78

79 Project Background

80 The Trunk Road T2 and Cha Kwo Ling Tunnel Project of Hong Kong comprised a 3.4 km long, dual-
81 two lane trunk road connecting the Central Kowloon Route to the West and the Tseung Kwan O-Lam
82 Tin Tunnel to the East. Together they constituted Route 6 of the road network in the city. To facilitate
83 the tunnelling operations, a TBM launching shaft was constructed, which comprised an approximately
84 22-m long cut-and-cover section of tunnel box connected to a 55-m long twin-circular cofferdam as
85 shown in Fig. 1(a). Adjacent to the TBM launching shaft, there was an existing 4-storey building which
86 housed the Public Works Central Laboratory and was founded on friction prestressed concrete piles.
87 The clearance between the shaft wall and the building pile extrados was only 3.0 m. The twin-circular
88 cofferdam comprised two open, strut-free circular cells with radii of about 22.0 m for Cell 1 and 19.5
89 m for Cell 2, respectively. This peanut-shaped geometry was preferred as it could enhance construction
90 flexibility by eliminating steel struts, facilitate faster shaft excavation, assembly of the TBMs and
91 construction of the permanent tunnel box structure, and significantly reduce impacts on adjacent
92 structures and environment.

93

94 As indicated in Fig. 1(b), the rectangular section for cut-and-cover tunnel construction was laterally
95 supported by five layers of concrete slabs, namely Slab 1 to Slab 4 and the base slab. There were two
96 square openings for Slabs 1 to 4 with a side length of 9.0 m. Below Slab 4, two layers of preloaded steel
97 struts were installed and then the western crosswall would be partially demolished between Slab 4 and
98 the base slab, from -15.0 to -28.0 mPD (metres above Hong Kong Principal Datum) for TBM assembly
99 and launching. The diaphragm walls of the twin-circular cofferdam were designed to resist the water
100 and soil pressures by developing hoop forces in compression transferred to four Y-panels. Two
101 reinforced concrete (RC) beams were constructed at +2.5 mPD and -13.5 mPD, respectively, between
102 Cell 1 and Cell 2 to enhance the lateral support. The eastern crosswall between Cell 1 and Cell 2 would

103 be demolished simultaneously with the excavation process, down to the elevation of -25.0 mPD. The
104 thickness of all diaphragm wall panels was 1.5 m. The construction sequences of the cut-and-cover
105 tunnel section and the twin-circular cofferdam are shown in Figs. 2(a) and (b), while Fig. 2(c) shows
106 the site photo after the bulk excavation stage.

107

108 The ground conditions at the site consisted of a layer of fill overlying a marine deposits (MD) layer and
109 then alluvium (ALL) layer, as shown in Fig. 1(b). Completely decomposed granite (CDG) was
110 encountered underneath the alluvium layer, while the bedrock was defined as Grade III or better rock
111 (granite), and was generally encountered below -57 mPD across the site. The groundwater was
112 encountered at around +2.0 mPD. The diaphragm wall panels of the cut-and-cover tunnel section were
113 embedded into Grade III or better bedrock for groundwater cut-off while most of the wall panels of the
114 twin-circular cofferdam were terminated above rockhead, and those adjacent to the Public Works
115 Central Laboratory building were grouted to rockhead level for groundwater cut-off.

116

117 Optical Frequency Domain Reflectometry (OFDR)

118 The distributed strain and temperature sensing in this study is based on the optical frequency domain
119 reflectometry (OFDR) technology. The working principle of the OFDR sensing system is illustrated in
120 Fig. 3. Contrary to the optical time domain reflectometry (OTDR) technique, OFDR utilizes continuous
121 waves of light sources to achieve higher signal-to-noise ratios. The incident light from a tunable laser
122 source is divided into the reference light and the sensing light by an optical coupler. The former is
123 reflected through a mirror, while the latter passes through the fibre optic sensing cable. Some portions
124 of the sensing light experience Rayleigh backscattering due to variations in the refractive index in the
125 fibre (Ding et al. 2018). The backscattered light is mixed with the reflected reference light by the optical
126 coupler and then the mixed light is received and demodulated by a photoelectric detector to obtain the
127 strain or temperature changes along the length of the fibre optic cable. Specifically, the Rayleigh
128 spectral shift can be related to the strain and temperature changes by

$$\Delta\nu_R = c_\epsilon\Delta\epsilon_m + c_T\Delta T \quad (1)$$

129 where $\Delta\nu_R$ is the Rayleigh spectral shift, $\Delta\varepsilon_m$ is the mechanical strain change in DFOS, ΔT is the
130 temperature change in DFOS, c_ε is the coefficient of Rayleigh frequency shift induced by mechanical
131 strain change, c_T is the coefficient of Rayleigh frequency shift induced by temperature change, c_ε and
132 c_T can be considered as fixed values for single mode fibre under Rayleigh backscattering, which are -
133 0.15 GHz/ $\mu\varepsilon$ and -1.25 GHz/K in OFDR system with 1550 nm bands (Leviton & Frey 2006; Wu et al.
134 2020). An OFDR-based interrogator (OSI-S) manufactured by Junlong Technology Ltd., Wuhan, China
135 was used to collect the DFOS data in this study. The spatial resolution was set as 5 cm with measuring
136 accuracy of ± 0.1 K or ± 1 $\mu\varepsilon$.

137

138 Installation of DFOS

139 Three types of fibre optic cables were used to monitor the behaviour of the diaphragm wall during
140 excavation. A type of tight-buffered single-mode cable was employed for strain sensing (Fig. 4a), with
141 the fibre core protected by a steel strand-reinforced, medium-density polyethylene (MDPE)-jacket. The
142 cable diameter was 5.0 mm, where the tight buffer ensures efficient strain transfer and the steel strand
143 reinforcement prevents the sensing fibre from being damaged during site activities such as hoisting of
144 reinforcement cage and tremie concreting. A type of loose tube cable with a diameter of 5.0 mm was
145 used to monitor the temperature changes (Fig. 4(b)). Surrounding the fibre core are four layers of filling
146 materials including a spiral armour, Kevlar, metal mesh and a low smoke zero halogen (LSZH) sleeve
147 that improve the robustness of the cable. The space between the optical fibre and the spiral armour
148 makes it mechanical strain free. Both types of cables were manufactured by Suzhou NanZee Sensing
149 Technology Ltd., China. A type of sensing cable (referred to as the LIOS cable in this study),
150 manufactured by LIOS Sensing in Cologne, Germany, was also adopted and it involves optical fibres
151 for both temperature and strain measurements within the same bundle, as shown in Fig. 4(c). The LIOS
152 cable had a diameter of 10.9 mm.

153

154 Three panels were instrumented with fibre optic cables to investigate the behaviour of the twin-circular
155 shaft excavation, as shown in Fig. 1(a). Panel 1 was located within the cut-and-cover tunnel section,

156 while Panel 2 and Panel 3 were located within Cells 2 and 1, respectively. Specifically, Panel 1 was
157 located near the center of the rectangular cut-and-cover tunnel section, where the bending moments
158 along vertical direction and the deflections of the diaphragm wall were monitored. Panel 2 was located
159 near the middle of circular Cell 2 where the purpose of DFOS instrumentation was to monitor the
160 development of the circumferential forces far away from Y panels (heavily reinforced diaphragm wall
161 panels to transmit hoop forces at the interface between Cell 1 and Cell 2, see Fig 1(a)). DFOS was also
162 installed along the vertical direction of the wall panel to monitor the deflections, which was expected
163 to be the largest deflection within Cell 2. Moreover, numerical simulations prior to the construction
164 showed that partial demolition of the western crosswall would lead to releases of circumferential forces
165 in nearby wall panels. Therefore, measurements at Panel 2 can be used to indicate the range and extent
166 of such force release. Panel 3 was located near a Y panel and its response could reveal the hoop force
167 transfer to the Y panel.

168

169 The cable arrangements for the three panels are illustrated in Fig. 5. In Panel 1, four strain sensing
170 cables were installed along the depth of wall panel, arranged in pairs on the excavated side and the
171 retained side of the wall, together with one temperature sensing cable installed on the excavated side
172 for temperature compensation. In Panel 2, besides similar arrangements of the vertical strain sensing
173 cables, an additional temperature sensing cable was installed on the retained side. Furthermore, two
174 strain sensing cables were attached to the reinforcement cage in a zigzag pattern for Panel 2 and Panel
175 3 to monitor the hoop strains at various levels between -26.7 mPD and -35.0 mPD. In Panel 3, one set
176 of temperature and strain sensing cable was installed to monitor the hoop strains between -26.9 mPD
177 and -31.5 mPD on the retained side, while one LIOS cable (containing both strain and temperature
178 sensing cables) was installed on the excavated side. For hoop strain monitoring in Panel 2 and Panel 3,
179 there were a total of six and four horizontal sections on each side, respectively, with a length of about
180 2.0 m each. A pre-tension of 1000 $\mu\epsilon$ was applied to the strain sensing cables to facilitate measurements
181 of compressive strains through reductions in tension (Schwamb, 2014; ASTM F3079-14, 2014).

182

183 Data Processing

184 *Temperature compensation*

185 In this study, the temperature was determined by stress-free cables. There is a lump coefficient $c_{T,f} =$
186 $c_T + \alpha_c c_\varepsilon$ for the stress-free cable (ASTM F3079-14, 2014). α_c is the coefficient of linear thermal
187 expansion of the cable coatings and tight buffer. The values of $c_{T,f}$ of the NanZee and LIOS temperature
188 sensing cables were obtained by water bath tests and found to be -4.38 GHz/K and -1.43 GHz/K,
189 respectively. Therefore, the temperature can be evaluated by:

$$\Delta T = \frac{\Delta v_R}{c_{T,f}} \quad (2)$$

190 The measurements of strain sensing cables were affected by both mechanical strain and temperature
191 changes. Contributions from the two components should be differentiated during the post-processing of
192 raw data (Mohamad et al, 2011). The mechanical strain changes $\Delta\varepsilon_m$ of strain sensing cables include
193 excavation-induced and concrete thermal-induced strains, and can be determined by

$$\Delta\varepsilon_m = \frac{1}{c_\varepsilon} \Delta v_R - \frac{c_T}{c_\varepsilon} \Delta T \quad (3)$$

195 The excavation-induced mechanical strain $\Delta\varepsilon'_m$ can be determined by

$$\Delta\varepsilon'_m = \Delta\varepsilon_m - \alpha_{con} \Delta T \quad (4)$$

197 where ΔT is the temperature change measured by the temperature sensing cable (Eq. (2)), α_{con} is the
198 coefficient of linear thermal expansion of the concrete and is taken as $\alpha_{con} = 10 \mu\varepsilon/K$ (Browne, 1972).

199

200 *Evaluation of curvature and internal forces*

201 Assuming linear-elastic material behaviour for the reinforced concrete, the curvature and bending
202 moment in the concrete wall panel can be evaluated by

$$\kappa_{zz} = \frac{\varepsilon_{zz_e} - \varepsilon_{zz_r}}{L} \quad (5a)$$

$$\kappa_{\theta\theta} = \frac{\varepsilon_{\theta\theta_e} - \varepsilon_{\theta\theta_r}}{L} \quad (5b)$$

$$M_{zz} = \frac{Et^3}{12(1-\nu^2)}(\kappa_{zz} + \nu\kappa_{\theta\theta}) \quad (5c)$$

$$M_{\theta\theta} = \frac{Et^3}{12(1-\nu^2)}(\kappa_{\theta\theta} + \nu\kappa_{zz}) \quad (5d)$$

203 where κ_{zz} and $\kappa_{\theta\theta}$ represent the curvatures in vertical and circumferential directions, respectively;
 204 ε_{zz_e} and ε_{zz_r} are the measured vertical strains on the excavated side and retained side, respectively;
 205 $\varepsilon_{\theta\theta_e}$ and $\varepsilon_{\theta\theta_r}$ are the measured horizontal or circumferential strains on the excavated side and retained
 206 side, respectively; L is the horizontal distance between sensing cables on the retained and excavated
 207 sides, which was 1.27 m in Panel 1 and 1.35 m in Panels 2 and 3 according to the site installation records;
 208 M_{zz} and $M_{\theta\theta}$ are the vertical and circumferential bending moments; the Young's modulus, E , was
 209 taken as 19.4 GPa considering the reduction in stiffness arising from the tremie concreting process, and
 210 cracking and creep effects in the concrete according to CIRIA C760 recommendations (Gaba et al.
 211 2017); t is the thickness of the wall panel and is taken as 1.5 m; ν is the Poisson's ratio of the wall panel
 212 and is taken as 0.2. Positive values of curvature and bending moment indicate wall bending (convex)
 213 towards the excavation, as indicated in Fig. 5.

214

215 For Panel 1 of the cut-and-cover tunnel, M_{zz} is mainly contributed by κ_{zz} while $M_{\theta\theta}$ can be neglected
 216 considering the rectangular excavation geometry. For Panel 2 and Panel 3 within the circular cells, M_{zz}
 217 and $M_{\theta\theta}$ should include the contributions from both κ_{zz} and $\kappa_{\theta\theta}$. In this study, the DFOS installed in
 218 the vertical direction of Panel 1 and Panel 2 are able to obtain κ_{zz} induced by excavation. However,
 219 $\kappa_{\theta\theta}$ of Panel 2 and Panel 3 could only be determined at depths where hoop strains were measured, as
 220 indicated in Fig. 5(b). In that case, κ_{zz} instead of M_{zz} was discussed below for Panel 2.

221

222 The hoop forces F induced in Panel 2 and Panel 3 can be calculated by

$$\varepsilon_{zz} = \frac{\varepsilon_{zz_e} + \varepsilon_{zz_r}}{2} \quad (6a)$$

$$\varepsilon_{\theta\theta} = \frac{\varepsilon_{\theta\theta_e} + \varepsilon_{\theta\theta_r}}{2} \quad (6b)$$

$$F = \frac{Et}{1 - \nu^2} (\nu \varepsilon_{zz} + \varepsilon_{\theta\theta}) \quad (6c)$$

223 where ε_{zz} and $\varepsilon_{\theta\theta}$ represent the vertical and circumferential normal strains of the wall panel,
224 respectively. Positive values of strain and stress (and hence force) indicate tension. Since ε_{zz_e} and ε_{zz_r}
225 of Panel 3 were not measured during excavation, $M_{\theta\theta}$ and F of Panel 3 presented below did not
226 consider the contribution from the vertical direction.

227

228 Behaviour of the Diaphragm Wall Based on OFDR Data

229 Most of the fibre optic cables remained functional after the installation of diaphragm wall panels, except
230 that the temperature sensing cable at Panel 1 was damaged at the elevation of -5.7 mPD after the
231 concreting process (Fig. 5). As described in earlier sections, two bending strain sensing cables were
232 installed on each side of the wall panels for redundancy. Since the measurements were very similar
233 between the two cables on the same side, the following sections only present one set of data for each
234 side of the wall.

235

236 *Temperature changes*

237 The hydration reaction of concrete generates considerable amounts of heat, causing significant
238 temperature increase in the diaphragm wall panels after the concreting process. In this study, the
239 benchmark readings for all fibre optic cables were taken shortly after concreting of the corresponding
240 panels. Subsequent readings were compared against the benchmark to obtain strain and temperature
241 changes during excavation. Therefore, temperature reductions are expected from the readings as heat
242 was dissipated during concrete curing.

243

244 As indicated in Fig. 6(a), the temperature at Panel 1 decreased by an average of 6.3 K on the excavated
245 side during excavation, two months after concreting. The temperature changes on both sides of Panel 2
246 are shown in Figs. 6(b) and (c). The temperature reductions, especially those on the excavated sides,
247 were observed to be correlated to the excavation levels, and the temperature changes on the retained

248 side and excavated side were notably different even at the same excavation stage. The temperature
249 reduction reached 22.5 K on the excavated side, while the maximum reduction on the retained side was
250 only 15.0 K. A possible reason for the difference could be the higher efficiency in heat
251 convective loss from the concrete surface exposed to air compared to the heat conductive
252 loss from the concrete to the surrounding soils. The similar phenomenon was also reported by Liou
253 (1999), Kumagai et al. (1999) and Torisu et al. (2019). Therefore, it is important to conduct
254 independent temperature monitoring on both sides of the diaphragm wall for respective temperature
255 compensation using DFOS technique.

256

257 *Curvature and bending moment*

258 The temperature sensing cable in Panel 1 was damaged during construction. As a compromise, the
259 measurements at -5.0 mPD of that cable were used for temperature compensation for evaluation of
260 strains at Panel 1. Torisu et al. (2019) reported the temperature changes on the excavated
261 and retained sides of diaphragm wall panels with thickness of 1.2 m and depth of 48
262 m, and stated that the temperature difference between the two sides were negligible
263 after excavation, which was four months after the concreting process. In the current study,
264 although errors might be introduced by imperfect temperature compensation at Panel
265 1, the estimated strains are deemed to produce reasonable estimates of the general trends of curvature
266 in this panel at the final stage of excavation (Stage 7), which was reached nine months after concreting.
267

268 As shown in Fig. 7, the bending moment of Panel 1 was negligible at Stage 1, which indicated the first
269 pumping test and dewatering had little effect on the wall deformation. As the excavation progressed,
270 the maximum (positive) incremental bending moments occurred at depths that roughly coincided with

271 the excavation levels from Stages 2 to 7. It is worth noting that negative values of incremental bending
272 moments were observed at the levels of the slabs and preloaded steel struts from Stages 5 to 7.

273

274 The developments of vertical curvature κ_{zz} in Panel 2 are shown in Fig. 8. At Stage 1, no excavation
275 work was conducted in Cell 2 except dewatering, although excavation of the adjacent cut-and-cover
276 tunnel section had reached -10.0 mPD. The incremental curvatures were negligible at this stage. At
277 Stages 2 and 3, the excavation reached -11.0 mPD and -16.0 mPD in Cell 2, respectively. An RC beam
278 located at -13.5 mPD between Cell 2 and Cell 1 was constructed at the end of Stage 3. The positive
279 incremental curvatures were observed above these two excavation levels. The positive incremental
280 curvatures at Stages 4, 5 and 6 were significantly smaller than that at Stage 3, although the excavation
281 progressed from -16.0 mPD to the final stage at -32.6 mPD. This could be attributed to the developments
282 of hoop actions (to be elaborated later), together with the additional support provided by the RC beam.
283 In addition, the eastern crosswall between the two cells remained at -25.0 mPD, which resisted the wall
284 deformation at Stage 6.

285

286 *Comparison of DFOS data and inclinometer data*

287 In this section, the DFOS data are compared with inclinometer measurements regarding the wall
288 curvatures in the vertical direction and lateral wall deflections. The inclinometer measurements at a
289 panel opposite to Panel 1 (south side of cut-and-cover tunnel section) were used to compare with the
290 fibre optics data since there was no inclinometer installed in Panel 1. On the contrary, inclinometer
291 measurements were available at Panel 2 for direct comparisons with the DFOS technology. Based on
292 Eq. (5a), the wall curvature can be directly estimated using the DFOS strain measurements from both
293 sides of the panel. To estimate the wall deflection, double integration of the curvature requires two
294 boundary conditions to be determined or assumed (Schwamb et al., 2016). In this study, the deflection
295 at the wall bottom was assumed to be zero (same assumption for interpretation of inclinometer data),
296 and the wall top deflection was assumed to be equal for DFOS and inclinometer data. It should be noted
297 that the wall curvature profiles deduced by inclinometer readings sometimes involve unreasonable

298 fluctuations when too few data points are used to determine the curvature. The phenomenon was
299 observed in this study and was also reported by other researchers (Briaud et al. 2000; Tan & Wang 2015;
300 Schwamb et al., 2016). To reduce data scattering and to capture the main trend of the wall curvature
301 profile measured by inclinometer, data points of inclinometers for curvature calculation were selected
302 with a depth interval (DI) of 2.5 m (original depth intervals of inclinometer readings were 0.5 m).

303

304 According to Fig. 9(a), both the fibre optic and inclinometer measurements showed that the maximum
305 accumulative curvature occurred near the final excavation level of the cut-and-cover tunnel section.
306 Negative values of curvature generally occur near the levels of slabs, with positive curvatures occurring
307 in between. The curvature profiles deduced from the two independent devices matched well at most
308 locations, except those values around -5.0 mPD and -45.0 mPD. As illustrated in Fig. 9(b), the
309 maximum deflections evaluated from the inclinometer data and the fibre optic data were both located
310 at the final excavation level, with magnitudes of about 42.6 mm and 38.5 mm, respectively. The
311 difference can be attributed to the fact that the DFOS and inclinometer were in different panels and the
312 geometry of the excavation was not exactly symmetric.

313

314 Figs. 10(a) and (b) present the accumulative curvature and wall deflection of Panel 2. The curvature
315 profile derived from inclinometer measurements fluctuated significantly, especially below the final
316 excavation level. On the contrary, the accumulative curvature profile calculated from the fibre optic
317 data was more reasonable with the maximum values occurring around the RC beam level. Meanwhile,
318 the locations of the maximum wall deflections obtained by two independent devices were similar with
319 a magnitude of about 13 mm. Although the final excavation level in the two cells was deeper than that
320 in the cut-and-cover tunnel, the deflections of Panel 2 were much smaller than those in Panel 1. This
321 highlighted the advantage of circular excavations where more effective deformation control can be
322 achieved with fewer lateral supports compared with excavation designs with conventional multi-
323 propped walls.

324

325 The DFOS data after downsampling, including depth intervals (DI) of 1.0 m and 2.5 m, are also shown
326 in Fig. 9(a) and Fig. 10(a). Downsampling from ‘DI 0.05’ to ‘DI 2.5’ reduced the data density and led
327 to smoother wall curvatures over depth, especially at the final excavation level of Panel 1. In this study,
328 the wall deflection was calculated using the DFOS data with a spatial resolution of 5 cm (DI 0.05),
329 which prevented it from being underestimated after double integration of the curvature, as indicated in
330 Fig. 9 (b) and Fig. 10 (b).

331

332 *Hoop force and circumferential bending moment*

333 The fibre optic cables were arranged in a zig-zag pattern on each side of Panel 2 and Panel 3 (Fig. 5),
334 which allowed the measurement of hoop strains at six different depths in Panel 2 and four different
335 depths in Panel 3, with a sensing length of 2.0 m in the horizontal direction. Temperature compensation
336 for the measurements of each depth was achieved by using the 1-m average temperature data at the
337 same depth of the temperature sensing cable. The hoop strain distributions along with sensing distance
338 on both sides of Panel 2 are shown in Figs. 11(a) and (b). Six hoop strain sensing zones could be clearly
339 identified. Contrary to the hoop strain measurements obtained by Schwamb et al. (2014) with a spatial
340 resolution of 1.0 m, the hoop strain measurements in this study showed more details, which arose from
341 the higher spatial resolution of 5 cm made possible by the OFDR technique.

342

343 To eliminate the possible boundary effects (Tan et al., 2021) near the two ends of the 2-m span and
344 possible sensing length variations during the DFOS installation, only the strains within the middle 1 m
345 of each span were averaged to represent the hoop strains at the corresponding depth. The development
346 of hoop strains at different depths of both sides throughout construction is shown in Figs. 11(c) and (d).
347 The compressive (negative) hoop strain between -26.7 mPD and -35.0 mPD of both sides gradually
348 increased with the excavation process, indicating that Panel 2 was under circumferential compression
349 throughout excavation.

350

351 The development of average hoop force and circumferential bending moment of Panel 2 is presented in
352 Figs. 12(a) and (b). After Stage 1, compressive hoop force and positive bending moment were observed
353 in Panel 2 due to the combined effects of the excavation in the adjacent cut-and-cover tunnel section
354 and the dewatering operations in the peanut-shaped shaft. The excavation work in the cells commenced
355 from Stage 2 and the excavation level reached -21.0 mPD at Stage 4. The compressive hoop forces and
356 circumferential bending moments at six monitoring positions increased synchronously with the
357 excavation, which indicated that Panel 2 was under eccentric compression. At Stage 5, the excavation
358 reached about -27.0 mPD and the western crosswall was demolished from -15.0 mPD to -27.0 mPD in
359 the meantime. Although the excavation was ongoing at this stage, both the compressive hoop force and
360 circumferential bending moment stayed almost constant at the start of Stage 5. These may be attributed
361 to the partial demolition of the western crosswall in this stage, which hampered the development of
362 hoop action and altered the path of load transfer around the individual panels constituting the peanut-
363 shaped structure. Some of the compressive hoop forces were therefore released in Panel 2 during this
364 construction stage, together with the circumferential bending moments. At Stage 6, the excavation
365 reached the final excavation level. The compressive hoop force increased again and eventually became
366 stable, while the circumferential bending moment generally remained stable. Figs. 12(c) and (d) show
367 the monitoring results at Panel 3, where the developments of compressive hoop forces and
368 circumferential bending moments before Stage 5 were consistent with those of Panel 2, but the internal
369 forces kept increasing during Stage 5. This indicated that the crosswall demolition did not have
370 significant impacts on Panel 3, which was located further away from the western crosswall.

371

372 Numerical Analysis on Development of Hoop Force and Circumferential Bending Moment

373 A series of numerical analyses have been performed to enhance the understanding on the behaviour of
374 diaphragm wall around the twin-circular cofferdam. The purpose of these is not to back-analyse the
375 system performance or calibrate material parameters. Instead, the goals of these simulations are twofold:
376 (i) to demonstrate the redistribution of hoop forces as the ‘circular’ geometry is broken up by the partial
377 demolition of crosswall; and (ii) to highlight the importance of hoop strain measurements in walls

378 supporting excavation using twin-circular or other multi-cell cofferdams, as they can be important
379 performance indicators of the effectiveness of lateral support system that are also related to
380 deformations of nearby ground and structures. The simulations presented in this study are performed
381 using the finite element modelling software PLAXIS 3D. The subsurface strata and model dimensions
382 are shown in Fig. 13(a). The diaphragm wall panels and slabs in the cut-and-cover tunnel section and
383 peanut-shaped cofferdam are modelled using isotropic elastic shell elements while the capping beams,
384 Y panels and steel walers are modelled using beam elements, as shown in Fig. 13(b). The preloading
385 forces of the two layers of steel struts are modelled as linearly distributed loads transferred to the walers,
386 with values of 1640 and 1460 kN/m (from site measurement), respectively. The loadings from nearby
387 existing facilities are also considered in the model. Tables 2 to 4 present the input parameters for the
388 numerical models, which are extracted from geotechnical investigation of the site and other published
389 studies on local soil properties (e.g., Ng et al., 2014). In total, four numerical models are generated to
390 investigate different scenarios. The benchmark model adopts parameters and modelling stages that
391 closely resemble the actual construction conditions, while three additional models are created for a
392 parametric study on the effects of partial demolition of western crosswall. Case 1 models the scenario
393 where the crosswall demolition does not take place; Case 2 involves demolition of a larger extent of the
394 wall (-4 to -15 mPD); Case 3 simulates the effects of reduced stiffness in the wall panels along the
395 circumferential direction, which may arise from panel misalignment, imperfect connections between
396 the panels or other construction defects. This is similar to a scenario described by Aye et al. (2014), on
397 the issue of deviation of wall alignment that would lead to additional eccentricity due to non-circularity
398 of the shaft.

399

400 In the benchmark case, two panels around Cell 2 are marked as 'L' and 'M', to indicate the leftmost
401 and middle panels in that section, as shown in Fig. 13(b). The development of internal forces at -26.7
402 mPD of these panels in the benchmark model are shown in Fig. 14. The partial demolition of the western
403 crosswall affects the development of hoop action around Cell 2, causing redistribution of hoop forces
404 and bending moments in the wall panels. In particular, significant release of the compressive hoop
405 forces in Panel 'L' is observed, while those in Panel 'M' are also mildly affected. The circumferential

406 bending moments in these two panels are also reduced during the process, with the effect attenuating
407 gradually with distance away from the western crosswall. The DFOS measurement data at -26.7 mPD
408 of Panel 2 are also presented in Fig. 14, which indicates that the numerical results generally capture the
409 trends of hoop force and circumferential bending moment developments in Panel 2, especially the hoop
410 force and bending moment release during Stage 5 of the construction. The discrepancies between the
411 measured data and numerical results can be partly attributed to non-uniform water levels and excavation
412 progress across the actual construction site which could not be fully captured in the numerical
413 simulations. In addition, the effect of the crosswall demolition on the hoop force and circumferential
414 bending moment of Panel 3 was insignificant in the benchmark model, which is consistent with the
415 DFOS measurements shown in Fig. 12(c) and (d).

416

417 Compared with the benchmark case, the hoop forces at Panel 'L' are about 20% larger in Case 1, as
418 shown in Figs. 15(a) and (c). This again indicates the effect of crosswall demolition (in benchmark
419 model) on the release of hoop force. As the hoop action develops more effectively in Case 1, the wall
420 deflections are approximately 10% smaller compared with the benchmark model (Figs. 15(b) and (d)).
421 On the contrary, Case 2 simulates a larger section of the crosswall being removed, which leads to the
422 release of hoop forces in a wider extent of the nearby Panel 'L'. Perhaps more importantly, the
423 deflection at that panel also increases by more than 20% at some locations. The more extreme scenario
424 modelled in Case 3 leads to even more significant reduction of hoop forces in the entire panel, while
425 the wall deflection increases by 40 to over 80% along the depth of the panel. In general, since circular
426 or multi-cell cofferdams rely on the hoop action in wall panels for overall stability, under-development
427 of such could result in excessive wall deflections and hence ground settlements in the vicinity. Therefore,
428 hoop strain monitoring based on DFOS would provide important indications or even early warning of
429 unexpected system performance.

430

431 Discussions

432 The DFOS used in this study revealed both the deflection profiles of individual diaphragm wall panels
433 around the shaft and the strains and bending moments developed in various directions as excavation
434 progressed. The measurements of hoop forces and circumferential bending moments are particularly
435 important for circular or multi-cell cofferdams which utilize hoop action as the main support mechanism
436 in lieu of steel struts as in rectangular cofferdams. In other words, monitoring of hoop action through
437 lateral strains in wall panels serves a similar purpose as strut force monitoring in multi-propped
438 excavations, as the development of support forces and nearby ground movements are often intertwined:
439 there had been previous cases where ground collapse shortly followed unexpected and sudden losses of
440 the measured support forces. High-resolution distributed strain sensing technique was not available in
441 the past, which hampered the implementation of lateral strain monitoring of concrete wall panels.
442 Following the success of this pilot study, future investigations on hoop strain developments could lead
443 to wider adoption of systematic guidelines of alarm thresholds of such for circular or multi-cell
444 cofferdams.

445

446 Based on the measurements and numerical results in this study, the instrumented panels for hoop force
447 monitoring can be selected according to three criteria. The first criterion is to identify and monitor wall
448 panels with the maximum hoop forces or circumferential bending moments induced by excavation,
449 according to numerical analyses in the design stage. The second one is to monitor the wall panel that
450 may be greatly impacted by construction activities such as local wall demolition, local surcharge, and
451 nearby excavations or tunnelling operations. In addition, the monitoring positions can be set where
452 significant eccentric stresses are expected in the circumferential direction, arising from the complex
453 multi-cellular geometries or cofferdams that are not perfectly circular in shape.

454

455 Conclusions

456 This paper investigates the response of a twin-circular, peanut-shaped cofferdam using distributed fibre
457 optic sensing technique with a high spatial resolution. This revealed the detailed developments in hoop
458 action in individual wall panel, including their hoop forces and circumferential bending moments,
459 during the complex construction process. The key findings are summarized as follows:

460 (a) The wall panels of the peanut-shaped cofferdam were under eccentric compression throughout
461 the excavation. Partial demolition of the crosswall influenced the hoop action and released some
462 of the compressive hoop forces and circumferential bending moments in wall panels. These
463 details are difficult to be captured using conventional instruments. More obvious hoop force
464 release is expected in wall panels near the location of wall demolition.

465 (b) Hoop strain monitoring based on DFOS for circular or multi-cell excavations can provide useful
466 information to validate the design assumptions or compare with design predictions. The
467 monitoring results also give indications of stress variations of the monitored wall panels due to
468 localised disturbance of the cofferdam during construction.

469 (c) Comparisons between the performances of Panel 1 and Panel 2 showed that smaller wall
470 deflections developed in the twin-circular cofferdam even though it supported a deeper
471 excavation with fewer lateral supports installed, as compared to the rectangular multi-propped
472 section. This demonstrates the effectiveness of utilizing hoop action to support the excavation.

473 (d) Temperature changes in the diaphragm wall were different between the excavated and retained
474 sides during excavation, especially shortly after concrete placement. This could be attributed to
475 the higher efficiency in heat convective loss from the surface exposure to air compared with
476 the heat conductive loss from the concrete surface to the surrounding soil strata. Therefore,
477 installation of temperature sensing cables on both sides of the wall is recommended if DFOS is
478 used for monitoring.

479 There are few reported field applications of DFOS techniques with high spatial resolution in
480 geotechnical monitoring. For certain geotechnical infrastructure, the monitoring accuracy might be
481 compromised or insufficient if the spatial resolution of measurements is low. Compared with

482 conventional discrete instruments or DFOS with low spatial resolution, the OFDR technology adopted
483 in this study can provide more details in performance monitoring. These details would facilitate the
484 analyses and enhance the understanding on the behaviour of geotechnical structures, including piles,
485 tunnels and other complicated structures with circular or elliptical geometries, where hoop force
486 development and the induced displacements are of great importance.

487

488 Data Availability Statement

489 All monitoring data and numerical results that support the findings of this study are available from the
490 corresponding author upon reasonable request.

491 Acknowledgments

492 This paper is published with the permission of the Director of Civil Engineering and Development, the
493 Head of the Geotechnical Engineering Office, and the Project Manager of the East Development Office
494 of the Government of the Hong Kong SAR, China. The work presented in this paper is supported by
495 Research Impact Fund (RIF) project (R5037-18), a Theme-based Research Scheme Fund (TRS) project
496 (T22-502/18-R), and four General Research Fund (GRF) projects (PolyU 152179/18E; PolyU
497 152130/19E; PolyU 152100/20E; 15222021) from Research Grants Council (RGC) of Hong Kong
498 Special Administrative Region Government of China. The authors also acknowledge the financial
499 supports from grants (CD82 and CD7A) from Research Institute for Land and Space, and grants (ZDBS,
500 BD8U) from The Hong Kong Polytechnic University.

501

502

503 References

504

505 ASTM. 2014. Standard practice for use of distributed optical fiber sensing systems for monitoring the
506 impact of ground movements during tunnel and utility construction on existing underground
507 utilities. F3079-14, West Conshohocken, PA.

508 Aye, T. T., Tong, M. S. Y., Yi, K. H., and Arunasoruban, E. 2014. "Design and construction of large
509 diameter circular shafts." In *Underground Singapore*. Tunnelling and Underground
510 Construction Society.

511 Browne, R. D. 1972. "Thermal movement in concrete." *Concrete* 6 (11): 51-53.

512 Briaud, J. L., Nicholson, P., and Lee, J. 2000. "Behavior of full-scale VERT wall in sand." *J. Geotech.*
513 *Geoenviron. Engng.* 126 (9): 808-818. [https://doi.org/10.1061/\(ASCE\)1090-0241\(2000\)126:9\(808\)](https://doi.org/10.1061/(ASCE)1090-0241(2000)126:9(808))

515 Ding, Z., Wang, C., Liu, K., Jiang, J., Yang, D., Pan, G., ..., and Liu, T. 2018. "Distributed optical fiber
516 sensors based on optical frequency domain reflectometry: A review." *Sensors* 18 (4): 1072.
517 <https://doi.org/10.3390/s18041072>

518 Gomes, A. T., Cardoso, A. S., Sousa, J.A., Andrade, J.C., and Campanhã, C. A. 2008. "Design and
519 behavior of Salgueiros station for Porto metro." *6th International conference on case histories
520 in geotechnical engineering*. 1-12. Scholars' Mine, Missouri University of Science and
521 Technology. <https://scholarsmine.mst.edu/icchge/6icchge/session08c/6>

522 Gaba, A., Hardy, S., Doughty, L., Powrie, W., and Selemetas, D. 2017. *Guidance on embedded
523 retaining wall design (C760)*. London: Construction Industry Research and Information
524 Association.

525 Kumagai, T., Ariizumi, K., and Kashiwagi, A. 1999. "Behaviour and analysis of a large-scale
526 cylindrical earth retaining structure." *Soils Found.* 39 (3): 13-26.
527 https://doi.org/10.3208/sandf.39.3_13

528 Liou, D. D. 1999. "Thermal effects in large-sized diaphragm wall." *J. Perform. Constr. Facil.* 13 (1):
529 17-21. [https://doi.org/10.1061/\(ASCE\)0887-3828\(1999\)13:1\(17\)](https://doi.org/10.1061/(ASCE)0887-3828(1999)13:1(17))

530 Leviton, D. B., and Frey, B. J. 2006. "Temperature-dependent absolute refractive index measurements
531 of synthetic fused silica." In Vol. 6273 of *Optomechanical technologies for astronomy, 800-
532 810*. Bellingham, WA: Society of Photo-Optical Instrumentation Engineers.

533 Li, Z., Soga, K., and Kechavarzi, C. 2018. "Distributed fibre optic sensing of a deep excavation adjacent
534 to pre-existing tunnels." *Géotechnique Letters* 8 (3): 171-177.
535 <https://doi.org/10.1680/jgele.18.00031>

536 Mohamad, H., Soga, K., Pellew, A., and Bennett, P. J. 2011. "Performance monitoring of a secant-piled
537 wall using distributed fiber optic strain sensing." *J. Geotech. Geoenviron. Engng.* 137 (12):
538 1236-1243. [https://doi.org/10.1061/\(ASCE\)GT.1943-5606.0000543](https://doi.org/10.1061/(ASCE)GT.1943-5606.0000543)

539 Ng, C. W. W., Leung, A. K., Kwok, S. S. K., and Yip, F. H. T. 2014. "Effects of stiffness nonlinearity
540 on E' standard penetration test N correlations for analysing wall deflections in Hong Kong
541 excavations." *HKIE Transactions* 21 (1): 35-49.
542 <https://doi.org/10.1080/1023697X.2014.884968>

543 Nejjar, K., Dias, D., Cuira, F., Chapron, G., and Lebissonnais, H. 2021. "Experimental study of the
544 performance of a 32 m deep excavation in the suburbs of Paris." *Géotechnique* 1-11.
545 <https://doi.org/10.1680/jgeot.21.00017>

546 Parashar, S., Mitchell, R., Hee, M. W., Sanmugnathan, D., and Nicholson, G. 2007. "Performance
547 monitoring of deep shafts at Changi WRP project, Singapore." In *Proc. 7th FMGM 2007: Field
548 Measurements in Geomechanics*, 1-12. Reston, VA: ASCE.

549 Pelecanos, L., Soga, K., Chung, M. P., Ouyang, Y., Kwan, V., Kechavarzi, C., and Nicholson, D. 2017.
550 "Distributed fibre-optic monitoring of an Osterberg-cell pile test in London." *Géotechnique
551 Letters* 7 (2): 152-160. <https://doi.org/10.1680/jgele.16.00081>

552 Pei, H., Yin, J., and Wang, Z. 2019. "Monitoring and analysis of cast-in-place concrete bored piles
553 adjacent to deep excavation by using BOTDA sensing technology". *J. Mod. Optic.* 66 (7): 703-
554 709. <https://doi.org/10.1080/09500340.2018.1559948>

555 Schwamb, T., Soga, K., Mair, R. J., Elshafie, M. Z. E. B., Sutherland, R., Boquet, C., and Greenwood,
556 J. 2014. "Fibre optic monitoring of a deep circular excavation." *Proc. Instn Civ. Engrs -
557 Geotech. Engng.* 167 (2): 144-154. <https://doi.org/10.1680/geng.13.00036>

558 Schwamb, T. 2014. "Performance monitoring and numerical modelling of a deep circular excavation."
559 Ph.D. thesis, Dept. of Engineering, Univ. of Cambridge.

560 Schwamb, T., Elshafie, M. Z. E. B., Soga, K., and Mair, R. J. 2016. "Considerations for monitoring of
561 deep circular excavations." *Proc. Instn Civ. Engrs - Geotech. Engng.* 169 (6): 477-493.
562 <https://doi.org/10.1680/jgeen.15.00063>

563 Schwob, A., Cagnat, E., Chen, S., Chan, A. W., and Ng, C. C. 2019. "Tuen Mun–Chek Lap Kok Link:
564 an outstanding subsea tunnel project in Hong Kong." *Proc. Instn. Civ. Engrs – Civ. Engng.* 173
565 (5): 33-40. Thomas Telford Ltd. <https://doi.org/10.1680/jcien.19.00027>

566 Song, H., Pei, H., and Zhu, H. 2021. "Monitoring of tunnel excavation based on the fiber Bragg grating
567 sensing technology." *Measurement* 169: 108334.
568 <https://doi.org/10.1016/j.measurement.2020.108334>

569 Sui, Y., Cheng, X., and Wei, J. 2021. "Distributed fibre optic monitoring of damaged lining in double-
570 arch tunnel and analysis of its deformation mode." *Tunnelling Underground Space Technol.*
571 110: 103812. <https://doi.org/10.1016/j.tust.2021.103812>

572 Tan, Y., and Wang, D. 2013. "Characteristics of a large-scale deep foundation pit excavated by the
573 central-island technique in Shanghai Soft Clay. I: bottom-up construction of the central
574 cylindrical shaft." *J. Geotech. Geoenviron. Engng.* 139 (11): 1875-1893.
575 [https://doi.org/10.1061/\(ASCE\)GT.1943-5606.0000928](https://doi.org/10.1061/(ASCE)GT.1943-5606.0000928)

576 Tan, Y., and Wang, D. 2015. "Structural behaviors of large underground earth-retaining systems in
577 Shanghai. I: Unpropped circular diaphragm wall." *J. Perform. Constr. Facil.* 29 (2): 04014058.
578 [https://doi.org/10.1061/\(ASCE\)CF.1943-5509.0000521](https://doi.org/10.1061/(ASCE)CF.1943-5509.0000521)

579 Torisu, S. S., Faustin, N. E., Elshafie, M. Z. E. B., Black, M., Soga, K., and Mair, R. J. 2019.
580 "Monitoring of Shaft Excavations in Clay." *In Proc., Int. Conf. on Smart Infrastructure and*
581 *Construction 2019 (ICSIC) Driving Data-Informed Decision-Making, 655–664. London:*
582 *Institution of Civil Engineers.*

583 Tan, X., Bao, Y., Zhang, Q., Nassif, H., and Chen, G. 2021. "Strain transfer effect in distributed fiber
584 optic sensors under an arbitrary field." *Automat. Constr.* 124: 103597.
585 <https://doi.org/10.1016/j.autcon.2021.103597>

586 Wang, F., Zhang, D. M., Zhu, H. H., Huang, H. W., and Yin, J. H. 2013. "Impact of overhead excavation
587 on an existing shield tunnel: field monitoring and a full 3D finite element analysis." *Comput.*
588 *Mater. Con.* 34 (1): 63-81.

589 Wu, J., Liu, H., Yang, P., Tang, B., and Wei, G. 2020. "Quantitative strain measurement and crack
590 opening estimate in concrete structures based on OFDR technology." *Opt. Fiber Technol.* 60:
591 102354. <https://doi.org/10.1016/j.yofte.2020.102354>

592 Zhu, H. H., Wang, D. Y., Shi, B., Wang, X., and Wei, G. Q. 2022. "Performance monitoring of a curved
593 shield tunnel during adjacent excavations using a fiber optic nervous sensing system."
594 *Tunnelling Underground Space Technol.* 124: 104483.
595 <https://doi.org/10.1016/j.tust.2022.104483>

596

Table 1. Summary of case studies of excavation monitoring using fibre optic sensing

Structure	Monitoring parameters	Technique	Site location	Installation method	Reference
Secant-piled wall	Strain and temperature	BOTDR	London, UK	Embedded in the secant-piled wall	Mohamad et al. (2011)
Existing tunnel	Tunnel displacement	FBG	Shanghai, China	Adhered to the PVC tube by epoxy resin	Wang et al. (2013)
Diaphragm wall	Bending and circumferential hoop strains	BOTDR	London, UK	Embedded in the wall panels	Schwamb et al. (2014)
Diaphragm wall	Strains at the soil side and the excavation side	BOTDR	London, UK	Embedded in the wall panels	Li et al. (2018)
Diaphragm wall	Bending and thermal strains	BOTDR	London, UK	Embedded in the wall panels	Torisu et al. (2019)
Bored pile	Strain and temperature	BOTDA	Hong Kong, China	Embedded in the piles	Pei et al. (2019)
Gypsum pile	Soil deformation	FBG	Model test	Attached to the piles	Song et al. (2021)
Tunnel linings	Longitudinal and circumferential strains	BOFDA	Suzhou, China	Point-to-point fixing using steel clamps	Zhu et al. (2022)

598 BOTDR: Brillouin optical time-domain reflectometry; FBG: Fibre Bragg grating; BOTDA: Brillouin optical time domain analysis; BOFDA: Brillouin optical
599 frequency domain analysis.

600

601

Table 2. The geotechnical parameters of strata in the design report

Stratum	γ : kN/m ³	SPT-N	E : MPa	c : kPa	ϕ : degrees	c_u : kPa	E_u : MPa
Fill	19.0	10	15.0	0.0	33.0	/	/
MD	19.0	4	6.0	0.0	28.0	20.0	10.0
All	19.0	18	27.0	0.0	36.0	/	/
		$2.75 \times (D - 22) + 18$	$4.125 \times (D - 22) + 27$				
CDG	19.0	$0.7 + 1.62D$	150.0	5.0	38.0	/	/

602 Note: D = depth below ground level; and SPT-N = N-value of the standard penetration test.

603

604

Table 3. Input geotechnical parameters


Stratum	Models	γ : kN/m ³	E : MPa	ν	c'_{ref} : kPa	ϕ' : degrees	E_{50}^{ref} : MPa	E_{oed}^{ref} : MPa	E_{ur}^{ref} : MPa	m	p^{ref} : kPa	$\gamma_{0.7}$: %	G_0^{ref} : MPa
Fill	HSS	19.0	/	/	0.1	32.0	25.0	20.0	75.0	0.5	27.0	0.0012	105.0
MD	HS	19.0	/	/	0.1	28.0	7.8	13.5	23.4	0.5	50.0	/	/
ALL	HS	19.0	/	/	0.1	36.0	24.0	24.0	75.0	1.0	200.0	/	/
CDG	HSS	19.0	/	/	0.1	35.0	40.0	32.0	120.0	0.5	30.0	0.0016	98.0
Bedrock	LE	24.0	5000.0	0.2	/	/	/	/	/	/	/	/	/

605 MD: marine deposit; All: alluvium (sand); CDG: completely decomposed granite.
606 HS: Hardening Soil model; HSS: Hardening Soil model with small-strain stiffness; LE: Linear elastic.
607


608 **Table 4.** Input structure parameters

Structures	t : m	γ : kN/m ³	E : GPa	ν	A : m ²
Capping beam	/	6.0*	18.5	/	6.0
RC beam	/	24.5	21.0	/	5.0
Y-panel	/	6.0*	20.2	/	15.6
Diaphragm wall	1.5	6.0*	19.4	0.2	/
Crosswall	1.5	6.0*	19.4	0.2	/
Slab 1~ Slab 4	1.5	24.5	18.5	0.2	/
Base slab	2.0	24.5	18.5	0.2	/
Steel waler	/	78.0	210.0	/	0.07

609 *To accurately reflect the stress experienced by the soil beneath concrete structures,
610 the unit weight of the concrete structures was reduced by the weight of the soil.



(a)




mPD: m Hong Kong Principal Datum
 MD: Marine Deposit
 ALL: Alluvium
 CDG: Completely Decomposed Granite


Section A-A

(b)


Fig. 1. (a) Sketch of the cofferdam with instrumented panels; (b) cross-section and ground conditions of the cofferdam



(a)



(b)



(c)

Fig. 2. Construction sequences of (a) the cut-and-cover tunnel section and (b) the twin-circular cofferdam; (c) site photo after excavation




Fig. 3. Working principle of the OFDR




Fig. 4. Fibre optic cables adopted in the wall monitoring: (a) steel strand-reinforced cable, (b) loose tube cable, and (c) LIOS cable




Fig. 5. Cable arrangements in three diaphragm wall panels and direction indication of the internal forces: (a) Panel 1; (b) Panel 2 and Panel 3




Fig. 6. Temperature changes of wall panels: (a) on the excavated side of Panel 1; (b) on the retained side of Panel 2; (c) on the excavated side of Panel 2




Fig. 7. Curvature and bending moment development in Panel 1: (a) Stage 1 ~ Stage 2; (b) Stage 3 ~ Stage 4; (c) Stage 5 ~ Stage 7 (EL: excavation level)




Fig. 8. Curvature development in Panel 2: (a) Stage 1 ~ Stage 2; (b) Stage 3 ~ Stage 4; (c) Stage 5 ~ Stage 6 (EL: excavation level)




Fig. 9. Comparison of DFOS data and inclinometer results in Panel 1




Fig. 10. Comparison of DFOS data and inclinometer results in Panel 2







Fig. 11. Hoop strain measurements of DFOS in Panel 2: strain distribution along with sensing distance (a) on the retained side and (b) on the excavated side; strain development during excavation (c) on the retained side and (d) on the excavated side



(a)



(b)



(c)






Fig. 12. Internal forces development: (a) hoop forces in Panel 2; (b) circumferential bending moments in Panel 2; (c) hoop forces in Panel 3; (d) circumferential bending moments in Panel 3




(a)




(b)

Fig. 13. Overview of the PLAXIS model: (a) stratum and dimensions; (b) structure deformation and data output positions




(a)




(b)


Fig. 14. Internal forces development in the benchmark model: (a) hoop force; (b) circumferential bending moment




(a)



(b)



(c)



(d)

0 **Fig. 15.** Results of four numerical cases at the final stage: (a) hoop force; (b) wall deflection, and
 1 difference in (c) hoop force; (d) wall deflection compared to the benchmark model

2

3