

# Modelling the critical risk factors for modular integrated construction projects

Ibrahim Yahaya Wuni <sup>a,\*</sup>, Geoffrey Qiping Shen<sup>a</sup>, Robert Osei-Kyei <sup>b</sup>, Stephen Agyeman-Yeboah<sup>c</sup>

<sup>a</sup> Department of Building and Real Estate, The Hong Kong Polytechnic University, 11 Yuk Choi Road, Kowloon, Hong Kong

<sup>b</sup> School of Computing Engineering and Mathematics, Western Sydney University, Sydney, Australia

<sup>c</sup> Department of Land Economy, Kwame Nkrumah University of Science and Technology, Kumasi, Ghana  
Corresponding Author Email\*: [ibrahim.wuni@connect.polyu.hk](mailto:ibrahim.wuni@connect.polyu.hk)

## Abstract

For many types of projects, modular integrated construction (MiC) is increasingly becoming a preferred method of construction. However, MiC projects are associated with unique risk factors different from those of the traditional construction projects. Thus, it is imperative to conduct a bespoke assessment of the risk factors for MiC projects. This research modelled 29 critical risk factors (CRFs) associated with MiC projects. Quantitative data on the relative significance of CRFs were collected from international MiC experts using structured questionnaires. A principal component analysis generated 4 principal risk factors (PRFs) for MiC projects comprising stakeholder and supply chain risks, design and capabilities risks, financing risks, and regulatory risks. A fuzzy synthetic modelling of the CRFs revealed that the 4 PRFs were significant but with varied impact on MiC projects. This research constitutes the first exclusive quantitative modelling of MiC risk factors with useful practical and theoretical implications. Practically, the research has identified and prioritized the CRFs associated with MiC projects and may serve as a risk evaluation decision support in MiC project planning and implementation. Theoretically, the results contribute to the checklists of CRFs for MiC projects which may form the basis for future studies on the risks of MiC projects.

**Keywords:** fuzzy synthetic evaluation; modular integrated construction; risk analysis; risk factors

**Please Cite As:** Wuni, I.Y., Shen, G.Q., Osei-Kyei, R. and Agyeman-Yeboah, S. (2020), "Modelling the critical risk factors for modular integrated construction projects", International Journal of Construction Management, Taylor & Francis, Vol. Early Cite, pp. 1–14.

1 **Introduction**

2 During the end of the 20<sup>th</sup> Century, the Egan (1998) Report demonstrated that the cost, time,  
3 quality, productivity, customer satisfaction, and environmental performance of projects engineered  
4 from the traditional stick-built construction (TSC) approach were falling short of desired  
5 requirement and sustainability indicators. These ill-performances were traced to the processes and  
6 end-products of the TSC approach. Off-site production (OSP) was put forward to address the  
7 shortfalls in the construction sector (Goulding *et al.* 2015). Modular integrated construction (MiC)  
8 is a disruptively-innovative OSP business model where prefabricated volumetric modules (building  
9 components) are engineered in an off-site manufacturing plant, trucked to the job-site in section,  
10 set in place with cranes, and systematically installed to generate a complete building (Wuni and  
11 Shen 2019a, 2019b, 2020).

12 Where circumstances merit, and favourable conditions prevail, the effective implementation of  
13 MiC shortens construction time, improves working environment & site safety, results in high  
14 construction quality, reduces construction dust & noise nuisance, minimizes construction waste,  
15 improves construction waste management, and improves management of the construction process  
16 (Construction Industry Council 2018). However, the disruptive nature of the processes involved  
17 in MiC engenders unique events and conditions which could compromise the success of its  
18 projects. As a result, MiC is associated with several risk events and factors. For instance, late  
19 design freeze, schedule delays, and components' installation errors could be counterproductive to  
20 the widely reported time and quality benefits of MiC (Velamat 2012, Wuni *et al.* 2019). Poor  
21 coordination and management of downstream segments of the MiC supply chain could  
22 significantly compromise upstream supply chain events (Wuni and Shen 2019c). Poor  
23 coordination of cross-border transportation of modules could significantly increase construction  
24 cost (Pan and Hon 2018).

25 Considering that risk abound in MiC projects, effective management of the associated risks  
26 constitutes a critical success factor (Choi *et al.* 2016). However, risk management involves several  
27 stages, including risk identification, evaluation, prioritization, minimization, monitoring, and  
28 control (Project Management Institute 2017). The first three stages are critical because risks events  
29 are numerous in MiC projects, but not all the risk factors are critical. Again, resources are limited,  
30 which instructs the need to identify, assess and highlight the critical risk factors to be managed

1 since they constitute the greatest threat to project success. However, existing MiC risks studies  
2 have been region-specific and primarily focused on schedule risks (Li *et al.* 2016, Li, Hong, *et al.*  
3 2018), stakeholder risks (Luo *et al.* 2015, 2019), cost and investment risk factors (Li *et al.* 2013),  
4 risks of work-related musculoskeletal disorders (Kim *et al.* 2011, 2012) and risk of dimensional  
5 and geometric variabilities (Shahtaheri *et al.* 2017, Enshassi *et al.* 2019).

6 As a result, there is no existing study which has identified, evaluated, and prioritized risk factors  
7 in the application of MiC, drawing on international lessons and experiences. Therefore, this  
8 research conducts a quantitative assessment and modelling of the risk factors associated with the  
9 implementation of MiC projects. To achieve this, the following specific research questions warrant  
10 critical consideration:

11 *RQ1.* What are the critical risks factors associated with MiC projects?

12 *RQ2.* How can these critical risks factors be quantitatively assessed?

13 This paper is situated within a broader research project which seeks to develop a best practice  
14 framework for implementing MiC projects. The output of the quantitative evaluation and  
15 benchmarking of the risk factors have practical and theoretical implications. Theoretically, the  
16 research will establish the first generalized risk register for MiC projects and contributes to the  
17 theoretical checklists of risk factors associated with the technology. Practically, the research will  
18 highlight the critical risk factors that should be prioritized in MiC projects implementation to  
19 improve success.

20 ***Point of departure***

21 Prior researches recognized the existence of risk factors in the implementation of MiC projects. Li  
22 *et al.* (2013) identified and assessed the impacts of risk factors on the cost and time performances  
23 of MiC projects in Canada using Analytical Hierarchy Process and Simulation. This study was  
24 useful but focused solely on the factors which affect time and cost of MiC projects in the context  
25 of Canada. The region-specific and narrow nature of the risk factors renders the study less useful  
26 to other countries with different construction climates and dynamics. Luo *et al.* (2015) identified  
27 and evaluated the risk factors that inhibit the adoption of MiC in China. Although useful, this study  
28 focused on the risk barriers to the adoption of MiC rather than the risk factors associated with the  
29 implementation of MiC projects. Again, the region-specific nature of the study renders it less  
30 useful to countries with different construction climates and industry dynamics.

1 Similarly, Li et al. (2016) assessed the schedule risks of residential MiC projects in Hong Kong  
2 using social network analysis whereas Li et al. (2017) modelled the schedule risk of residential  
3 MiC in the context of Hong Kong using systems dynamics. These studies were robust and useful,  
4 but they constituted scoping assessments of the risks associated with MiC projects. Subsequently,  
5 Li et al. (2018) modelled the schedule risk events in MiC projects using a hybrid of systems  
6 dynamics and discrete event simulation whereas Lee and Kim (2017) evaluated the risk factors  
7 that account for cost increase in MiC projects in Korea. These studies were scoping in nature and  
8 conducted in the context of Hong Kong and Korea, respectively. This limits the applicability of  
9 their results in other contexts since they did draw on international experts' opinions and data.

10 Luo et al. (2019) recently examined the stakeholder risks associated with MiC projects and  
11 explored the interactions of the risk events. However, it was conducted in the context of Hong  
12 Kong. More recently, Wuni et al. (2019) conducted a systematic review of studies on the risks of  
13 MiC and established a theoretical checklist of the risk factors associated with MiC Projects.  
14 However, the factors were ranked using the frequency of occurrences rather than the experiences  
15 and knowledge of international experts. Therefore, existing MiC risks literature do not include an  
16 empirical assessment of the generic risk factors associated with the implementation of MiC and  
17 drawing on the opinions of international experts. Thus, this research makes a unique contribution  
18 to the extant literature and constitutes a natural extension of the works of Wuni et al. (2019)  
19 through a quantitative evaluation of the critical risk factors associated with the implementation of  
20 MiC projects.

## 21 **Modular integrated construction**

22 MiC is a disruptively-innovative construction approach that changes the way projects are planned,  
23 designed, engineered, constructed, and management in the construction engineering and  
24 management (CEM) domain. The Construction Industry Council (2018) defined MiC as an  
25 innovative construction technology where “free-standing integrated modules (completed with  
26 finishes, fixtures, and fittings) are manufactured and assembled in a factory”, transported to the  
27 jobsite in sections and finally installed to generate liveable space. The prefabricated prefinished  
28 volumetric modules are manufactured in a workshop, partly assembled in the factory and then  
29 trucked in sections to the construction for final installation (Wuni *et al.* 2019). This makes the  
30 business model of MiC unique and individuates it from the traditional construction approach. MiC

1 draws primarily on the concepts of modularity, modularization, lean production, and Design for  
2 Manufacture and Assembly, DfMA (Construction Industry Council 2018, Pan and Hon 2018).

3 The construction process involves distinct but interdependent stages of project design, statutory  
4 approvals, manufacturing of the modules, transportation of the modules to site, and on-site  
5 installation of the modules (Construction Industry Council 2018). The modules are designed based  
6 on local codes and engineering specifications (Hwang *et al.* 2018b). This stage often requires the  
7 early engagement of module fabricator, supplier, local contractor, and the client (Construction  
8 Industry Council 2018). This facilitates early completion and freezing of the design for subsequent  
9 stages to commence. Thus, late design freeze becomes a source of risks in the MiC supply chain  
10 (Wuni *et al.* 2019). The statutory approval stage is required to ensure that the design complies with  
11 building codes and regulations.

12 During the production stage, Hwang *et al.* (2018) noted that the fabrication method must be an  
13 accredited one to reduce dimensional and geometric variabilities. Before mass production, mock-  
14 ups, and prototypes of each type of modular component are fabricated, inspected, and tested  
15 (Construction Industry Council 2018). Trial assembly involving stacking of the modules is  
16 conducted in the factory to ascertain the ease of assembly at the job site. Since this stage proceeds  
17 the statutory approval, construction trades such as piling, foundation works, and external  
18 underground utility works are concurrently executed on the job-site. This shortens the construction  
19 time in MiC projects (Wuni *et al.* 2019). The modules are produced based on transport restrictions  
20 regarding masses and sizes. The produced modules may be transported to the job-site directly for  
21 installation, or they may be stored in a temporary location. The latter is known as buffering.

22 Finally, the modules are set in place with cranes and joined together to form the structure. Once  
23 the modules are firmly stacked together to form the volumetric units, both temporary and  
24 permanent waterproofing are executed. The prefabricated volumetric modules are connected to other  
25 modules to form the modular building. The products of these processes are considered as  
26 industrialized building systems where the same design details and engineering specification could  
27 result in the construction of highly diversified and individualized buildings which can meet the  
28 requirements of different clients and inhabitants (Richard 2005). These building systems are  
29 flexible, demountable, and industrialized (Richard 2006) and can meet the multigenerational  
30 housing requirement. According to the Construction Industry Council (2018), the three forms of

1 MiC include reinforced concrete modules, steel frame modules, and hybrid modules based on  
2 construction materials.

3 However, some critical processes must be given due consideration in the supply chain of MiC.  
4 First, allowance and forgivable tolerance levels must be duly considered in the design and  
5 production of modules. This is because dimensional and geometric variabilities may trigger  
6 expensive rectification of errors and site-fit reworks (Shahtaheri *et al.* 2017). Second, the modules  
7 are often designed to be used specifically in an MiC project. Thus, the quantities of each type of  
8 module must precisely match the total of that module required to complete the project. This is  
9 because the inventory must return to zero on completion of the project to avoid wastage. Third, in  
10 case there will be an upstream supply of the modules for hedging, enough storage space must be  
11 created on-site or close to the site to temporarily accommodate the modules. The hedging is quite  
12 crucial because shortage of the modular components could halt the entire installation process and  
13 increase the cost of hired equipment and machinery (Wuni and Shen 2019c, Wuni *et al.* 2019).  
14 These and other critical events must be carefully considered because the impact of their (mis)  
15 occurrence could be counterproductive to the benefits of MiC projects.

## 16 **Research design and approach**

17 This section describes the systematic procedures and techniques deployed to investigate the  
18 research problem. The study is situated within a positivist paradigm and adopts a quantitative  
19 research design to identify and assess the risk factors in the implementation of MiC projects. The  
20 research paradigm and design adopted instructs the use of quantitative data and analytical tools.  
21 Figure 1 shows the methodological framework of the research.

## 22 ***Prior literature and pilot study***

23 Before the questionnaire survey, the research developed risk factor register to be used to conduct  
24 the survey. Although a comprehensive review of the literature and content analysis is required to  
25 establish a checklist of the risk factors, the research constitutes an extension of the recent works  
26 of Wuni et al. (2019). The researchers conducted a systematic review of the extant literature on  
27 the risks of MiC and establish a generic list of risk factors for MiC projects. The current study  
28 adopted the checklists and conducted a pilot survey to ascertain their relevance to the different  
29 regions around the world. Three experts with rich industrial and research experience in MiC from  
30 Hong Kong and Australia were asked to examine the checklist to validate their relevance. The

1 experts confirmed the adequacy and relevance of the risk factors to many MiC project types and  
 2 territories. Table 1 shows the 29 risk factors used to conduct the survey.


3 **Table 1.** Risk factors in the implementation of MiC projects (Wuni *et al.* 2019)

<b>Serial No.</b>	<b>Risk factors</b>
RF1	Stakeholder fragmentation and management complexity
RF2	Higher initial capital cost
RF3	Poor supply chain integration and disturbances
RF4	Delays in delivery of modules to the site
RF5	Poor government support and regulations
RF6	Lack of MiC design codes and standards
RF7	Defective design and change order
RF8	Supply chain information gap and inconsistency
RF9	Inefficient scheduling
RF10	Limited MiC expertise and experience
RF11	Shortage of modular components
RF12	Complex interfacing between systems
RF13	Weather disruptions and force majeure
RF14	Transportation restrictions
RF15	Inexperience of contractors in MiC
RF16	Specialist skilled labor requirement
RF17	Modular installation errors, complex rectifications and reworks
RF18	Poor cooperation and communication among project participants
RF19	Modular design complexity
RF20	Unsupportive planning and building regulations
RF21	Limited capacity of modular manufacturers/suppliers
RF22	Manual handling of heavy modules
RF23	Absence of standardized modules
RF24	Unable to freeze design early
RF25	Higher prices of modules
RF26	Diseconomies of scale and longer break-even period
RF27	Modular production system failure
RF28	Lack of best management practices
RF29	Geometric and dimensional intolerances

4 ***Survey approach and sample of participants***

5 Based on the precedents of Osei-Kyei et al. (2017), an international expert survey approach was  
 6 adopted. This instructed the adoption of a quantitative research instrument and hence, the use of a  
 7 questionnaire. The research relied solely on questionnaires due to the following reasons. (i) The

1 quantitative evaluation of the risk factors required numerical data based on the opinions of  
 2 international experts. Structured questionnaires are used to collect quantitative data using closed-  
 3 ended questions and have been relied upon in previous studies to collect quantitative data (Zhang  
 4 2005, Sachs *et al.* 2007, Osei-Kyei *et al.* 2017). (ii) Questionnaires are known to many CEM  
 5 researchers and industry practitioners, and hence, it can generate more reliable results (Wuni *et al.*  
 6 2019). (iii) Questionnaires can generate an adequate amount of data within a short period and can  
 7 be considered as the cheapest survey instrument in terms of time and resources. Thus, following  
 8 the precedents of international surveys, questionnaires were very appropriate for this study.



9  
 10 **Figure 1.** Methodological framework of the research

11 The study targeted MiC (including modular and off-site construction) experts in academia and  
 12 industry. Considering that there is no central database for these experts, random sampling was  
 13 practically inappropriate. As a result, the purposive and snowballing sampling techniques were  
 14 adopted. The purposive sampling technique facilitated the collection of data from experts who had  
 15 substantial and industry experience in MiC projects. In the context of the snowballing technique,  
 16 experts were invited to respond to the questions and recommend other experts who have substantial  
 17 experience in MiC projects. The experts were selected based on the following criteria. (i) The



1 expert should have extensive theoretical and practical knowledge of MiC or similar models such  
2 as modular construction, prefabrication, industrialized building systems, or prefabricated  
3 prefinished volumetric construction. (ii) The experts should have detailed knowledge of the  
4 processes involved in MiC project delivery. (iii) The expert should have been involved in at least  
5 one MiC project (Osei-Kyei *et al.* 2017).

6 Given these criteria, the researchers collected contact information of MiC researchers from  
7 published articles in reputable journals and industry experts from reputable construction industry  
8 councils' websites. In all, 400 experts were invited to complete the online survey. The  
9 questionnaire requested the experts to evaluate the criticality of the risk factors on a 5-point grading  
10 scale; 1 = Least critical, 2 = Fairly critical, 3 = Critical, 4 = Very critical, and 5 = Extremely critical.  
11 These linguistic variables and grading continuum are appropriate for evaluating the risk factors  
12 based on fuzzy logic. After several reminders, a total sample of 56 responses was collected and  
13 was deemed adequate for analysis. Although small, such sample sizes are characteristic of web-  
14 based international surveys in CEM research. Indeed, the sample size compares favourably against  
15 similar international surveys such as 46 (Zhang 2005), 42 (Osei-Kyei *et al.* 2017), and 29 (Sachs  
16 *et al.* 2007).

### 17 ***Statistical analysis and data pretesting***

18 Statistical analyses were executed on the data to ascertain its reliability and suitability for adopted  
19 methods of data analysis in the research. The analysis was conducted using the Statistical Package  
20 for the Social Sciences (SPSS v.25). A reliability test of internal consistency in the survey  
21 instrument was conducted using the Cronbach's Alpha. Based on this indicator, the statistical  
22 reliability of the dataset ranges from 0 to 1, where an Alpha value closer to 1 signals stronger  
23 reliability of the dataset and a value closer to 0 indicates weaker reliability. Based on the  
24 recommendation of Tavakol and Dennick (2011), a minimum Alpha score of 0.7 is required as  
25 acceptable reliability of the dataset. Reliability analysis of the dataset using SPSS generated a  
26 Cronbach's Alpha of 0.873, indicating a strong internal consistency within the dataset. Several  
27 statistical analyses were conducted to ascertain the suitability of the dataset and sample for factor  
28 analysis. Before this analysis, the dataset was assessed for normality to determine whether  
29 parametric or non-parametric statistical methods are suitable for the data analysis. The Wilk-  
30 Shapiro test was conducted based on the recommendations of Chou *et al.* (1998). The Wilk-

1 Shapiro test generated P-values less than 0.05 for all factors (Table 3), indicating that the data is  
2 non-normally distributed and instructs the use of non-parametric statistical methods to assess the  
3 suitability of the data set for factor analysis.

4 Based on this outcome, an ordinal-based non-parametric technique called the Mann-Whitney  
5 U-Test test was conducted to determine whether there are significant variations in the responses  
6 of the experts in academia and industry. The Mann-Whitney U-Test was implemented due to the  
7 three reasons: (a) the dependent variables (CRFs) were measured at the ordinal level using the  
8 Likert scale; (b) the independent variable consisted of two categorical, independent groups –  
9 experts from academia and industry; and (c) the data was not normally distributed (Norusis 2008).  
10 The asymptotic significance (2-tailed) p-values greater than 0.05 for all the factors (Table 3)  
11 indicated that there are no significant variations in the responses of the different experts, suggesting  
12 that the responses can be treated holistically (Ameyaw and Chan 2015). According to Lingard and  
13 Rowlinson (2006), a factor to sample size ratio of 1:5 is a prerequisite for exploratory factor  
14 analysis (hereafter, factor analysis). The dataset did not meet this condition since the ratio is 1: 2  
15 (29/56) in the dataset. However, there are other overriding statistical analyses which can be  
16 conducted. First, the Kaiser-Meyer-Olkin (KMO) test statistic was used to measure the adequacy  
17 of the sample for factor analysis. A KMO test statistic of 0.647 was above the minimum threshold  
18 of 0.6 (Norusis 2008), indicating that the sample is adequate for factor analysis. Second, Bartlett's  
19 test of sphericity was carried out to determine whether the correlation matrix is significantly  
20 different from an identity matrix. A Pearson Chi-square,  $\chi^2 = 1076.806$ , and  $p < 0.000$ , indicated  
21 that the correlation matrix is not an identity matrix. Considering the Cronbach's Alpha value of  
22 0.873, the KMO test statistic and Bartlett's test of sphericity, the dataset was deemed suitable for  
23 factor analysis.


24 According to Fang et al. (2004), factor analysis is a multivariate statistical method used to  
25 measure variability among observed, correlated variables, and the possibility of categorizing  
26 related factors. Due to the unique power of factor reduction and clustering (Brown 2015), factor  
27 analysis is widely used in the CEM research domain to reduce, cluster and manage a large set of  
28 risk factors. Thus, factor analysis was used to evaluate and cluster the risk factors in the  
29 implementation of MiC projects.

30 ***Fuzzy logic and fuzzy synthetic evaluation analysis***

1 Fuzzy logic is based on fuzzy set theory. Zadeh (1965) propounded fuzzy set theory to  
2 mathematically deal with objects which are imprecisely defined with grades of a continuum. Zadeh  
3 (1975) introduced linguistic variables to approximate reasoning using the fuzzy sets. Fuzzy set  
4 theory has the power to precisely and objectively explain and quantify ill-defined and imprecise  
5 information. Mathematically, a fuzzy set takes the form of membership functions which allocate  
6 grades of membership to define the extent of association of each element in the universe of  
7 discourse to the concept represented by a fuzzy set (Ameyaw and Chan 2015).

8 These membership grades are represented using real numbers that range between a closed  
9 interval of zero to one, where zero represents no membership, and one represents full membership  
10 in the fuzzy set. It employs linguistic variables and terms to model the characteristic vagueness in  
11 the human cognitive process. For this reason, fuzzy logic has been used in a multi-attribute  
12 decision-making problem. Notably, the fuzzy synthetic evaluation (FSE) analysis is widely used  
13 in CEM research domain to quantitatively evaluate and model risk factors. For instance, Ameyaw  
14 and Chan (2015) used FSE to evaluate and rank risk factors in public-private partnership water  
15 projects; Wuni and Shen (2019) used FSE to allocate risk events in the supply chain of MiC; and  
16 Zafar et al. (2019) used FSE to analyze time overrun risk factors in highway projects. This study  
17 used FSE to evaluate and rank the risk factors in the implementation of MiC projects because the  
18 technique can be used to make a meaningful quantitative assessment of the fuzzy linguistic  
19 variables such as least critical, fairly critical, etc. as used in the current study. This research adopted  
20 the FSE protocol established in Ameyaw and Chan (2015), as shown in Figure 2. Details of each  
21 stage are discussed in the next section.

22



1  
2 **Figure 2.** Flowchart of the fuzzy synthetic evaluation procedure

3 **Data analysis and results**

4 ***Background information of the international experts***


5 One of the setbacks of international surveys is data quality problems. This could arise from the  
6 engagement of inappropriate or inexperienced respondents. Engaging respondents with substantial  
7 practical and theoretical knowledge of the subject matter can resolve this. Table 2 shows the work  
8 experience, job category, and the country in which the expert obtained their experiences. From  
9 Table 2, the majority of the experts were from academia but had substantial practical and research  
10 experience in MiC project implementation. These experts have strong links with industry and are  
11 regularly engaged in solving difficult challenges. About 51.8% of the respondents had at least 5  
12 years' experience with MiC projects, and about 28.6% of them had over 11 years' experience and  
13 knowledge in MiC projects. Thus, the engaged experts had enough practical and research

1 experience to comment on the risk factors in the application of MiC. These experts had worked in  
 2 over 18 countries distributed across the six continents. Although the experts were asked to indicate  
 3 the country in which they were engaged in the MiC projects, some indicated that they had extensive  
 4 experience in the technology in more than 1 country.

5 **Table 2.** Background data of the international experts

Attribute	Sub-attribute	Responses	% Responses
Years of MiC work experience	Below 5 years	27	48.2
	5 - 10 years	13	23.2
	11 - 15 years	5	8.9
	16 - 20 years	2	3.6
	21years and above	9	16.1
	<b>Total</b>	<b>56</b>	<b>100.0</b>
Country	United States	10	17.9
	Canada	8	14.3
	China	7	12.5
	Hong Kong	7	12.5
	Australia	5	8.9
	Malaysia	4	7.1
	United Kingdom	4	7.2
	Brazil	1	1.8
	Finland	1	1.8
	Germany	1	1.8
	Greece	1	1.8
	Lebanon	1	1.8
	Singapore	1	1.8
	Slovakia	1	1.8
	Spain	1	1.8
	Sweden	1	1.8
	Switzerland	1	1.8
	Tanzania	1	1.8
	<b>Total</b>	<b>56</b>	<b>100.0</b>

6 The experts had worked in developing, transition and developed economies and thus, their  
 7 holistic opinions constitute a useful knowledge base in the assessment of the risk factors. The  
 8 geospatial distribution of experts is unique and comprehensive because it includes countries with  
 9 the most advanced and successful MiC projects and thus, their collective opinions could be quite  
 10 useful in most countries. Figure 3 shows the project types in which the experts had been engaged  
 11 in. Majority of the experts (40) had worked on residential MiC projects because most countries are  
 12 using the technology to respond to the growing housing crisis across the globe (Wuni and Shen  
 13 2019d, Wuni *et al.* 2019).



1  
2 **Figure 3.** Types of MiC projects worked on by international experts.

3 Figure 3 also shows that the experts had worked on several MiC project types, and thus, their  
4 opinions on the risk factors draw on experience, research, and knowledge of different MiC  
5 projects. This further highlights the quality and representativeness of the experts in the study.

6 ***Identifying the critical risk factors of MiC projects***

7 The mean score analysis was used to identify the critical risk factors associated with the  
8 implementation of MiC projects. This statistic is widely and commonly used in CEM research  
9 domain to explore the average evaluation of risk factors on the Likert scale. Based on the grades  
10 of the 5-point Likert scale used in the study, a mean score of 3 or more indicates that the risk factor  
11 is at least critical (Osei-Kyei *et al.* 2017, Zafar *et al.* 2019) in MiC projects. Table 3 shows the  
12 results of the mean score indices of the risk factors. The mean score analysis (Table 3) results  
13 indicate that the experts assessed 23 of the 29 risk factors as critical in MiC projects. These risk  
14 factors deserve the critical attention of investors, contractors, and policymakers and thus, require  
15 further in-depth evaluation. This implies that the register of risk factors established in Wuni *et al.*  
16 (2019) was appropriate and useful. The top 5 critical risk factors (CRFs) include poor supply chain  
17 integration (3.80); higher initial capital cost (3.59); limited MiC expertise and experience (3.52);  
18 modular installation errors, complex rectifications and reworks (3.46); and stakeholder  
19 fragmentation and management complexity (3.39).

1 **Table 3.** Mean score ranking of the risk factors for MiC Projects

S.N.	Risks Factors	Mean	SD	Rank	Shapiro - Wilk Test	Mann-Whitney U-Test
RF3	Poor supply chain integration and disturbances	3.80	0.90	1	0.000*	0.627
RF2	Higher initial capital cost	3.59	1.07	2	0.000*	0.850
RF10	Limited MiC expertise and experience	3.52	0.91	3	0.000*	0.769
RF17	Modular installation errors, complex rectifications and reworks	3.46	0.87	4	0.000*	0.522
RF1	Stakeholder fragmentation and management complexity	3.39	1.04	5	0.000*	0.076
RF7	Defective design and change order	3.38	1.15	6	0.000*	0.538
RF18	Poor cooperation and communication among project participants	3.38	0.96	6	0.000*	0.735
RF9	Inefficient scheduling	3.32	1.01	8	0.000*	0.768
RF20	Unsupportive planning and building regulations	3.30	1.06	9	0.000*	0.215
RF6	Lack of MiC design codes and standards	3.29	1.28	10	0.000*	0.886
RF21	Limited capacity of modular manufacturers/suppliers	3.29	1.07	10	0.001*	0.950
RF26	Diseconomies of scale and longer break-even period	3.27	1.07	12	0.000*	0.486
RF24	Unable to freeze design early	3.25	1.24	13	0.000*	0.333
RF8	Supply chain information gap and inconsistency	3.23	0.89	14	0.000*	0.409
RF29	Geometric and dimensional intolerances	3.18	1.01	15	0.001*	0.875
RF12	Complex interfacing between systems	3.16	1.06	16	0.000*	0.764
RF19	Modular design complexity	3.14	1.03	17	0.000*	0.082
RF4	Delays in delivery of modules to site	3.11	0.98	18	0.000*	0.531
RF11	Shortage of modular components	3.11	1.11	18	0.000*	0.934
RF27	Modular production system failure	3.09	4.10	20	0.000*	0.586
RF15	Inexperience of contractors in MiC	3.09	0.72	21	0.000*	0.550
RF16	Specialist skilled labour requirement	3.07	0.95	22	0.000*	0.567
RF25	Higher prices of modules	3.00	1.11	23	0.000*	0.505
RF23	Absence of standardized modules	2.95	1.07	24	0.001*	0.709
RF14	Transportation restrictions	2.93	0.99	25	0.000*	0.770
RF28	Lack of best management practices	2.93	0.83	25	0.000*	0.503
RF22	Manual handling of heavy modules	2.79	1.17	27	0.000*	0.733
RF5	Poor government support and regulations	2.75	1.05	28	0.000*	0.403
RF13	Weather disruptions and force majeure	2.48	0.97	29	0.000*	0.104

2 Note\*: The Shapiro – Wilk test was significant at the 0.05 significance level, indicating the data were not  
 3 normally distributed.

4 However, the 20<sup>th</sup> ranked critical risk factor (RF27) scored a standard deviation of 4.10. This is  
 5 quite suspicious because it indicates that experts’ ratings for the risk factor were widely dispersed

1 around the statistical mean. The implication may be that the experts do not have consensus or  
2 unanimous opinion on the criticality of the risk factor. Perhaps, its relative importance varies  
3 considerably in different geospatial context or project type. However, it was considered due to the  
4 higher mean score, but future research should measure its significance in another context. RF1,  
5 F2, and RF3 were ranked among the top 5 critical risk factors (CRFs) in Wuni et al. (2019),  
6 suggesting that the number of times a risk factor is cited in studies might reflect its significance  
7 and criticality.

8 Six risk factors were evaluated below the critical threshold of 3.0 on the 5-point grading scale  
9 by the experts. These include absence of standardized modules (2.95); transportation restrictions  
10 (2.93); lack of best management practices (2.93); manual handling of heavy modules (2.79); poor  
11 government support and regulations (2.75); and weather disruptions and force majeure (2.48). The  
12 scores of the first 5 factors evaluated as not critical by the experts have scores closer to critical  
13 threshold of 3.0, suggesting that they could be critical in some countries and hence, need to be  
14 considered in MiC risk planning and management. Again, even though RF13 recorded the lowest  
15 mean score and has been assessed as least critical, this factor, in reality, constitute a CRF in some  
16 countries. For instance, in Hong Kong, the strong wind forces from typhoons present a significant  
17 compromise and challenge to the structural stability and integrity of high-rise MiC projects (Pan  
18 and Hon 2018, Wuni *et al.* 2019). Indeed, these weather elements could significantly affect  
19 schedule by sending workers off the job-site for days; which is extremely significant in the case  
20 of six-day cycle assembly (Li, Xu, *et al.* 2018).

### 21 ***Factor analysis of the critical risk factors in the implementation of MiC projects***

22 A principal component analysis of the 23 CRFs using Varimax Rotation converged in 8 iterations  
23 and generated a 4-factor solution with eigenvalues greater than 1, explaining 72.616% of the total  
24 variance. Considering that there is no existing study which classified the various risk factors  
25 examined in the current study, the characteristics and nature of the individual risk factors under  
26 each factor grouping (hereafter principal risk factors, PRFs) were used to determine a  
27 nomenclature for each PRF. The 23 CRFs were classified into 4 PRFs comprising stakeholder and  
28 supply chain risks, PRF1 (with 9 CRFs); design and capabilities risks, PRF2 (with 9 CRFs);  
29 financing risks, PRF3 (with 3 CRFs); and regulatory risks, PRF4 (with 2 CRFs). There are some  
30 overlaps within the risk factors in the various PRFs. However, no attempt was made to move the  
31 risk factors to other PRF because of the need for objectivity in the evaluation process. According



1 to Ameyaw and Chan (2015), classification of the risk factors into factor groupings offer two  
 2 advantages: (i) the PRFs are used as input variables in the assessment of the overall risk level of  
 3 MiC projects and (ii) the PRFs offers a systematic framework and basis for effective risk  
 4 management by reducing the need to deal directly with a long risk factor register. The risk factors  
 5 and PRFs in Table 4 form the basis for the fuzzy synthetic evaluation analysis of the risk factors  
 6 in the implementation of MiC projects.

7 **Table 4.** Critical risk factor extraction and loadings

Critical risk factors (CRFs) /Principal risk factors (PRFs)	Factor loadings	Eigen-value	% of variance explained	Cumulative % of variance explained
<i>Stakeholder and supply chain risks (PRF1)</i>		11.257	40.205	40.205
Stakeholder fragmentation and management complexity	0.953			
Delays in delivery of modules to site	0.827			
Complex interfacing between systems	0.825			
Supply chain information gap and inconsistency	0.814			
Shortage of modular components	0.755			
Poor supply chain integration and disturbances	0.674			
Modular production system failure	0.670			
Inefficient scheduling	0.485			
Poor cooperation and communication among project participants	0.451			
<i>Design and capabilities risks (PRF2)</i>		5.411	19.326	59.531
Geometric and dimensional intolerances	0.852			
Unable to freeze design early	0.772			
Modular installation errors, complex rectifications and reworks	0.713			
Inexperience of contractors in MiC	0.676			
Specialist skilled labour requirement	0.607			
Limited capacity of modular manufacturers/suppliers	0.529			
Limited MiC expertise and experience	0.554			
Modular design complexity	0.542			
Defective design and change order	0.509			
<i>Financing risks (PRF3)</i>		2.088	7.458	66.989
Higher prices of modules	0.734			
Diseconomies of scale and longer break-even period	0.661			
Higher initial capital cost	0.566			
<i>Regulatory risks (PRF4)</i>		1.576	5.627	72.616

Lack of MiC design codes and standards	0.768
Unsupportive planning and building regulations	0.754

1 ***Fuzzy synthetic evaluation of the CRFs in the implementation of MiC projects***

2 Drawing on the outcome of the factor analysis, three levels of FSE of risk of MiC projects are  
3 derived. The third level involves evaluation of the criticality of risk factors within each PRF and  
4 the second level involves assessment of the criticality of the PRFs. The overall risk index (1<sup>st</sup> level)  
5 for MiC projects is then computed based on the criticality assessment of the individual PRFs. This  
6 is considered as a multi-factor and multi-level FSE (Ameyaw and Chan 2015) of the risk of MiC  
7 projects. The systematic implementation of the multi-level FSE is shown in Figure 2.

8 *Computing the weighting function of each CRF and PRF:* According to Lo (1999), the overall  
9 accuracy of the FSE model depends on the accuracy of the weightings assigned to each CRF and  
10 PRF. Various techniques are available for accurate computations of the weightings from survey  
11 data using a Likert scale such as the analytic hierarchy process, direct point allocation, unit  
12 weighting, tabulated judgment method, and normalized mean method (Hsiao 1998, Lo 1999,  
13 Ameyaw and Chan 2015). Based on the recommendation of Ameyaw and Chan (2015), the  
14 normalized mean method is used to compute the weightings of each CRF and PRF. Following the  
15 works of Xu et al. (2010), the weighting functions were derived through normalization of the mean  
16 scores of each CRF and PRF as:

17 
$$w_i = \frac{M_i}{\sum_{i=1}^5 M_i}, 0 < w_i < 1, \text{ and } \sum_{i=1}^n w_i = 1 \tag{1}$$

18 where  $w_i$  is the weighting function of a specific CRF/PRF;  $M_i$  is the mean score of each CRF/PRF;  
19 and  $i$  ranges from 1 to 5 based on the 5-point grading scale. As shown in Figure 2, the weighting  
20 function is given by:

21 
$$W_i = \{w_1, w_2, \dots, w_n\} \tag{2}$$

22 For example, in Table 5, the mean score for RF3 is 3.80, and the total mean score for PRF1 is  
23 29.59. The weighting for RF3 is computed using equation (1) as:

24 
$$w_{RF3} = \frac{3.80}{3.80+3.39+3.38+3.32+3.23+3.16+3.11+3.11+3.09} = \frac{3.80}{29.59} = 0.128$$

25 Similarly, the weighting functions of the remaining risk factors under PRF1 – PRF4 are  
26 computed using the same procedure (Table 5), and the normalized weighting function sets satisfy

1 the condition in Equation (1) for each PRF (Table 5). For example, the normalized weighting  
 2 function for PRF1 is given as:

$$3 \sum_{i=1}^9 W_i = 0.128 + 0.115 + 0.114 + 0.112 + 0.109 + 0.107 + 0.105 + 0.105 + 0.104 = 1.000$$

4 **Table 5.** Weightings for the CRFs and PRFs for MiC projects

S.N.	Factors	Mean for CRFs	Weightings for each CRF	Total Mean for each PRF	Weightings for each PRF
<i>PRF1</i>	<i>Stakeholder and supply chain risks</i>			29.59	0.392
RF3	Poor supply chain integration and disturbances	3.80	0.128		
RF1	Stakeholder fragmentation and management complexity	3.39	0.115		
RF18	Poor cooperation and communication among project participants	3.38	0.114		
RF9	Inefficient scheduling	3.32	0.112		
RF8	Supply chain information gap and inconsistency	3.23	0.109		
RF12	Complex interfacing between systems	3.16	0.107		
RF4	Delays in delivery of modules to site	3.11	0.105		
RF11	Shortage of modular components	3.11	0.105		
RF27	Modular production system failure	3.09	0.104		
<i>PRF2</i>	<i>Design and capabilities risks</i>		1.000	29.38	0.390
RF10	Limited MiC expertise and experience	3.52	0.120		
RF17	Modular installation errors, complex rectifications and reworks	3.46	0.118		
RF7	Defective design and change order	3.38	0.115		
RF21	Limited capacity of modular manufacturers/suppliers	3.29	0.112		
RF24	Unable to freeze design early	3.25	0.111		
RF29	Geometric and dimensional intolerances	3.18	0.108		
RF19	Modular design complexity	3.14	0.107		
RF15	Inexperience of contractors in MiC	3.09	0.105		
RF16	Specialist skilled labour requirement	3.07	0.104		
<i>PRF3</i>	<i>Financing risks</i>		1.000	9.86	0.131
RF2	Higher initial capital cost	3.59	0.364		
RF26	Diseconomies of scale and longer break-even period	3.27	0.332		
RF25	Higher prices of modules	3.00	0.304		
<i>PRF4</i>	<i>Regulatory risks</i>		1.00	6.59	0.087
RF20	Unsupportive planning and building regulations	3.30	0.501		
RF6	Lack of MiC design codes and standards	3.29	0.499		

Total PRF	75.42
-----------	-------

1

2

3

4

Considering the total mean scores of the PRFs (PRF1 = 29.59, PRF2 = 29.38, PRF3 = 9.86 and PRF4 = 6.59) as 75.42, the mean scores of each PRF can be normalized to obtain their weighting functions using equation (1) as:

$$5 \quad W_{PRF1} = \frac{29.59}{29.59+29.38+9.86+6.59} = \frac{29.59}{75.42} = 0.392$$

$$6 \quad W_{PRF2} = \frac{29.38}{29.59+29.38+9.86+6.59} = \frac{29.38}{75.42} = 0.390$$

$$7 \quad W_{PRF3} = \frac{9.86}{29.59+29.38+9.86+6.59} = \frac{9.86}{75.42} = 0.131$$

$$8 \quad W_{PRF4} = \frac{6.59}{29.59+29.38+9.86+6.59} = \frac{6.59}{75.42} = 0.087$$

9 Similarly, the sum of normalized weightings of the all the PRFs equals 1. The weightings for the

10 individual risk factors and PRFs form the basis for calibrating the membership functions in the next section.

11 *Computing the membership functions of each CRF and PRF:* The membership function (MF)

12 of each CRF is computed from the percentage responses of the experts. The membership function

13 of each PRF is further computed from the membership functions of the CRFs within each factor

14 grouping. The membership functions of each CRF and PRF is then used to develop the fuzzy

15 matrix (Figure 3). To compute the MF for each CRF, the analyst needs to ascertain the percentage

16 responses of the experts for the various grading point scales comprising *least critical* (LC), *fairly*

17 *critical* (FC), *critical* (C), *very critical* (VC), and *extremely critical* (EC). For example, the data

18 analysis shows that 1.8% of the experts assessed “stakeholder fragmentation and management

19 complexity (CRF1)” as *least critical*, 16.1% assessed it as *fairly critical*, 42.9% assessed it as

20 *critical*, 19.6% assessed as *very critical* and 19.6% also assessed it as *extremely critical*. Thus, the

21 membership function for CRF1 is computed as:

$$22 \quad MF_{CRF1} = \frac{0.018}{LC(1)} + \frac{0.161}{FC(2)} + \frac{0.429}{C(3)} + \frac{0.196}{LC(4)} + \frac{0.196}{VC(5)} \quad (3)$$

23 Thus, the membership function of CRF1 can be expressed otherwise as (0.02, 0.16, 0.43, 0.20,

24 0.20). The membership functions of the rest of the CRFs are computed using the same approach

25 as shown in Table 6. The membership functions (Level 3) of the individual CRFs form the basis

26 for computing the membership functions (Level 2) of the PRF. However, the computations of the

27 membership functions of the PRFs require the fuzzy evaluation matrix. Based on the works of

28 Ameyaw and Chan (2015), the fuzzy evaluation matrix is given by:

29 **Table 6.** Membership functions (MF) for all CRFs and PRFs for MiC projects

S.N.	CRFs and PRF	Weigh tings	Membership functions for each CRF (Level 3)	Membership Function for each PRF (Level 2)
<i>PRF1</i>	<i>Stakeholder and supply chain risks</i>			<i>(0.03, 0.18, 0.36, 0.30, 0.12)</i>
RF3	Poor supply chain integration and disturbances	0.128	(0.00, 0.09, 0.25, 0.43, 0.23)	
RF1	Stakeholder fragmentation and management complexity	0.115	(0.02, 0.16, 0.43, 0.20, 0.20)	
RF18	Poor cooperation and communication among project participants	0.114	(0.02, 0.20, 0.27, 0.43, 0.09)	
RF9	Inefficient scheduling	0.112	(0.05, 0.11, 0.43, 0.27, 0.13)	
RF8	Supply chain information gap and inconsistency	0.109	(0.02, 0.16, 0.48, 0.25, 0.09)	
RF12	Complex interfacing between systems	0.107	(0.04, 0.27, 0.30, 0.29, 0.11)	
RF4	Delays in delivery of modules to site	0.105	(0.04, 0.27, 0.30, 0.34, 0.05)	
RF11	Shortage of modular components	0.105	(0.11, 0.14, 0.38, 0.29, 0.09)	
RF27	Modular production system failure	0.104	(0.00, 0.27, 0.46, 0.18, 0.09)	
<i>PRF2</i>	<i>Design and capabilities risks</i>			<i>(0.05, 0.17, 0.35, 0.33, 0.11)</i>
RF10	Limited MiC expertise and experience	0.120	(0.02, 0.14, 0.23, 0.52, 0.09)	
RF17	Modular installation errors, complex rectifications and reworks	0.118	(0.02, 0.09, 0.41, 0.38, 0.11)	
RF7	Defective design and change order	0.115	(0.07, 0.18, 0.20, 0.41, 0.14)	
RF21	Limited capacity of modular manufacturers/suppliers	0.112	(0.04, 0.21, 0.32, 0.29, 0.14)	
RF24	Unable to freeze design early	0.111	(0.09, 0.23, 0.18, 0.34, 0.16)	
RF29	Geometric and dimensional intolerances	0.108	(0.05, 0.18, 0.39, 0.29, 0.09)	
RF19	Modular design complexity	0.107	(0.05, 0.18, 0.46, 0.18, 0.13)	
RF15	Inexperience of contractors in MiC	0.105	(0.00, 0.18, 0.59, 0.20, 0.04)	
RF16	Specialist skilled labour requirement	0.104	(0.07, 0.16, 0.43, 0.30, 0.04)	
<i>PRF3</i>	<i>Financing risks</i>			<i>(0.05, 0.23, 0.22, 0.38, 0.13)</i>
RF2	Higher initial capital cost	0.364	(0.02, 0.20, 0.16, 0.43, 0.20)	
RF26	Diseconomies of scale and longer break-even period	0.332	(0.02, 0.29, 0.23, 0.34, 0.13)	
RF25	Higher prices of modules	0.304	(0.13, 0.20, 0.27, 0.38, 0.04)	
<i>PRF4</i>	<i>Regulatory risks</i>			<i>(0.09, 0.16, 0.26, 0.35, 0.14)</i>
RF20	Unsupportive planning and building regulations	0.501	(0.05, 0.18, 0.29, 0.38, 0.11)	
RF6	Lack of MiC design codes and standards	0.499	(0.13, 0.14, 0.23, 0.32, 0.18)	

$$1 \quad R_i = \begin{bmatrix} MF_{u1} \\ MF_{u2} \\ MF_{u3} \\ \dots \\ MF_{un} \end{bmatrix} = \begin{bmatrix} C_{1u_{i1}} & C_{2u_{i1}} & C_{3u_{i1}} & C_{4u_{i1}} & C_{5u_{i1}} \\ C_{1u_{i2}} & C_{2u_{i2}} & C_{3u_{i2}} & C_{4u_{i2}} & C_{5u_{i2}} \\ C_{1u_{i3}} & C_{2u_{i3}} & C_{3u_{i3}} & C_{4u_{i3}} & C_{5u_{i3}} \\ \dots & \dots & \dots & \dots & \dots \\ C_{1u_{in}} & C_{2u_{in}} & C_{3u_{in}} & C_{4u_{in}} & C_{5u_{in}} \end{bmatrix} \quad (4)$$

2        Where  $R_i$  denotes the fuzzy membership functions for the CRFs within a given PRF (called  
3 fuzzy matrix) and  $MF_{u1}$  to  $MF_{un}$  denotes the membership functions of  $n$  CRFs in a given PRF. The  
4 values for  $C_1$  to  $C_5$  in equation (4) are the Level 3 membership functions shown in Table 6. Given  
5 the fuzzy matrix ( $R_i$ ) and the weightings ( $W_i$ ), the fuzzy evaluation matrix ( $D_i$ ), as shown in Figure  
6 2 can be computed using the equation:

$$7 \quad D_i = W_i \bullet R_i = \{w_1, w_2, w_3, \dots, w_n\} * \begin{bmatrix} C_{1u_{i1}} & C_{2u_{i1}} & C_{3u_{i1}} & C_{4u_{i1}} & C_{5u_{i1}} \\ C_{1u_{i2}} & C_{2u_{i2}} & C_{3u_{i2}} & C_{4u_{i2}} & C_{5u_{i2}} \\ C_{1u_{i3}} & C_{2u_{i3}} & C_{3u_{i3}} & C_{4u_{i3}} & C_{5u_{i3}} \\ \dots & \dots & \dots & \dots & \dots \\ C_{1u_{in}} & C_{2u_{in}} & C_{3u_{in}} & C_{4u_{in}} & C_{5u_{in}} \end{bmatrix} = (d_{i1}, d_{i2}, \dots, d_{in}) \quad (5)$$

8        where;  $d_{in}$  denotes the degree of membership of the grade alternative for a given PRF and “ $\bullet$ ”  
9 denotes a fuzzy composite operator. For example, PRF3 contains three CRFs comprising RF2,  
10 RF25, and RF26. The weights of the CRFs include RF2 (0.364), RF25 (0.304), and RF26 (0.332)  
11 as shown in Table 6 and thus, the weighting function for PRF3 is given by:

$$12 \quad W_{PRF3} = \{0.364, 0.304, 0.332\}$$

13        Considering the membership functions of RF2, RF25, and RF26 (Table 6), the fuzzy evaluation  
14 matrix for PRF3 is given by:

$$15 \quad R_{PRF3} = \begin{bmatrix} MF_{RF2} \\ MF_{RF25} \\ MF_{RF26} \end{bmatrix} = \begin{bmatrix} 0.02 & 0.20 & 0.16 & 0.43 & 0.20 \\ 0.13 & 0.20 & 0.27 & 0.38 & 0.04 \\ 0.02 & 0.29 & 0.23 & 0.34 & 0.13 \end{bmatrix}$$

16        Thus, using equation (5), the fuzzy evaluation matrix for PRF3 is computed as follows:

$$17 \quad D_{PRF3} = W_{PRF3} \bullet R_{PRF3} = (0.364, 0.304, 0.332) * \begin{bmatrix} 0.02 & 0.20 & 0.16 & 0.43 & 0.20 \\ 0.13 & 0.20 & 0.27 & 0.38 & 0.04 \\ 0.02 & 0.29 & 0.23 & 0.34 & 0.13 \end{bmatrix}$$

1 = (0.05, 0.23, 0.22, 0.38, 0.13)

2 Similarly, the fuzzy evaluation matrix of PRF1, PRF2 and PRF4 are obtained using the  
3 weighting functions set in column 3 and the membership functions of the CRFs in column 4 under  
4 each PRF, as shown in Table 6.

5 *Computing the criticality indices of the PRFs and the overall risk index:* The criticality indices  
6 of the PRFs can be computed as a product of the fuzzy evaluation matrix of each PRF and the  
7 grade alternatives on the Likert scale adopted for the study. Mathematically, the criticality index  
8 of each PRF is given by:

$$9 \text{ PRF}_{\text{Index}} = \sum_{i=1}^5 (D_i \times E_i) \quad (6)$$

10 Where;  $D_i$  denotes the fuzzy evaluation matrix of a given PRF and  $E_i$  denotes the grade  
11 alternatives of the adopted 5-point Likert scale (Figure 2). Using equation (6), the criticality indices  
12 of the PRF are computed as follows:


$$13 \text{ PRF1} = (0.03, 0.18, 0.36, 0.30, 0.12) \times (1, 2, 3, 4, 5) = (0.03*1 + 0.18*2 + 0.36*3 + 0.30*4 + 0.12*5) = \mathbf{3.31}$$

$$14 \text{ PRF2} = (0.05, 0.17, 0.35, 0.33, 0.11) \times (1, 2, 3, 4, 5) = (0.05*1 + 0.17*2 + 0.35*3 + 0.33*4 + 0.11*5) = \mathbf{3.28}$$

$$15 \text{ PRF3} = (0.05, 0.23, 0.22, 0.38, 0.13) \times (1, 2, 3, 4, 5) = (0.05*1 + 0.23*2 + 0.22*3 + 0.38*4 + 0.13*5) = \mathbf{3.34}$$

$$16 \text{ PRF4} = (0.09, 0.16, 0.26, 0.35, 0.14) \times (1, 2, 3, 4, 5) = (0.09*1 + 0.16*2 + 0.26*3 + 0.35*4 + 0.14*5) = \mathbf{3.32}$$

17 The above criticality indices are considered the second level fuzzy synthetic evaluation analysis.  
18 The final evaluation matrix of overall risk level index for MiC projects can be computed using the  
19 fuzzy evaluation matrices of the PRFs and their associated total weightings. The weightings for  
20 PRF1, PRF2, PRF3, and PRF4 are 0.392, 0.390, 0.131, and 0.087, respectively, as shown in Table  
21 5. The fuzzy evaluation matrices of the PRFs are PRF1 (0.03, 0.18, 0.36, 0.30, 0.12), PRF2 (0.05,  
22 0.17, 0.35, 0.33, 0.11), PRF3 (0.05, 0.23, 0.22, 0.38, 0.13), and PRF4 (0.09, 0.16, 0.26, 0.35, 0.14),  
23 as shown in Table 6. Therefore, the following functions can be deduced.



1  
2 **Figure 4.** Criticality indices of the PRFs and overall risk level of MiC projects

3  $W_{Overall} = (0.392, 0.390, 0.131, 0.087)$

4  $R_{Overall} = \begin{bmatrix} MF_{PRF1} \\ MF_{PRF2} \\ MF_{PRF3} \\ MF_{PRF4} \end{bmatrix} = \begin{bmatrix} 0.03 & 0.18 & 0.36 & 0.30 & 0.12 \\ 0.05 & 0.17 & 0.35 & 0.33 & 0.11 \\ 0.05 & 0.23 & 0.22 & 0.38 & 0.13 \\ 0.09 & 0.16 & 0.26 & 0.35 & 0.14 \end{bmatrix}$

5 Thus, the final fuzzy evaluation matrix ( $D_{Overall}$ ) of the overall risk level for MiC projects can  
6 be computed using equation (5) as follows:

7  $D_{Overall} = W_{Overall} \bullet R_{Overall} = (0.392, 0.390, 0.131, 0.087) \times \begin{bmatrix} 0.03 & 0.18 & 0.36 & 0.30 & 0.12 \\ 0.05 & 0.17 & 0.35 & 0.33 & 0.11 \\ 0.05 & 0.23 & 0.22 & 0.38 & 0.13 \\ 0.09 & 0.16 & 0.26 & 0.35 & 0.14 \end{bmatrix}$

8  $= (0.05, 0.18, 0.33, 0.33, 0.12)$

9 The overall risk index (Level 1) for MiC projects is computed as a product of the final fuzzy  
10 evaluation matrix ( $D_{Overall}$ ) and the grade alternatives (1, 2, 3, 4, 5) on the Likert scale adopted for



1 the study. Mathematically, the overall risk level index for MiC Projects is calculated using  
2 equation (6) as follows:

$$3 \textbf{Overall risk level index} = (0.05, 0.18, 0.33, 0.33, 0.12) \times (1, 2, 3, 4, 5)$$
$$4 = (0.05*1 + 0.18*2 + 0.33*3 + 0.33*4 + 0.12*5) = 3.30 \textbf{(Critical)}$$

5 *Developing a risk assessment model for MiC projects:* Given the indices for the four PRFs, it is  
6 useful to develop a model which can facilitate risk assessment in MiC projects. Drawing on the  
7 works of Chen et al. (2019), a linear additive approach is used to develop the risk assessment  
8 model because it is simple, easy to understand, and can be supported by the criticality indices of  
9 the various PRFs. To develop the overall MiC risk assessment model, the criticality indices of the  
10 four PRFs are normalized using equation (1) to obtain their criticality weightings. From the  
11 computations above, the criticality indices of PRF1, PRF2, PRF3, and PRF4 are 3.31, 3.28, 3.34,  
12 and 3.32, respectively. Thus, the normalized criticality weighting for PRF1 is given by:

$$13 W_{\text{PRF1}} = \frac{3.31}{3.31+3.28+3.34+3.32} = \frac{3.31}{13.25} = 0.250$$

14 Similarly, the normalized criticality weightings for PRF2, PRF3, and PRF4 are computed as  
15 0.246, 0.252, and 0.251, respectively. Therefore, the linear additive risk assessment index (RAI)  
16 for MiC projects is given by:

$$17 \textbf{RAI}_{(\text{MiC projects})} = \mathbf{0.250}*(\text{stakeholder and supply chain risks}) + \mathbf{0.246}*(\text{design and capabilities}$$
$$18 \text{risks}) + \mathbf{0.252}*(\text{financing risks}) + \mathbf{0.251}*(\text{regulatory risks})$$

## 19 **Discussions and implications of the results**

20 The statistics in Figure 4 shows the criticality indices of principal risk factors and the overall risk  
21 level index of MiC projects. The PRFs are also ranked according to their criticality indices. The  
22 FSE analysis resulted in an overall risk index of 3.30, indicating that MiC projects in both  
23 developing and developed countries have some significant risks (Wuni and Shen 2019c, Wuni *et*  
24 *al.* 2019). Analysis of the summary results in Figure 4 shows that the indices of all the PRFs exceed  
25 the criticality threshold of 3.0 based on the 5-point Likert scale. This means all the risk factor  
26 groupings are at least critical and thus, policymakers, investors, and industry practitioners should  
27 examine, plan, and manage these risk factors in the implementation of MiC projects. The various  
28 PRFs are discussed in the following subsections.

1 ***PRF1 - Stakeholder and supply chain risks***

2 This PRF explains about 40.21% of the variations in the risk profile of MiC projects and scored  
3 an Eigenvalue of 11.26 (Table 4). It comprises nine significant risk factors with a total mean of  
4 29.59 and normalized weighting of 0.392 (Table 5). It has an overall risk level of 3.31 (Figure 4)  
5 and ranked 3<sup>rd</sup> among the four PRFs. Considering the nature of the nine CRFs under this PRF, the  
6 term “stakeholder and supply chain risks” holistically and appropriately describes the risks factors  
7 because they are associated with stakeholders and the MiC supply chain (Wuni and Shen 2019c).  
8 The nine CRFs of PRF1 were expected because they have been assessed as critical in previous  
9 studies. For instance, based on a systematic review, Wuni et al. (2019) found that stakeholder  
10 fragmentation and management complexity (RF1), poor supply chain integration and disturbances  
11 (RF3), delays in delivery of modules to site (RF4), supply chain information gap and inconsistency  
12 (RF8), and inefficient scheduling (RF9) ranked globally among the top 10 most CRFs in the  
13 application of MiC. Notably, there are several multidisciplinary stakeholders in the MiC supply  
14 chain with their unique goals and value systems (Luo *et al.* 2019). Yet, these stakeholders are  
15 fragmented along with the various segments of the MiC supply chain (Li *et al.* 2013, Wuni *et al.*  
16 2019). This increases the complexity of stakeholder management in MiC projects and hence, could  
17 compromise the success of a project since all key stakeholders need to be coordinated to ensure  
18 smooth delivery of the MiC project.

19 Furthermore, the MiC supply chain comprises linked segments (Li *et al.* 2016) and thus, poor  
20 integration and resulting disturbances could trigger detrimental impact on the entire supply chain  
21 (Wuni *et al.* 2019). For instance, delay in the delivery of modular components to site resulted in  
22 significant schedule delays of MiC projects in Hong Kong (Li, Xu, *et al.* 2018). Luo et al. (2019)  
23 reported that poor cooperation and communication among project participants (RF18) constitute a  
24 significant risk factor because it could compromise the success of the MiC project from the very  
25 early stages. For instance, the poor cooperation could result in late design freeze which has a  
26 significant impact on the schedule of MiC projects. Wuni and Shen (2019a) found that modular  
27 production system failure (RF27) could trigger shortage in the supply of modules which translates  
28 into a shortage of modular components (RF11) on site, in cases where there is no safety stock. This  
29 implies that government and industry practitioners should understand and recognize the impact of  
30 these stakeholder and supply chain risk factors prior to and during the implementation of MiC  
31 projects.

1 ***PRF2 - Design and capabilities risks***

2 This PRF explains about 19.33% of the variations in risk profile of MiC projects and scored an  
3 Eigenvalue of 5.411 (Table 4). It comprises nine significant risk factors with a total mean of 29.38  
4 and normalized weighting of 0.390 (Table 5). It has an overall risk level of 3.28 (Figure 4) and  
5 ranked 4<sup>th</sup> among the four PRFs. Based on the nine CRFs under this PRF, the term “design and  
6 capabilities risks” best describe their nature and characteristics (Wuni and Shen 2019c). PRF2  
7 describes the risk factors associated with the design stage and the capabilities (skills) required to  
8 deliver MiC projects. Luo et al. (2015) identified limited MiC expertise and experience (RF10)  
9 and inexperience of contractors in the MiC technology (RF15) as two CRFs in the implementation  
10 of MiC projects in China. Indeed, the unique engineering and installation requirements of MiC is  
11 challenging the traditional knowledge and expertise of contractors (Hwang *et al.* 2018a). The  
12 implementation of MiC requires some technical manufacturing skills and knowledge to ensure  
13 effective management of the projects. However, as MiC is still fledgling in many countries,  
14 contractors are yet to upgrade their skills set to meet the skills requirements of MiC projects, and  
15 thus their limited knowledge and inexperience amount to significant risk in the implementation of  
16 MiC projects (Wuni *et al.* 2019). Geometric and dimensional variability (RF29) constitute a CRF  
17 in MiC projects because intolerances beyond the allowable parameters could trigger expensive  
18 site-fit reworks (Shahtaheri *et al.* 2017, Enshassi *et al.* 2019).

19 Further, late design freeze (RF24) in MiC projects implies a delay in the manufacture of the  
20 components because the modules produced in the workshop are based on the final design (Wuni  
21 *et al.* 2019). This ultimately affects the schedule of MiC projects. In MiC, the modular components  
22 are the key driver of the project. Thus, limited capacity of modular manufacturers or suppliers  
23 (RF21) constitutes a recipe for the shortage of modular components on the jobsite. Where safety  
24 stock or Just-in-Time delivery arrangement is not made, failure to make a timely supply of the  
25 modules to the site will halt the entire installation process (Wuni *et al.* 2019). This will increase  
26 the cost of hired equipment and further trigger expensive schedule delay in the project (Li, Hong,  
27 *et al.* 2018). Wuni et al. (2019) ranked modular design complexity (RF19) and defective design  
28 and change order (RF7) among the top 10 CRFs in the application of MiC projects. Wang et al.  
29 (2018) found that the former (RF19) is a recipe for the latter (RF7). Deficiencies in the modular  
30 design trigger significant differences between modular production and assembly tolerances  
31 (Shahtaheri *et al.* 2017). Such defective design instructs significant alterations to the original

1 design and scope of the MiC projects. However, there is almost zero tolerance for defective design  
2 and change order in MiC projects because the schedules of the workshop production become fixed,  
3 once initiated (Hsu *et al.* 2018). Changes in the scope of MiC projects are challenging to implement  
4 at later stages because there is little flexibility for these late design changes once the design is  
5 frozen. Finally, modular installation errors, complex rectifications and reworks (RF17) constitute  
6 a CRF because error rectification and reworks in MiC projects are prohibitively expensive to  
7 implement. In some cases, reworks require complete recycling and repetition of the entire MiC  
8 supply chain ranging from redesign to reinstallation. These engender significant risks to quality,  
9 cost, schedule, and overall client satisfaction (Wuni *et al.* 2019).

### 10 ***PRF3 - Financing risks***

11 This PRF explains about 7.46% of the variations in the risk profile of MiC projects and scored an  
12 Eigenvalue of 2.088 (Table 4). It comprises three significant risk factors with a total mean of 9.86  
13 and normalized weighting of 0.131 (Table 5). However, it has an overall risk level of 3.34 (Figure  
14 4) and ranked 1<sup>st</sup> among the four PRFs. The FSE analysis identified "financing risks" as the most  
15 critical PRF in the implementation of MiC projects. Although this was not expected because of the  
16 fewer number of CRFs under PRF3, it does indicate that the experts recognize the risk associated  
17 with financing MiC projects to be extremely profound. Under PRF3, higher initial capital cost  
18 (RF2) is considered the most CRF with a weighting of 0.364 (Table 6), followed by diseconomies  
19 of scale and longer break-even period (RF26) with a weighting of 0.332, and higher prices of  
20 modules (RF25) with a weighting of 0.304 (Table 6). Higher initial capital cost becomes even a  
21 more significant risk where there are no readily available modular manufacturers and suppliers. In  
22 this case, clients or developers will have to either import modules from other regions and incur  
23 expensive cross-border transportation costs (Pan and Hon 2018), or they may have to build new  
24 moulds, secure land for factory yards, build manufacturing plants, and warehouses for temporary  
25 storages of the produced modules. These require colossal sums of financing, which might not be  
26 justified in a market with uncertain demand for MiC projects (Hwang *et al.* 2018a).

27 Moreover, the lower demand for MiC projects may expose investors and developers to cost  
28 disadvantages due to diseconomies of scale. This risk is exacerbated because MiC projects take  
29 longer time to break even due to the higher initial capital cost. It is not surprising that the experts  
30 ranked PRF3 as the most critical risk factor grouping because industry practitioners are  
31 conservative and profit-oriented and will not implement technologies which are not tried and

1 tested. Even in cases where modular manufacturers and suppliers are available, studies have shown  
2 that the prices of the modules tend to be high (Li *et al.* 2013, Luo *et al.* 2015, Li, Li, *et al.* 2017).  
3 The higher prices of the modules translate into a higher cost of construction.

#### 4 ***PRF4 - Regulatory risks***

5 PRF4 constitutes the risk factors associated with general building regulations, MiC design codes,  
6 standards, and specification. The "regulatory risks" explains about 5.63% of the variations in the  
7 risk profile of MiC projects and scored an Eigenvalue of 1.576 (Table 4). It comprises two  
8 significant risk factors with a total mean of 6.59 and normalized weighting of 0.087 (Table 5). The  
9 two CRFs under PRF4 are “unsupportive planning and building regulations (RF20)” weighted  
10 0.501 and “lack of MiC design codes and standards (RF6)” weighted 0.499. Although these factors  
11 are only two, their importance cannot be overemphasized because they are directly intertwined  
12 with major sections of the MiC project implementation process, ranging from statutory approval  
13 through to modular design and installation. For instance, if the design of a project lends itself to  
14 modularization and there are readily available project participants with the requisite skills set, the  
15 project might not even be initiated if the building regulations do not support MiC. Thus, any prior  
16 resources and time expended at the conceptual design stage and planning of the project might be  
17 wasted. This often occurs where local authorities and the government do not support the MiC  
18 technology (Mao *et al.* 2014, Luo *et al.* 2015). Thus, it becomes difficult to obtain a planning  
19 permit and statutory approval to proceed with the MiC project implementation process.

20 Furthermore, Wuni *et al.* (2019) ranked lack of MiC design codes and standards (RF20) among  
21 the top 10 CRFs in the application of MiC projects. Building regulations and design codes require  
22 that the design and construction of projects conform to some built environment requirements such  
23 as indoor environmental quality, insulation, comfort, structural integrity, and sustainability. The  
24 absence of MiC design codes and standards means that the completed projects may not meet the  
25 bespoke building regulatory requirement of a region. This could affect the value of the investment  
26 in terms of pricing and demand. The implication is that developers and clients must understand  
27 these regulatory risk factors before the implementation of MiC projects.

#### 28 **Conclusions, contributions, limitations and future research**

29 The unique planning, design, engineering, production, and installation of modular components in  
30 the MiC business model hatch different risk factors which may compromise the practical  
31 realization of project objectives. As MiC continues to become a preferred method of building

1 construction, stakeholders require risk identification and assessment to ascertain the significant  
2 risk factors which may affect MiC projects. This study evaluated 29 risk factors in the  
3 implementation of MiC projects using a 5-point grading scale. A soft computing technique known  
4 as FSE facilitated objective analysis, assessment, and modelling of the subjective responses of  
5 experts from academia and industry in 18 countries and 6 continents. A mean score analysis  
6 generated 23 risk factors with mean scores above the critical threshold. Of these, the top 5 risk  
7 factors with significant impact include poor supply chain integration; higher initial capital cost;  
8 limited MiC expertise and experience; modular installation errors, complex rectifications and  
9 reworks; and stakeholder fragmentation and management complexity. A factor analysis of the 23  
10 CRFs generated a 4-factor solution which clustered the risk factors into stakeholder and supply  
11 chain risks (PRF1); design and capabilities risks (PRF2); financing risks (PRF3); and regulatory  
12 risks (PRF4). The FSE analysis showed that all the factor groupings are critical with indices above  
13 the critical threshold of 3.0 on a 5-point grading scale. The FSE modelling ranked financing risks  
14 as the first and most critical; followed by regulatory risks ranking second; stakeholder and supply  
15 chain risks ranking third; and design and capabilities risks ranking fourth. A FSE model of the  
16 overall risk level generated an overall criticality index of 3.30, indicating that MiC projects have  
17 some significant risk and should be planned extensively before implementation.

18 The quantitative evaluation and ranking of the risk factors have useful practical and managerial  
19 implications in any MiC project. First, the paper accomplished the first three stages of risk  
20 management which include risk planning, identification, and assessment. Thus, it has screened the  
21 risk factors and identified the CRFs, which may significantly derail MiC project success. Although  
22 the magnitude of the impact of the risk factors differs across different MiC project types and  
23 territories, the identified CRFs may be further given detailed quantitative analysis to ascertain the  
24 most CRFs for a given MiC project and territory. This will allow for the efficient allocation of  
25 resources to improve the success of MiC projects. Indeed, the four PRFs identified in the research  
26 may serve as a basis for developing cost-effective risk management guidelines. Second, the risk  
27 assessment conducted in the current study may serve as decision support in investment planning  
28 and decision-making. It provides a preliminary basis to choose between MiC projects and deciding  
29 whether to invest in a given project based on the risk indices. Third, given the identified CRFs,  
30 stakeholders may assess their capabilities of managing the risk events during risk control and  
31 allocation. Fourth, this research constitutes the first exclusive empirical multi-attribute objective

1 risk assessment for MiC projects. The most significant risk factors identified may serve as a risk  
2 evaluation tool at the early stages of an MiC project where bespoke studies are unavailable or not  
3 feasible.

4 However, the results of the study must be examined against the following limitations. First, the  
5 risk factors evaluated in the current study were extracted from empirical studies in the literature  
6 and generalized. Stakeholders, researchers, and practitioners should recognize that MiC risk  
7 factors are sensitive to project types, countries, locations, and objectives. Thus, bespoke studies  
8 may have to be conducted to identify those risk factors relevant to a project and territory. Second,  
9 the analysis identified 6 risk factors as less critical but, these risk factors may constitute the critical  
10 risk factors in different contexts and should be included in initial risk assessment. Third, the study  
11 constitutes a global one but the sample size, although adequate may be considered small. The  
12 generalization may suffer from the limited sample size. However, such a sweeping generalization  
13 is useful for the theoretical progress of MiC risk management because it is often useful to overlook  
14 these project and geospatial sensitivities since they become absolutely essential when such  
15 generalized analysis is tailored towards a specific project for risk management. Third, the study  
16 implemented an FSE analysis of the risk factors, but the method has its own limitations. Future  
17 research may address this methodological limitation by using other methods such as structural  
18 equation modelling, artificial neural networks, systems dynamic, simulation, or fuzzy analytical  
19 hierarchy process to analyse data on the risk factors. The next stage of this research will develop  
20 a robust systems dynamic model of the risks factors to explore their interdependences and  
21 interactions.

## 22 **Data Availability Statement**

23 Some or all data, models, or code generated or used during the study are available from the  
24 corresponding author by request (*Background information of the MiC experts and evaluation of*  
25 *the risk factors for MiC projects*)

## 26 **References**

- 27 Ameyaw, E.E. and Chan, A.P.C., 2015. Evaluation and ranking of risk factors in public-private  
28 partnership water supply projects in developing countries using fuzzy synthetic evaluation  
29 approach. *Expert Systems with Applications*, 42 (12), 5102–5116.
- 30 Brown, T.A., 2015. *Confirmatory Factor Analysis for Applied Research*. 2nd ed. The American  
31 Statistician. New York: The Guilford Press.

- 1 Chen, C., Yu, Y., Osei-Kyei, R., Chan, A.P.C., and Xu, J., 2019. Developing a project  
2 sustainability index for sustainable development in transnational public–private partnership  
3 projects. *Sustainable Development*, (November 2018), 1–15.
- 4 Choi, J.O., O’Connor, J.T., and Kim, T.W., 2016. Recipes for Cost and Schedule Successes in  
5 Industrial Modular Projects: Qualitative Comparative Analysis. *Journal of Construction  
6 Engineering and Management*, 142 (10), 04016055.
- 7 Chou, Y.-M., Polansky, A.M., and Mason, R.L., 1998. Transforming Non-Normal Data to  
8 Normality in Statistical Process Control. *Journal of Quality Technology*, 30 (2), 133–141.
- 9 Construction Industry Council, 2018. About Modular Integrated Construction.
- 10 Egan, J., 1998. *Rethinking construction: The Report of the Construction Task Force*.
- 11 Enshassi, M.S.A., Walbridge, S., West, J.S., and Haas, C.T., 2019. Integrated Risk Management  
12 Framework for Tolerance-Based Mitigation Strategy Decision Support in Modular  
13 Construction Projects. *Journal of Management in Engineering*, 35 (4), 05019004.
- 14 Fang, D.P., Xie, F., Huang, X.Y., and Li, H., 2004. Factor analysis-based studies on construction  
15 workplace safety management in China. *International Journal of Project Management*, 22  
16 (1), 43–49.
- 17 Goulding, J.S., Pour Rahimian, F., Arif, M., and Sharp, M.D., 2015. New offsite production and  
18 business models in construction: priorities for the future research agenda. *Architectural  
19 Engineering and Design Management*, 11 (3), 163–184.
- 20 Hsiao, S.W., 1998. Fuzzy logic based decision model for product design. *International Journal of  
21 Industrial Ergonomics*, 21 (2), 103–116.
- 22 Hsu, P.Y., Angeloudis, P., and Aurisicchio, M., 2018. Optimal logistics planning for modular  
23 construction using two-stage stochastic programming. *Automation in Construction*, 94 (May),  
24 47–61.
- 25 Hwang, B.-G., Shan, M., and Looi, K.-Y., 2018a. Key constraints and mitigation strategies for  
26 prefabricated prefinished volumetric construction. *Journal of Cleaner Production*, 183, 183–  
27 193.
- 28 Hwang, B.-G., Shan, M., and Looi, K.Y., 2018b. Knowledge-based decision support system for  
29 prefabricated prefinished volumetric construction. *Automation in Construction*, 94 (July),  
30 168–178.
- 31 Kim, S., Nussbaum, M.A., and Jia, B., 2011. Low back injury risks during construction with  
32 prefabricated (panelised) walls: Effects of task and design factors. *Ergonomics*, 54 (1), 60–  
33 71.
- 34 Kim, S., Nussbaum, M.A., and Jia, B., 2012. The benefits of an additional worker are task-  
35 dependent: Assessing low-back injury risks during prefabricated (panelized) wall  
36 construction. *Applied Ergonomics*, 43 (5), 843–849.
- 37 Lee, J.S. and Kim, Y.S., 2017. Analysis of cost-increasing risk factors in modular construction in  
38 Korea using FMEA. *KSCE Journal of Civil Engineering*, 21 (6), 1999–2010.



- 1 Li, C.Z., Hong, J., Fan, C., Xu, X., and Shen, G.Q., 2018. Schedule delay analysis of prefabricated  
2 housing production: A hybrid dynamic approach. *Journal of Cleaner Production*, 195, 1533–  
3 1545.
- 4 Li, C.Z., Hong, J., Xue, F., Shen, G.Q., Xu, X., and Mok, M.K., 2016. Schedule risks in  
5 prefabrication housing production in Hong Kong: a social network analysis. *Journal of*  
6 *Cleaner Production*, 134 (Part B), 482–494.
- 7 Li, C.Z., Shen, G.Q., Xue, F., Luo, L., Xu, X., and Sommer, L., 2017. Schedule risk modeling in  
8 prefabrication housing production. *Journal of Cleaner Production*, 153, 692–706.
- 9 Li, C.Z., Xu, X., Shen, G.Q., Fan, C., Li, X., and Hong, J., 2018. A model for simulating schedule  
10 risks in prefabrication housing production: A case study of six-day cycle assembly activities  
11 in Hong Kong. *Journal of Cleaner Production*, 185, 366–381.
- 12 Li, H.X., Al-Hussein, M., Lei, Z., and Ajweh, Z., 2013. Risk identification and assessment of  
13 modular construction utilizing fuzzy analytic hierarchy process (AHP) and simulation.  
14 *Canadian Journal of Civil Engineering*, 40 (12), 1184–1195.
- 15 Li, M., Li, G., Huang, Y., and Deng, L., 2017. Research on Investment Risk Management of  
16 Chinese Prefabricated Construction Projects Based on a System Dynamics Model. *Buildings*,  
17 7 (3), 83.
- 18 Lingard, H. and Rowlinson, S., 2006. Letter to the Editor. *Construction Management and*  
19 *Economics*, 24 (11), 1107–1109.
- 20 Lo, S.M., 1999. A fire safety assessment system for existing buildings. *Fire Technology*, 35 (2),  
21 131–152.
- 22 Luo, L., Mao, C., Shen, L., and Li, Z., 2015. Risk factors affecting practitioners' attitudes toward  
23 the implementation of an industrialized building system a case study from China.  
24 *Engineering, Construction and Architectural Management*, 22 (6), 622–643.
- 25 Luo, L., Shen, G.Q., Xu, G., Liu, Y., and Wang, Y., 2019. Stakeholder-associated Supply Chain  
26 Risks and Their Interactions in a Prefabricated Building Project: A Case Study in Hong  
27 Kong. *Journal of Management in Engineering*, 35 (2), 1–14.
- 28 Mao, C., Shen, Q., Pan, W., and Ye, K., 2014. Major Barriers to Off-Site Construction: The  
29 Developer's Perspective in China. *Journal of Management in Engineering*, 31 (3), 04014043.
- 30 Norusis, M.J., 2008. *SPSS 16.0 Advanced Statistical Procedures Companion*. Upper Saddle River,  
31 NJ.: Prentice-Hall.
- 32 Osei-Kyei, R., Chan, A.P.C., and Ameyaw, E.E., 2017. A fuzzy synthetic evaluation analysis of  
33 operational management critical success factors for public-private partnership infrastructure  
34 projects. *Benchmarking: An International Journal*, 24 (7), 2092–2112.
- 35 Pan, W. and Hon, C.K., 2018. Modular integrated construction for high-rise buildings.  
36 *Proceedings of the Institution of Civil Engineers - Municipal Engineer*, 1–12.
- 37 Project Management Institute, 2017. *A Guide to the Project Management Body of Knowledge*  
38 *(PMBOK Guide)*. 6th Editio. Newton Square, Pennsylvania: Project Management Institute.

- 1 Richard, R.-B., 2006. Industrialize, Flexible and Demountable Building Systems. *In: The*  
2 *CRIOCM 2006 International Symposium on “Advancement of Construction Management*  
3 *and Real Estate” INDUSTRIALISED*,. 1–11.
- 4 Richard, R.B., 2005. Industrialised building systems: Reproduction before automation and  
5 robotics. *Automation in Construction*, 14 (4), 442–451.
- 6 Sachs, T., Tiong, R., and Qing Wang, S., 2007. Analysis of political risks and opportunities in  
7 public private partnerships (PPP) in China and selected Asian countries: Survey results.  
8 *Chinese Management Studies*, 1 (2), 126–148.
- 9 Shahtaheri, Y., Rausch, C., West, J., Haas, C., and Nahangi, M., 2017. Managing risk in modular  
10 construction using dimensional and geometric tolerance strategies. *Automation in*  
11 *Construction*, 83, 303–315.
- 12 Tavakol, M. and Dennick, R., 2011. Making sense of Cronbach’s alpha. *International Journal of*  
13 *Medical Education*, 2, 53–55.
- 14 Velamat, S., 2012. Feasibility, Benefits and Challenges of Modular Construction in High Rise  
15 Development in the United States: A Developer’s Perspective. Massachusetts Institute of  
16 Technology.
- 17 Wang, Z., Hu, H., and Gong, J., 2018. Simulation based multiple disturbances evaluation in the  
18 precast supply chain for improved disturbance prevention. *Journal of Cleaner Production*,  
19 177, 232–244.
- 20 Wuni, I.Y. and Shen, G.Q., 2019a. Towards a Decision Support for Modular Integrated  
21 Construction : An Integrative Review of the Primary Decision-Making Factors. *International*  
22 *Journal of Construction Management*, 1–20.
- 23 Wuni, I.Y. and Shen, G.Q., 2019b. Critical success factors for modular integrated construction  
24 projects: a review. *Building Research & Information Information*, 0 (0), 1–22.
- 25 Wuni, I.Y. and Shen, G.Q., 2019c. Risks Identification and Allocation in the Supply Chain of  
26 Modular Integrated Construction ( MiC ). *In: M. Al-Hussein, ed. Proceedings of the 2019*  
27 *Modular and Offsite Construction (MOC) Summit*. Banff, Alberta, Canada: University of  
28 Alberta, 189–197.
- 29 Wuni, I.Y. and Shen, G.Q., 2019d. Holistic Review and Conceptual Framework for the Drivers of  
30 Offsite Construction : A Total Interpretive Structural Modelling Approach. *Buildings*, 9  
31 (117), 1–24.
- 32 Wuni, I.Y. and Shen, G.Q., 2020. Barriers to the adoption of modular integrated construction :  
33 Systematic review and meta-analysis , integrated conceptual framework , and strategies.  
34 *Journal of Cleaner Production*, 249 (March), 119347.
- 35 Wuni, I.Y., Shen, G.Q., and Mahmud, A.T., 2019. Critical risk factors in the application of modular  
36 integrated construction: a systematic review. *International Journal of Construction*  
37 *Management*, 1–15.
- 38 Xu, Y., Chan, A.P.C., and Yeung, J.F.Y., 2010. Developing a Fuzzy Risk Allocation Model for  
39 PPP Projects in China. *Journal of Construction Engineering and Management*, 136 (8), 894–

- 1           903.
- 2   Zadeh, L.A., 1965. Fuzzy Sets. *Information and control*, 8, 338–353.
- 3   Zadeh, L.A., 1975. The concept of a linguistic variable and its application to approximate  
4       reasoning—II. *Information Sciences*, 8, 199–249.
- 5   Zafar, I., Wuni, I.Y., Shen, G.Q., Ahmed, S., and Yousaf, T., 2019. A fuzzy synthetic evaluation  
6       analysis of time overrun risk factors in highway projects of terrorism-affected countries: the  
7       case of Pakistan. *International Journal of Construction Management*, 0 (0), 1–19.
- 8   Zhang, X., 2005. Critical success factors for public-private partnerships in infrastructure  
9       development. *Journal of Construction Engineering and Management*, 131 (1), 3–14.