

This version of the article has been accepted for publication, after peer review (when applicable) and is subject to Springer Nature's AM terms of use (<https://www.springernature.com/gp/open-research/policies/accepted-manuscript-terms>), but is not the Version of Record and does not reflect post-acceptance improvements, or any corrections. The Version of Record is available online at: <http://dx.doi.org/10.1007/s42524-019-0059-7>

1 Risks of Modular Integrated Construction: A Review and Future 2 Research Directions

3 Ibrahim Yahaya Wuni^{1*}, Geoffrey Qiping Shen², Bon-Gang Hwang³

4
5 ¹Department of Building and Real Estate, The Hong Kong Polytechnic University, 11 Yuk Choi Road, Hung Hom,
6 Kowloon, Hong Kong

7 Corresponding Author's Email: ibrahim.wuni@connect.polyu.hk

8
9 ²Department of Building and Real Estate, The Hong Kong Polytechnic University, 11 Yuk Choi Road, Hung Hom,
10 Kowloon, Hong Kong

11
12 ³Department of Building, National University of Singapore, 4 Architecture Drive, 117566, Singapore

13
14 **Abstract:** Despite the extensively documented benefits of modular integrated construction (MiC),
15 stakeholders continue to remain sceptical in its adoption due to the associated risks and uncertainties. The
16 unique business model of MiC nurtures several risks and uncertainties different from those of the
17 conventional construction approach. Although MiC is gaining attention with its market expansion, there is
18 no systematic evaluation of the research progress. This research conducted a systematic review and
19 synthesis of published studies on the risks of MiC from 1992 to 2019 inclusive. The analysis reveals that
20 the research publications on risks of MiC witnessed a steady growth, with significant progress occurring in
21 the last decade. This implies that the risk of MiC has gained more attention in the construction engineering
22 and management domain in recent times. Existing empirical studies have focused more on *perceived*
23 *implementation risks; supply chain risks; schedule risks; investment risks; structural risks; ergonomic*
24 *risks; and MiC risk management strategies*, which indicates that MiC is associated with a host of risk
25 events. The paper further identified the critical risk events (CREs) in the application of MiC based on
26 frequency of occurrence. The identified CREs contribute to the checklists of risk events in the
27 implementation of offsite construction, which may be useful in risk planning especially where the MiC
28 market is still fledgling, and fewer or no bespoke risk assessment exist. The paper highlighted research gaps
29 in existing studies and proposed areas for further studies. Thus, the paper makes a useful contribution to
30 the scholarly literature on the risk of OSC and maybe useful to offsite construction researchers, industry
31 practitioners, and project managers.

32 **Keywords:** modular integrated construction, risk, supply chain, uncertainties

33 1. Introduction

34 Industrialization of construction is pursued to address the manifold ill-performances of the
35 traditional business model of the construction sector. Richard (2005) argued that industrialized
36 construction could increase the efficiency and productivity of the construction industry like those
37 of the manufacturing industry. Offsite construction (OSC) is one of the approaches to industrialize
38 the construction sector. OSC is a construction production process which shifts preponderances of
39 the trades in the traditional cast-in-situ construction (TCC) approach to an offsite factory, resulting
40 in the fabrication of building components which are then transported to a construction site for final
41 assembly and installation (Gibb 2001, Pan and Goodier 2012). Modular integrated construction
42 (MiC) is a distinctive form of OSC where 80-95% of a whole building can be manufactured in an
43 offsite factory environment (Smith 2016). MiC reduces construction time due to the concurrent
44 offsite and onsite activities, minimizes labor cost owing to the stable factory labor force, quickens
45 the learning curve due to the repetitive works (Murtaza *et al.* 1993), reduces project lifecycle cost
46 (Blismas *et al.* 2006), improves project adaptability, supports change without demolition (Richard
47 2005), reduces construction waste and water footprint (Jaillon and Poon 2008, Jaillon *et al.* 2009),
48 and reduces greenhouse gas emissions (Mao *et al.* 2013). Thus, MiC is considered a cleaner,
49 innovative and sustainable construction approach (Quale *et al.* 2012).

50 Due to these benefits, models of MiC are promoted in Australia, Canada, USA, UK, Singapore,
51 Sweden, Korea, China, and Malaysia such as off-site manufacture, modular construction, prework,
52 off-site production, prefabricated prefinished volumetric construction, industrialized housing
53 construction, and industrialized building systems. However, MiC is associated with a unique
54 supply chain, stakeholder composition, procurement model, engineering process and management
55 requirement (Wuni, Shen, and Mahmud 2019) resulting in significant risks and uncertainties
56 different from those of the TCC (Li *et al.* 2013). For instance, the application of MiC demands
57 modular design, manufacturing, transportation, storage, and onsite installation. These segments of
58 the MiC supply chain are currently fragmented but substantially interdependent, resulting in
59 manifold uncertainties which could derail the success of MiC projects (Li *et al.* 2016). As these
60 linked segments constitute nearly a fixed and unique linear sequence with minimal overlapping,
61 disturbances in upstream segments may affect the continuity of downstream segments or the entire

62 supply chain (Wang *et al.* 2018a). For instance, too early delivery of modular components requires
63 storage space whereas delays in the delivery of modules to the site may halt the entire installation
64 process (Li, Hong, *et al.* 2018). Also, failure of modular production plants may directly translate
65 into delays in modular delivery and a shortage of modular components on the construction site
66 since third-party modular manufacturers cannot complement the deficit with different components.


67 Again, problematic dimensional and geometric variabilities in modular elements in MiC
68 projects abound and constitute recipes for defects and expensive reworks (Shahtaheri *et al.* 2017).
69 According to the Bureau of Labor Statistics (Bureau of Labor Statistics 2009), construction
70 workers in residential MiC projects in the United States are exposed to higher rates of injuries and
71 risk of work-related musculoskeletal disorders (WMSDs), compared to the rates in the TCC. These
72 uncertainties and risk events translate into barriers to the adoption of MiC as some of them are
73 counterproductive to the benefits of the approach. Despite these uncertainties and risks events,
74 MiC is gaining attention with its market expansion in the Architecture, Engineering, and
75 Construction (AEC) industry. As risk is inevitable in construction projects (Baloi and Price 2003),
76 there is a growing body of studies seeking to understand the risks and uncertainties associated with
77 MiC. However, a systematic review of these empirical studies has not been well established,
78 although it is essential to monitor the progress of studies on the risk of MiC and to bridge the gap
79 between empirical studies, and practical risk management. Hosseini *et al.* (2018) conducted a
80 scientometric review of studies on OSC and Li *et al.* (2014) offered a critical review of studies on
81 the management of MiC projects. However, these studies were generic and offered very little or
82 no documentation of the risks of MiC.

83 Thus, this research conducts a systematic review and synthesis of empirical studies on the risk
84 of MiC. Specifically, the study aims to: (1) examine the research publications trend on the risks of
85 MiC, (2) identify the emerging salient research areas on the risk of MiC, (3) highlight the critical
86 risks events (CREs) in MiC, (4) propose a risk breakdown structure of MiC, and (5) highlight the
87 areas that require further studies. By doing so, the paper makes a useful contribution to the
88 scholarly literature on OSC as it represents the first exclusive review and synthesis of studies on
89 the risk of MiC. Particularly, the paper delineates the knowledge boundaries in existing studies,

90 highlights some research gaps and proffers directions for future studies. The paper highlights some
 91 critical risk events in MiC. These contribute to the checklists of the risk events in OSC and may
 92 be prioritized in the implementation of MiC, especially in countries where bespoke MiC risk
 93 assessment are not available. A risk breakdown structure is also developed to offer a bird’s eye
 94 view of the risk structure of MiC. As such, this paper is relevant to OSC researchers, developers,
 95 project managers, teaching staff, policymakers, and industry practitioners. The remainder of the
 96 paper is structured as follows. The next section offers an overview of MiC, followed by a
 97 description of the research methodology. The paper then offers discussions of the review findings
 98 and finally, draws logical conclusions based on the findings.

99 **2. Overview of modular integrated construction (MiC)**

100 Modular integrated construction (MiC) is a construction technique whereby “free-standing
 101 integrated modules (completed with finishes, fixtures, and fittings) are manufactured in a
 102 prefabrication factory and then transported to site for installation in a building” (Hong Kong
 103 Buildings Department 2018). Smith (2016) describes MiC as the most complete form of OSC.
 104 Based on the degree of modularization, Gibb (1999) describes the four (4) levels of MiC as
 105 components manufacture and subassembly (e.g. windows), non-volumetric preassembly (e.g.
 106 cladding panels), volumetric preassembly (e.g. toilet pods and complete modular building (e.g.
 107 modular home). Fig. 1 shows the major stages in the modular integrated construction process.



115

116

117

Fig. 1. Stages of the modular integrated construction process

118 The supply chain of MiC can be simplified as modular design, engineering, manufacturing,
119 transportation, storage (and/or buffer) and onsite installation (Li *et al.* 2016). These involve several
120 stakeholders including main contractors, assembly subcontractors, manufacturers, suppliers,
121 architects, engineers, site engineer, developers, housebuilders, designers, clients, consultants,
122 academics, transporters, logistics managers, project coordinators, and local government (Li *et al.*
123 2016, Bortolini *et al.* 2019). Nam and Tatum (1997) described these stakeholders as leaders and
124 champions of construction innovation. These multidisciplinary practitioners and professionals
125 have their unique goals and value systems within the MiC supply chain, engendering increased
126 complexity in coordinating and managing the involved stakeholders in MiC projects (Luo *et al.*
127 2019).

128 MiC often follows the design for manufacturing and assembly (DfMA) philosophy (Hsu *et al.*
129 2018), and engineer-to-order manufacturing process (Dawood 1995a, 1995b, Bortolini *et al.*
130 2019). Typically, modular components are made-to-order and designed to be used exclusively in
131 a specific project. As such, the quantity of each manufactured modular component is engineered
132 to precisely match the optimum quantity demanded to complete the MiC project and thus, the
133 inventory must return to zero at the end of the project (Hsu *et al.* 2018). Due to this, the onsite
134 modular demand deficit cannot be satisfied by a third-party manufacturer. This unique production
135 scheduling individuates the MiC supply chain from that of the TCC, resulting in layers of new
136 uncertainties in the construction process. The resulting MiC project could be permanent or
137 temporary (Smith 2016). However, the products are industrialized building systems rather than
138 standardized buildings. Richard (2005) indicated that the goal of MiC is to manufacture
139 industrialized building systems where the same details generate diversified and adaptable
140 individualized buildings which can be situated in different areas. Models of MiC include
141 prefabricated prefinished volumetric construction in Singapore, industrialized building systems in

142 Malaysia, and PPMOF- prefabrication, preassembly, modularization, and off-site fabrication in
143 North America, etc.

144 **3. Research methods**

145 This paper adopted a pragmatist research paradigm to review empirical studies on the risks of MiC.
146 The pragmatist stance allowed for the synthesis of both empirical qualitative and quantitative
147 studies. In doing so, the systematic literature review (SLR) methodology was deployed. SLR is a
148 powerful scientific method which adopts a systematic, and objective protocol in synthesizing
149 knowledge on a subject (Webster and Watson 2002, Levy and Ellis 2006). Due to the organic
150 attribute of literature, SLR is widely adopted to delineate the boundaries of scientific knowledge
151 in the construction engineering and management (CEM) research domain (e.g. Wuni and Shen
152 2019, Wuni, Shen, and Mahmud 2019). Similarly, this paper adopted the SLR to review studies
153 on the risks of MiC based on a comprehensive methodological framework comprising systematic
154 literature search, critical appraisal, meta-synthesis, and content analysis.


155 ***3.1 Database selection and literature search***

156 An SLR must be underpinned by a thorough, and unbiased search for relevant studies (Evans
157 2004). To ensure wider coverage of the relevant studies, this research initiated the search process
158 by specifying databases rather than journals. As such, the most powerful CEM databases and
159 libraries comprising Elsevier's Scopus, Clarivate Analytics' Web of Science, ASCE library,
160 Engineering Village, Taylor and Francis, and Emerald Insight were examined to identify the one
161 with the widest coverage. Preliminary searches revealed that preponderances of the articles were
162 contemporaneously indexed in nearly all the databases, but Scopus had the highest coverage. Wuni
163 et al. (2019) made a similar observation in a scientometric review. As such, Scopus was mainly
164 adopted in the literature retrieval process. Prior to the search query in Scopus, synonyms for 'risk'
165 and 'MiC' were extracted from the extant literature. The keywords were updated and refined
166 throughout the review process to ensure the widest possible coverage. The implemented full
167 Scopus search algorithm is shown below.

168 *(TITLE-ABS-KEY (risk OR hazard OR uncertainty OR uncertainties OR safety OR delay OR*
169 *"cost overrun" OR "time overrun") AND TITLE ("offsite construction" OR "off-site construction"*

170 OR "offsite production" OR "off-site production" OR "offsite manufacturing" OR prefabrication
 171 OR prefabricated OR prefab OR pre-fabricated) OR TITLE ("industrialized building system" OR
 172 "modular construction" OR modular OR "precast construction" OR "off-site fabrication" OR
 173 "prefabricated prefinished volumetric construction" OR "modern method of construction" OR
 174 "industrialized construction")) AND (LIMIT-TO (DOCTYPE, "ar") OR LIMIT-TO (DOCTYPE,
 175 "ip")) AND (LIMIT-TO (LANGUAGE, "English")) AND (LIMIT-TO (SRCTYPE, "j"))

176 Some of the keywords for MiC has been repeated in the algorithm but spelled differently
 177 because such spelling variations were observed during the review process. The algorithm is a
 178 structured but constrained search string. The *Document type* was restricted to "Article" and
 179 "Article in Press"; the *Source type* was restricted to only "journals" and the *Language* was limited
 180 to only "English". These restrictions generated 1,164 Scopus records (as of 15 February 2019).
 181 These were screened to identify relevant articles. Also, the Scopus search was repeated
 182 immediately prior to submission (9 April 2019) to retrieve new relevant articles. As a result, three
 183 (3) additional articles were retrieved, evaluated and included.



Please Cite As: Wuni, I.Y., Shen, G.Q. and Hwang, B. (2020), "Risks of modular integrated construction: A review and future research directions", *Frontiers of Engineering Management*, Vol. 7 No. 1, pp. 63–80.

198
199
200
201
202
203
204
205
206
207

Fig. 2. Flowchart of systematic search and article selection protocol

209

3.2 Inclusion and exclusion criteria

210
211 Wohlin (2014) noted that inclusion and exclusion criteria constitute the benchmarks used in an
212 SLR for filtering the actual sample size from the universe of articles in search queries. As such,
213 the research specified some inclusion and exclusion criteria to screen the articles. The inclusion
214 criteria were: (i) the paper should be an empirical study on the risks of MiC, and (ii) published in
215 a peer-reviewed journal. Conference papers were not included since they do not go through a
216 rigorous peer-review process. Articles were selected based on metadata (title and abstracts)
217 screening and full-text evaluations.

218 **Table 1.** Bibliographic summary of the included studies

S.N.	Reference	S.N.	Reference
1	Gustavsson <i>et al.</i> (1992)	28	Li, Shen, <i>et al.</i> (2017)
2	Dawood (1995a)	29	Li, Zhong, <i>et al.</i> (2017)
3	Dawood (1995b)	30	Li, Li, <i>et al.</i> (2017)
4	Gibb and Neale (1997)	31	Love <i>et al.</i> (2017)
5	Chiang <i>et al.</i> (2006)	32	Salama <i>et al.</i> (2017)
6	Hassim <i>et al.</i> (2008)	33	Shahtaheri <i>et al.</i> (2017)

7	Polat (2008)	34	Jiang <i>et al.</i> (2017)
8	Hassim <i>et al.</i> (2009)	35	Xue <i>et al.</i> (2017)
9	Nahmens and Ikuma (2009)	36	Jiao and Li (2018)
10	Blismas and Wakefield (2009)	37	Jiang <i>et al.</i> (2018)
11	Kim <i>et al.</i> (2011)	38	Lin <i>et al.</i> (2018)
12	Ikuma <i>et al.</i> (2011)	39	Li, Hong, <i>et al.</i> (2018)
13	Kim <i>et al.</i> (2012)	40	Li, Xu, <i>et al.</i> (2018)
14	Azman <i>et al.</i> (2013)	41	Havinga and Schellen (2018)
15	Chiu <i>et al.</i> (2013)	42	Hwang <i>et al.</i> (2018)
16	Li <i>et al.</i> (2013)	43	Ji <i>et al.</i> (2018)
17	James <i>et al.</i> (2014)	44	Gan <i>et al.</i> (2018)
18	Rahman (2014)	45	Hsu <i>et al.</i> (2018)
19	Zhai <i>et al.</i> (2014)	46	Taghaddos <i>et al.</i> (2018)
20	Mao <i>et al.</i> (2014)	47	Xue <i>et al.</i> (2018)
21	Luo <i>et al.</i> (2015)	48	Wang <i>et al.</i> (2018a)
22	Li <i>et al.</i> (2016)	49	Wang <i>et al.</i> (2018b)
23	Segura <i>et al.</i> (2016)	50	Li <i>et al.</i> (2019)
24	Adekunle and Nikolopoulou (2016)	51	Luo <i>et al.</i> (2019)
25	Fard <i>et al.</i> (2017)	52	Wu <i>et al.</i> (2019)
26	Hong <i>et al.</i> (2017)	53	Bortolini <i>et al.</i> (2019)
27	Lee and Kim (2017)	54	Enshassi <i>et al.</i> (2019)

219 Following a rapid screening of the 1,164 Scopus records, 125 articles were deemed valid for
220 full-text evaluations. After the full-text evaluation, 38 articles were included. Fig. 2 is a flowchart
221 of the article screening process. Although the sample size (38) compares favorably with previous
222 CEM reviews such as 16 (Newaz *et al.* 2018) and 32 (Saieg *et al.* 2018), the snowballing search
223 strategy was adopted to further locate relevant articles.

224 The ‘snowballing’ search strategy was adopted as Wohlin (2014) noted that the algorithm-
225 driven search string alone is not adequate due to the impracticality of specifying exhaustive
226 keywords in the search string. Snowballing search refers to a strategy of using reference lists and
227 citations of a paper to locate additional studies (Wohlin 2014). It involves searching the references
228 (backward snowballing) and tracking the citations (forward snowballing) of an article to locate
229 additional studies. Based on the recommendations of Levy and Ellis (2006) and Wohlin (2014),
230 the 38 articles constituted the sample set for the snowballing search. The authors conducted
231 backward, and forward snowballing searches using these articles. Given the iterative nature of the

232 snowballing search, Webster and Watson (2002) and Levy and Ellis (2006) suggested that the
233 search should be aborted when: (i) new findings are not emerging from the newly retrieved articles,
234 (ii) no different citations are discovered in the newly retrieved articles, and (iii) the articles cited
235 in newly retrieved articles have been evaluated. Thus, the authors aborted the iterative search based
236 on these realizations. This resulted in the inclusion of ten (12) additional relevant articles,
237 increasing the actual sample size to 54. Table 1 shows a bibliographic summary of the included
238 studies.

239 ***3.3 Meta-synthesis and content analysis***


240 The paper adopted meta-synthesis as the organizing framework for extracting and integrating the
241 metadata of the 54 empirical studies. Meta-synthesis is a mixed method of conducting SLR which
242 draws on both qualitative and quantitative studies (Baker 2016). It starts with the specification of
243 units of analyses and extraction of metadata (Finfgeld-Connett 2014). For each study, year of
244 publication, journal name, research focus and limitations of the study were extracted and
245 cataloged. These were organized into an excel file as a summary table based on the units of
246 analyses. Webster and Watson (2002) described this summary table as a concept matrix augmented
247 with units of analyses. A systematic approach was further used to cluster the studies into various
248 research themes based on the emphasis of each study. This method is described as a content
249 analysis (Finfgeld-Connett 2014). It provides an organizing framework to identify emerging trends
250 from larger volumes of literature. The content analysis formed the basis of identifying the main
251 research topics in previous studies and was relied upon in developing the current and future
252 research framework.

253 **4. Review findings and discussions**

254 ***4.1 Annual research publications trend on the risks of MiC***

255 The articles included in the review spanned from 1992 to 2019, although there was no ‘date range’
256 restriction during the search. This suggests that risk of MiC has been recognized in the CEM field
257 since the last three decades. Fig. 3 shows the annual research publications trend on the risks of
258 MiC from 1992 to 2019. No trend is observed between 1992 and 2009 since an average of 1 article
259 was published annually. However, the period 2009-2019 recorded a steady growth of publications
260 on the risks of MiC. Notably, the highest number of articles (14) was recorded in 2018. This is

261 expected because the last decade witnessed a renaissance of the OSC movement and a concomitant
 262 renewed commitment to the promotion of MiC in many countries (Wuni and Shen 2019). The
 263 rising trend suggests that the risk of MiC is gaining increasing research attention in the AEC
 264 industry (Li *et al.* 2014). As such, this study is timely and useful because when risks become
 265 reality, they can derail the performance of MiC projects (Baloi and Price 2003, Jiang *et al.* 2018).



266
 267 **Fig. 3.** Annual publications trend on the risk of MiC from 1992 to 2019 inclusive
 268

269 **4.2 Journal distribution of the included studies**

270 The included studies were published in 27 journals. Table 2 shows the journals with publications
 271 on the risk of MiC. It is useful to highlight the active journals involved in the publication of studies
 272 on the risk of MiC as this will offer a cursory view of the quality of studies included in the review.
 273 These journals may also serve as a reference point to researchers when deciding to submit future
 274 studies on the risks of MiC for publication. Of twenty-seven journals, nine contributed at least 2
 275 articles. These included *Journal of Cleaner Production* (20.4%), *Automation in Construction*
 276 (13.0%), *Journal of Management in Engineering* (7.4%), *Building and Environment* (5.6%),
 277 *Journal of Construction Engineering and Management* (5.6%), *Journal of Architectural*

278 *Engineering* (3.7%), *Journal of Civil Engineering and Management* (3.7%), *Construction*
 279 *Management and Economics* (3.7%) and *Sustainability* (3.7%). These journals cumulatively
 280 published 36 (66.7%) of the 54 included studies. The rest of the journals contributed 1 article each
 281 and collectively contributed 18 (33.3%) of the included studies. Owing to the environmental
 282 friendliness of MiC (Quale *et al.* 2012, Mao *et al.* 2013), it is not surprising that a superior
 283 contribution is made by the *Journal of Cleaner Production* since sustainability is one of its core
 284 missions.

285 **Table 2.** Active journals on the risk of MiC studies

Name of Journal	Number of Articles (N=52)
Journal of Cleaner Production	11
Automation in Construction	7
Journal of Management in Engineering	4
Building and Environment	3
Journal of Construction Engineering and Management	3
Journal of Architectural Engineering	2
Journal of Civil Engineering and Management	2
Construction Management and Economics	2
Sustainability (Switzerland)	2
Construction innovation	1
American Journal of Applied Sciences	1
American Journal of Industrial Medicine	1
Applied Sciences (Switzerland)	1
Applied Ergonomics	1
Archives of Civil Engineering	1
Buildings	1
Canadian Journal of Civil Engineering	1
Engineering, Construction and Architectural Management	1
Ergonomics	1
European Journal of Social Sciences	1
Habitat International	1
International Journal of Advanced Manufacturing Technology	1
International Journal of Injury Control and Safety Promotion	1
Lean Construction Journal	1
Journal of Performance of Constructed Facilities	1
KSCE Journal of Civil Engineering	1

286 Also, MiC improves possible automation in the construction process (Richard 2005,
287 Shahtaheri *et al.* 2017) and thus, it is justifiable that a relatively higher number of the articles have
288 been published in *Automation in Construction*. Finally, articles related to ergonomic exposure and
289 risks of WMSDs (Kim *et al.* 2011), low back injury (Kim *et al.* 2012) and safety of construction
290 workers in MiC projects (Fard *et al.* 2017) were published in journals such as *Ergonomics*, *Applied*
291 *Ergonomics*, and *the International Journal of Injury Control and Safety Management*,
292 respectively.

293 **4.3 Analysis of the salient research topics in existing studies**

294 It is recognized that the classification of studies into major research areas is subjective. However,
295 it was observed that preponderances of the studies identified, and assessed risk events in MiC. The
296 main difference in the studies was the category of risks the authors investigated. As such, it was
297 deemed prudent to cluster the studies based on the forms of risks. Although useful, the
298 classification is for reference only. Some articles discussed more than one identified theme and in
299 such a case, the paper is discussed according to the best-fit research area. The content analysis
300 revealed seven major research themes: (i) implementation risks, (ii) supply chain risks, (iii)
301 schedule risks, (iv) investment risks, (v) structural risks, (vi) ergonomic risks, (vii) risks
302 management strategies. Table 3 shows the seven major themes, the associated sub-themes and
303 percentages of the articles addressing each theme.

304 **4.3.1 Implementation risks**

305 MiC is considered innovation because it involves significant changes to the traditional project
306 design, procurement, scope and interfaces of the construction process (Slaughter 1998). These
307 changes introduce new layers of uncertainties in the construction process and expose decision
308 makers to new challenges (Luo *et al.* 2015). As an innovative technology, MiC is facing significant
309 resistance from industry practitioners as it requires changes to entrenched construction practices
310 (Lovell and Smith 2010). Studies have shown that MiC is stereotyped by stakeholders as a risky
311 approach owing to the perceived increased complexity in project delivery resulting from the
312 manifold trades and stakeholders to be coordinated (Lovell and Smith 2010, Xue *et al.* 2018).

313 Hassim et al. (2008) found that contractors in Malaysia associated the perceived riskiness of MiC
 314 to insufficient experience, design complexity, and contractor performance failure.

315 **Table 3.** Percentages of paper addressing the seven major research themes

Research theme	Sub-themes	% of papers
Implementation risks	MiC adoption risks; risks perceptions; sources of risks; implementation uncertainties; perceived barriers; project failures; MiC project management problems	9
Supply chain risks	Stakeholder management risks; fragmented and complex network of stakeholders; complex coordination of supply chain stages; supply chain management constraints; complexity in optimal supply chain configuration; supply chain disturbances	19
Schedule risks	MiC project delays; modular components delivery delays; scheduling uncertainties; schedule delays risk events; components assembly challenges	10
Investment risks	Higher setup capital; longer break-even periods; market demand for modular homes; volatile economic conditions; public consumption habits	6
Structural risks	Complexity in structural design for high risk MiC projects; structural integrity issues; vertical connections of modular components; complex multi-interfaces; dimensional and geometric tolerances; multi-hazard design; stable seismic performance; structural resilience; gravitational load of floor slabs; eccentricities; deterioration of components; dampness	13
Ergonomic risks	Health and safety of factory workers; fall injuries; low back pains; awkward working postures; spinal comprehensive and shear forces; fatigue; work-related musculoskeletal disorders	15
Risks management strategies	Time and space hedging; integrated building information modelling platforms; smart construction monitoring; integrated project delivery; stakeholder collaborative management; optimal supply chain configuration; tolerance risk management; automated ergonomic risk management; lean production and management	29

316 Hassim et al. (2009) further reported that work changes, defective design, changes in government
 317 regulation, contractor inexperience, and payment problems represent the top five (5) sources of
 318 risks in MiC in Malaysia. Some of these risk perceptions (e.g. complex project delivery) may be
 319 due to inexperience and insufficient knowledge of the MiC business model because the goal of the

320 approach is to simplify the construction process (Richard 2005). Notwithstanding, Nussbaum et
321 al. (2009) opined that due to the complex parade of trades, and the extensive fragmented discrete
322 events, MiC is associated with manifold risks and uncertainties. Luo et al. (2015) reported that
323 poor cooperation between multi-interface, inadequate design codes and standards, lack of best
324 management practices, higher initial capital cost, and lack of quality monitoring mechanisms
325 constitute the five (5) critical risk factors that breed the reluctance to adopt MiC in China. As the
326 MiC industry is still fledgling in some countries (e.g. China), Jiang et al. (2018) found that failure
327 of demonstration projects, limited capacity of modular manufacturers and inexperience account
328 for the perceived riskiness of MiC. Essentially, these risk perceptions make MiC unattractive to
329 stakeholders.

330 **4.3.2 Supply chain risks**

331 The supply chain of MiC involves modular design, manufacturing, transportation, storage, and
332 onsite assembly. These linked segments are currently fragmented, resulting in uncertainties at each
333 level of the continuum (Li *et al.* 2013). Hwang et al. (2018) stated that the application of MiC
334 requires extensive coordination of the supply chain segments and involved stakeholders prior to
335 and during the construction process. As such, several decisions and trade-offs are made under
336 uncertainties at various segments of the supply chain. At the initial design phase, the justification
337 to apply MiC in a project is grounded on multiple factors, which are also project and context-
338 dependent (Murtaza *et al.* 1993). For example, the decision to adopt MiC in the One Ludgate Place
339 in London was based on cost, time, past experience, design, structural interface, weather joints,
340 performance tests, site logistics and safety (Gibb and Neale 1997) whereas a decision to apply MiC
341 in a power plant project was based on plant location, labor, environmental consideration, project
342 characteristics and risk profile (Murtaza *et al.* 1993). These differences in decision factors
343 introduce bespoke uncertainties, which are unique to a project during the feasibility and economic
344 analysis. Meanwhile, these decisions at the conceptual design stage of MiC projects are
345 indispensable because changes are obscure to implement during construction (Shahtaheri *et al.*
346 2017).

347 Again, modular manufacturing operations are often based on engineer-to-order owing to the
348 uniqueness of each MiC project (Bortolini *et al.* 2019). The bidding decisions of modular
349 manufacturers require a precise valuation of the optimal mark-up on price based on design and
350 production planning of every MiC project (Dawood 1995a). Such decisions are made in the context
351 of uncertainties. Even the selection of a location for a modular production factory depends on
352 multiple factors such as costs, transportation, land accessibility, availability of raw materials and
353 infrastructure (Azman *et al.* 2013). Essentially, the optimal configuration of the entire supply chain
354 is required to minimize extreme uncertainties, disruptions, and disturbances during the
355 construction process (Shahtaheri *et al.* 2017). As modular components are specific to a project and
356 made-to-order, logistical planning in MiC must ensure that the quantity of components produced
357 in a factory precisely match the onsite modular demand, allowing the inventory to become empty
358 on completion of the project (Hsu *et al.* 2018). This unique scheduling and procurement
359 configuration require the consideration of multiple schedule deviation factors and disturbances
360 along the entire supply chain. Owing to the interdependences of the supply chain segments (Li,
361 Hong, *et al.* 2018), disturbances within one segment could compromise the reliability of the entire
362 supply chain. For instance, modular production system failure, and defects in modular components
363 may halt the onsite installation process, especially when there is no safety stock (Wang *et al.*
364 2018a). The impacts of these supply chain disturbances are pronounced because their causes
365 cannot be anticipated until they occur (Wang *et al.* 2018a).

366 Furthermore, the MiC supply chain is dominated by multidisciplinary stakeholders such as
367 designers, architects, engineers, manufacturers, transporters, logistics managers, main contractors,
368 assembly subcontractors, site engineers, project managers and local government (Li *et al.* 2016,
369 Bortolini *et al.* 2019). Each practitioner or stakeholder has an exclusive motive and value system
370 within the supply chain. Coordination of the interests and value systems of the multiple involved
371 parties introduces new layers of uncertainties and risks in the construction process (Li, Shen, *et al.*
372 2017). The fragmented and complex MiC stakeholder composition may result in poor resources
373 planning and scheduling, workflow control, and information sharing among project stakeholders
374 (Luo *et al.* 2019). For instance, the separate dominance of different stakeholders in the planning
375 and control of each of the linked supply chain segments may increase the lead time of MiC projects

376 (Bortolini *et al.* 2019). Again, failure in upstream segments of the supply chain has detrimental
377 implications on the reliability of downstream segments.

378 **4.3.3 Schedule risks**

379 Project delay occurs when a completion date of a project extends beyond the stipulated contractual
380 duration (Assaf and Al-Hejji 2006). project delays are inevitable in the construction sector (Egan
381 1998). Ji *et al.* (2018) found that inadequate worker experience, inefficient modular components
382 connection, poor stakeholder management, and low productivity constitute some of the most
383 critical causes of delays in MiC projects. It should be reiterated that schedule delays constitute one
384 of the causes of MiC project delays (Li, Hong, *et al.* 2018). As modular components are made-to-
385 order, modular production often requires job shop scheduling to optimize the allocation of
386 resources and facilitate timely modular delivery (Dawood 1995b). However, job shop scheduling
387 is sensitive to fluctuations in sales, cost, and volume of modules, cost of changeovers, margins of
388 profit and curing time (Dawood 1995b). These also depend on modular plant characteristics,
389 attributes of modules, scheduling shift patterns, demand forecast, and dispatch information (*ibid.*).
390 These nurture multiple uncertainties and risks in the modular scheduling process. Beyond the
391 scheduling stage, there are several events which may cause schedule delays in MiC projects. For
392 instance, wind disruptions resulted in 18 days lost time during the installation of complex
393 prefabricated cladding in the One Ludgate Place in London (Gibb and Neale 1997).

394 Similarly, Hsu *et al.* (2018) found that weather disruptions, delays in modular delivery, and
395 crane failure resulted in significant schedule delays in MiC projects in the UK. Moreover, design
396 information gap between designer and manufacturer, inefficient design approval, ineffective
397 design data transition, inefficient verification of modules, delays in modular delivery, low
398 information interoperability between different information management tools, modular installation
399 errors and tower crane malfunction were found to be the most critical schedule delay risk factors
400 in residential MiC projects in Hong Kong (Li *et al.* 2016, Li, Shen, *et al.* 2017, Li, Hong, *et al.*
401 2018). These information and stakeholder-driven risk events resulted in 200-300min delays in the
402 six-day cycle assembly of MiC projects in Hong Kong (Li, Xu, *et al.* 2018). Although the schedule

403 risk factors may differ across projects and regions, the review reveals that there a host of events
404 which could trigger schedule delays in MiC projects.

405 **4.3.4 Investment risks**

406 The application of MiC in a project requires reliable production and supply of modular
407 components. Thus, the adoption of MiC in a country requires significant investment from
408 stakeholders. Huge capital is required to purchase land for the offsite factory, the manufacturing
409 plant, production equipment, raw materials, and labor (Zhang *et al.* 2014). The capital-intensive
410 profile of MiC exposes investors to manifold uncertainties and risks, as it could take several years
411 to break-even. Studies have identified some MiC investment risk factors. Li, Li, et al. (2017) found
412 that high price of modular components, conservative public consumption habit, inadequate
413 modular codes and lack of cutting-edge modular production technologies constitute the most
414 critical investment risk factors in China. Li et al. (2013) found that volatile economic conditions
415 and sociopolitical climate are the most important investment risk factors in Canada. Lee and Kim
416 (2017) identified insufficient modular design expertise, poor cost estimation, unstable modular
417 production rate, and errors in structural designs to be the most critical cost-increasing risk factors
418 in MiC projects in Korea. Essentially, critical investment risk factors differ across countries and
419 projects. However, the findings suggest that MiC is associated with a host of investment risk
420 factors. Particularly, it may take a relatively longer period for investors to break-even or achieve
421 commensurate returns on the higher initial capital investment, especially in countries where the
422 MiC market is at the fledgling stage (Dawood 1995b, Richard 2005).

423 **4.3.5 Structural risks**

424 Climate change-driven hazards such as typhoons, earthquakes, progressive collapse, landslides,
425 cyclones, flooding, and severe marine environment is changing the structural requirement of
426 construction projects (Lin *et al.* 2018) and have spurred research on structural risks of projects in
427 the construction and civil engineering domain. The higher complexity in structural design for high-
428 rise MiC projects which can accommodate strong wind load constitutes a significant challenge in
429 high-density cities and neighborhoods (Wuni, Shen, and Mahmud 2019). Meanwhile, the structural
430 integrity of MiC projects is paramount to overcome the historic stigma of prefabricated buildings

431 such as the 1968 collapse of the 22-story Ronan Point Apartment Tower in East London. Structural
432 integrity and operational capability of MiC projects have an influence on cost, quality and clients'
433 satisfaction (Shahtaheri *et al.* 2017). However, due to the complex multi-interfaces in MiC
434 projects, intolerances of modular components engender defects in MiC projects and render them
435 vulnerable to structural failure (Gibb and Neale 1997, Shahtaheri *et al.* 2017).

436 Shahtaheri *et al.* (2017) noted that amid the precise methods of modular production (e.g. 3D
437 fixturing, laser cutting, robotic assembly, etc.) and cutting-edge modular inspection technologies
438 (e.g. laser scanning), problematic dimensional and geometric variabilities abound in MiC projects
439 owing to modular geometric conflicts during production; and between modules & site interfaces.
440 Additionally, incompatibility between process capabilities and desired levels of tolerance trigger
441 a significant challenge in dealing with the excessive geometric variability risks in modular
442 components and assembly (Enshassi *et al.* 2019). The accurate specification of allowable
443 tolerances in MiC projects is indispensable because imprecision may result in less clemency
444 between manufacturing and onsite erection tolerances (*ibid.*). Dimensional and geometric
445 tolerances in MiC are sensitive to modular production errors, the variability of components,
446 measurement imprecision and discrepancies between modular interfaces and thus, failure to
447 specify allowable variability and control tolerances could incubate an obligatory need for reworks
448 (Shahtaheri *et al.* 2017). Existing geometric variability management practices mostly involve trial
449 and error solutions, ad hoc strategies, and the application of strict tolerances which have often
450 resulted in quality problems, schedule delays, budget overrun and increased site-fit reworks
451 (Shahtaheri *et al.* 2017, Enshassi *et al.* 2019). Optimum geometric variability solution may require
452 the combination of both relaxed and strict tolerance approaches to minimize quality and
453 problematic dimensional tolerances (Enshassi *et al.* 2019).

454 During the onsite assembly process of multi-story MiC projects, there are potential events
455 which may breed detrimental eccentricities. Construction errors and a gravitational load of floor
456 slabs are recipes for eccentricities which could complicate the installation of upper floors (Hong
457 *et al.* 2017). These complications translate into low productivity, schedule delays, and cost
458 overruns. Thus, the selection of an effective modular connection method is required to avoid

459 eccentricities. Lin et al. (2018) noted that the structural performance and safety of high-rise MiC
460 projects could be enhanced if they are designed to be multi-hazard resistant. Of critical
461 considerations are seismic actions and progressive collapse (Chiu *et al.* 2013, Lin *et al.* 2018). The
462 multi-hazard design (structural seismic + progressive collapse design) is required to resist lateral
463 forces from seismic actions and unbalanced vertical loads induced by localized failure (Lin *et al.*
464 2018). The multi-hazard MiC project should achieve stable seismic performance, structural
465 resilience and infinitesimal deformation following hazards (ibid).

466 Also, studies have explored the structural risk of MiC projects at the operations stage. Segura
467 et al. (2016) reported that a cooling tower for a thermal power plant constructed of precast concrete
468 suffered a severe deterioration within 3 years of its service-life following a severe exposure to
469 marine conditions. Although the early deterioration was associated with the wetting-drying cycles
470 and chloride-induced corrosion, it demonstrates the potential weaknesses of MiC under severe
471 marine conditions. Adekunle and Nikolopoulou (2016) found that 67% of 116 modular (timber)
472 houses in the UK suffered poor indoor thermal conditions and summertime overheating.
473 Apparently, the low thermal mass of timber exposes such houses to the risk of summertime
474 overheating. Havinga and Schellen (2018) reported mold growth and condensation in 144 Airey
475 houses in the UK amid internal insulation. This highlights the need to carefully select insulation
476 materials for panelized residential MiC projects to prevent early deterioration. Jiao and Li (2018)
477 also reported severe dampness in the external walls of MiC projects in China.

478 **4.3.6 Ergonomic risks**

479 The construction industry is one of the most dangerous sectors which expose its workforce to
480 several health threats due to falls, and awkward working postures (Newaz *et al.* 2018). Thus, a
481 higher incidence of fall injuries, low back pains, and risk of WMSDs are common among
482 construction workers (Bureau of Labor Statistics 2009, Valero *et al.* 2016). Owing to the controlled
483 factory environment, reduced onsite activities, fewer construction workers on site and the
484 minimized requirement to work from heights, MiC improves the safety and health of construction
485 workers (Blismas *et al.* 2006, McGraw Hill Construction 2013). In a survey, the majority of
486 general and specialty contractors in the UK indicated that MiC improves the safety performance

487 of projects (McGraw Hill Construction, 2013). However, the Bureau of Labor Statistics (2017)
488 reported that the total injury and incidence rates (10.2 per 100 workers) were higher in
489 manufactured housing compared to the rates (5.2 per 100 workers) in the onsite residential
490 construction and both of which were above the 4.2 per 100 workers national average of the United
491 States (US). In lean construction parlance, poor safety constitutes a significant cost due to human
492 suffering, worker's compensation cost, lost productivity and higher employee turnover (Nahmens
493 and Ikuma 2009).

494 Different construction workers are exposed to safety risks at various segments of the MiC
495 supply chain. Gustavsson *et al.* (1992) reported that 16 of 1068 workers exposed to artificial
496 mineral fibers, asbestos, combustion fumes from furnaces and arsenic in a Swedish manufactured
497 housing factory died of lung cancer. In the US, construction workers in a modular home
498 manufacturing plant sustained several injuries following exposure to sawdust, excessive noise and
499 volatile organic compounds and forceful exertion during cutting and assembly of heavy
500 components (Ikuma *et al.* 2011). Similarly, Kim *et al.* (2011) found that construction workers were
501 subjected to awkward working postures during the erection of prefabricated panelized wall
502 systems as they exceeded their action limits for spinal compressive (34%) and shear forces
503 (77%).

504 These ergonomic exposures and biomechanical risk events abound because construction
505 workers still engage in the manual (team) handling of modular components such as wall panels in
506 residential MiC (Kim *et al.* 2012). Although manual team handling is appropriate where
507 mechanical aids are unfeasible, the heavy masses of modular components engender risks to the
508 safety of the workers. Nussbaum *et al.* (2009) found that residential carpenters in the manufactured
509 housing in the US were involved in the lifting, carrying and erecting panelized walls in the range
510 of 1.2-6.0m wide and about 250kg. This exposed the workforce to fall injuries, arm, lower and
511 upper back pains (*ibid*). Similarly, Fard *et al.* (2017) found that out of 125 accidents during
512 modular production and onsite installation, fatalities (38.4%), hospitalized injuries (50.4%) and
513 non-hospitalized injuries (11.2%) resulted from 'falls', being struck by a tilt-up roof, falls from
514 roofs, and being struck by objects during hoisting and rigging of large items. Essentially, the

515 manual handling and operations during modular production and on-site assembly are the recipes
 516 for the safety risks. Hsu et al. (2018) found that construction workers in the UK reported severe
 517 fatigue as they manually inspected, unpacked, lined-up, unfastened, screwed, welded modules and
 518 enabled crane lift upon the arrival of modules to a construction site.

519 **4.4 Critical risk events (CREs) in the implementation of MiC**

520 Following risk identification and assessment, the next level on the risk management hierarchy
 521 is risk prioritization (Project Management Institute 2017). Risk events abound in MiC projects, but
 522 their impact varies. It is just not economical and practical to deal with all risk events and thus, risk
 523 management often prioritizes the (critical) risk events as they can derail the performance of
 524 projects. Critical risk events (CREs) are the risk events with the most ‘violent or aggressive’
 525 impact on MiC project’s objectives. Table 4 shows the nineteen most cited risk events. The study
 526 recognizes that a quantitative assessment is required to identify the CREs and that the CREs would
 527 differ across countries and projects. However, the CREs in this paper represent risk events which
 528 were frequently cited and reported in the literature. The frequency column of Table 4 depicts the
 529 number of articles that reported the associated risk event. These were extracted and synthesized
 530 whiles conducting the full-text evaluation and review of the included studies. The rank of each
 531 individual risk event is based on the number of times (frequency) it was cited in the literature.

532 **Table 4.** Critical risk events in the application of MiC

Critical risk event	Freq.	Rank
Delay in modular components delivery	9	1
Supply chain disruptions and disturbances	9	1
Inefficient scheduling	8	3
Defects in design, change order and change in project scope	7	4
Complex stakeholder composition	6	5
Crane breakdown and malfunction	6	5
Insufficient information coordination among project participants	6	5
Modular installation error	6	5
Weather disruptions	6	5
Exposure to fumes, noise and toxic compounds in modular production plant	5	10
Flexing, warping, and damage from transportation and handling	5	10

Manual inspection, unwrapping, lining-up, unhooking, screwing and welding of modular components	5	10
Modular production materials and components shortages	5	10
Insufficient capacity of modular manufacturers and suppliers	4	14
Complex interfacing between modules	3	15
Geometric conflicts between components during manufacturing and between modules & site interfaces	3	15
Longer distance between modular production plant and construction site	3	15
Dimensional and geometric variabilities	3	15
Modular production system failure	2	18

533 **4.5 Risk Management Strategies**

534 Several studies proposed strategies to avoid, reduce or mitigate the impact of some of the MiC risk
535 events discussed in the previous sections. However, it is useful to present a risk structure of MiC
536 prior to synthesis of the risk management strategies. One useful tool in facilitating the
537 comprehensive management of risk is the Risk Breakdown Structure (RBS). RBS depicts a
538 hierarchical structure of the risks associated with a project. Fig. 4 shows the RBS of MiC based on
539 the review. For simplicity, only two levels are presented. The aim is to illustrate the risk associated
540 with the approach and its business model. The various proposed risk management strategies in the
541 extant literature are discussed below.

542 Towards addressing the supply chain and schedule risk events, Zhai et al. (2015) proposed lead-
543 time (T), space (S) and L+S hedging techniques to create a buffer against unforeseen delays,
544 upstream supply, and modular delivery uncertainties. These hedging techniques are aimed at
545 improving the reliability of modular supply to reduce schedule delays. However, as modules are
546 made-to-order (Bortolini *et al.* 2019), advance production, transshipping, and dual sourcing
547 components in MiC is less feasible due to its relatively fixed supply chain once scheduled
548 (Shahtaheri *et al.* 2017). Li, Zhong, et al. (2017) demonstrated how radio frequency identification
549 (RFID) and building information modeling (BIM) could manage and mitigate schedule risk events.
550 They proposed an RFID-enabled real-time BIM platform which integrates all relevant stakeholders
551 in the MiC supply chain to allow for information sharing. The platform allows for real-time
552 information interoperability, visibility, traceability, and exchange. Thus, it facilitates proactive risk

553 management because stakeholders can monitor progress at all levels and could initiate timely
 554 measures to control latent events which could cause schedule delays (Li, Shen, *et al.* 2017).

555 However, these information-driven strategies must move in tandem with other strategies to
 556 improve schedule performance. Wu *et al.* (2019) proposed the adoption of the integrated project
 557 delivery (IPD) (e.g. design-build model) model to diffuse the fragmentation of the MiC supply
 558 chain and stakeholders since IPD demands multi-stakeholder collaboration (e.g. design-build
 559 team). Stakeholder collaborative management is found to have a positive influence on the cost
 560 performance of MiC projects (Xue *et al.* 2018). Bortolini *et al.* (2019) found that collaborative
 561 planning enhances logistics management. Additionally, Hsu *et al.* (2018) proposed an optimal
 562 supply chain configuration to account for onsite modular demand variations. The model aims to
 563 reduce production, operational and penalty cost through the determination of the optimal supply
 564 chain configuration based on all possible demand profiles. The optimal configuration makes a
 565 warehouse an obligatory buffer and decoupling unit between the modular manufacturing plant and
 566 the construction site (Hsu *et al.* 2018).

567 Towards improving the engineer-to-order manufacturing process, Wang *et al.* (2018b) proposed
 568 an optimization of the modular production scheduling based on operational uncertainties such as
 569 ‘process-waiting time on the flow of work’, processing time uncertainty and resources constraints.

570

571

572

573

574

575

576


577

578

579

580

581



582
583
584
585
586
587
588
589
590
591
592
593
594
595
596
597
598
599
600

601 **Fig. 4.** Risk breakdown structure of modular integrated construction

602 The optimization aims at generating minimal manufacturing cost, timely delivery of modules
603 and minimal resources wastage (Wang *et al.* 2018b). Taghaddos et al. (2018) also demonstrated
604 how effective planning, selection, and optimization of crane configurations and lifting options
605 improve the time, cost and safety performance of an industrial project in Alberta, Canada. As such,
606 optimization at every stage of the supply chain could improve the schedule and cost performance
607 of MiC projects.

608 In the context of structural risk, studies have proposed ways of minimizing dimensional
609 intolerances. According to Salama et al. (2017), modular manufacturers should select an optimized

610 configuration of modular components based on the limitations of onsite connection, transportation,
611 and weight. The aim is to minimize the intolerance during modular production. For managing the
612 accumulated effects of dimensional and geometric variability in MiC, Shahtaheri et al. (2017)
613 proposed an approach of combining project risk and structural analysis (risk-based framework) to
614 determine a Pareto-optimal structural assembly configuration with the lowest amalgamated cost
615 of modular production and project risk. This framework is crucial at the planning and design phases
616 of MiC as it allows for an informed trade-off to be made between modular production costs,
617 transport cost, cost of reworks and safety of construction workers. Enshassi *et al.* (2019) proposed
618 a systematic risk management framework to proactively manage the persistent geometric
619 variability risks in MiC projects. The proposed framework offers decision support that allows for
620 quantitative evaluation of modularization risks, uses either a strict or relaxed tolerance approach
621 to identify optimum geometric variability, and generates an optimal selection of mitigation
622 strategy-based on tolerance theory.


623 Moreover, some studies investigated the mitigation strategies for ergonomic exposure and
624 safety risks. Li et al. (2019) developed ErgoSystem; an automated post-3D visualization system
625 which supports worker-friendly workplace design based on automated ergonomic risk assessment.
626 The system automatically assesses ergonomic exposures and allows for changes to be made to the
627 factory layout to prevent ergonomic exposures. Nussbaum et al. (2009) proposed that panelized
628 wall designers should eliminate ergonomic risk by incorporating ergonomic principles into the
629 design of the wall systems. Fard et al. (2017) proposed that injuries could be minimized through
630 stabilization of structures during lifting, storing, and permanent installation; securing fall
631 protection systems during modular assembly while working from heights; and developing safety
632 management initiatives in MiC projects. Studies have also investigated how a lean philosophy can
633 minimize safety risks in MiC projects. Ikuma et al. (2011) implemented Safety and Lean Integrated
634 Kaizen in a modular homebuilding plant and found that back strain, trip hazards and pinch points
635 were significantly reduced. James et al. (2014) and Nahmens and Ikuma (2009) found that good
636 scheduling practice, housekeeping, systematic workflow, production standardization and
637 improved handling of materials minimized injuries and improved the safety of construction
638 workers in the manufactured housing industry in the US. Similarly, Nahmens and Ikuma (2009)

639 implemented lean principles in MiC projects in the US and observed reduced biomechanical
640 hazards, falls and low back injuries.

641 **4.6 Future research directions**

642 Fig. 5 shows the current and proposed future research framework on the risks of MiC. The
643 proposed areas for future research considerations were identified from the gaps in the reviewed
644 studies. The review showed that most of the studies examined MiC supply chain risks events. This
645 suggests that risk events in the supply chain constitute one of the major concerns in MiC. Notably,
646 studies have identified the supply chain risk events (Li *et al.* 2016, Li, Shen, *et al.* 2017, Li, Hong,
647 *et al.* 2018), and the stakeholder-associated risk factors (Li *et al.* 2016, Luo *et al.* 2019). However,
648 there is no quantitative assessment of the supply chain risk events to identify the most critical ones.
649 It should be reiterated that the MiC supply chain involves multidisciplinary practitioners with their
650 unique goals and value systems (Wuni, Shen, and Mahmud 2019). Each of the stakeholders may
651 focus on the risk associated with a segment of the supply chain. Aggregating the risks associated
652 with the entire MiC supply chain is less likely to serve the specific needs of the disparate
653 stakeholders.

654 Thus, future studies would identify and allocate critical risk events in the segments of the MiC
655 supply chain. Furthermore, there are limited studies on the resilience of the MiC supply chain.
656 However, the adaptive capability of the MiC supply chain which allows it to recover quickly
657 following any disturbances is important (Wang *et al.* 2018a) to improve the performance of MiC
658 projects. Thus, future studies would develop a risk resilience framework for the MiC supply chain.
659 Moreover, MiC is associated with different risks and uncertainties (Li *et al.* 2013). However, the
660 magnitude of the risks and uncertainties differ across projects and regions. As risk planning is
661 conducted prior to and during the construction of projects (Baloi and Price 2003), a risk evaluation
662 index is required as a decision support system to guide the selection (Murtaza *et al.* 1993) and risk-
663 rating of MiC projects. However, there is currently no risk evaluation index and decision support
664 for MiC projects (Wuni, Shen, and Mahmud 2019). As such, future studies would develop a risk
665 evaluation index and decision support for MiC projects.



667
668
669
670
671
672
673
674
675
676
677

Fig. 5. Current and future research framework on the risks of MiC

679 Furthermore, one significant challenge in the application of MiC is the management of the
680 geometric variabilities during the modular manufacturing and assembly due to incompatibility
681 between process capabilities and desired levels of tolerance (Enshassi *et al.* 2019). The prevailing
682 reactive geometric variability management practices continue to apply strict tolerances based on
683 trial and error solutions (Shahtaheri *et al.* 2017, Enshassi *et al.* 2019). These practices have proven
684 to be recipes for quality problems, excessive site-fit reworks, cost, and time overruns (Wuni, Shen,
685 and Mahmud 2019). Shahtaheri *et al.* (2017) proposed a geometric and dimensional risk
686 management framework based on strict tolerance approach whereas Enshassi *et al.* (2019)
687 proposed a systematic proactive risk management framework and decision support based on
688 relaxed tolerance approach. However, there are little studies on the possibility of managing
689 geometric variability risk based on a combined strict-relaxed tolerance approach. Future studies

690 will conduct a robust assessment of the impact of this combined tolerance-based mitigation
691 strategy on quality, schedule, and cost performance of MiC projects.

692 Finally, studies have deployed smart construction objects and developed RFID - enabled BIM
693 platform which integrates involved stakeholders, allowing for effective monitoring of workflow
694 progress and information/data exchange in the manufacturing, logistics and on-site assembly
695 segments of the MiC supply chain (Li, Zhong, *et al.* 2017, Zhong *et al.* 2017, Li, Xue, *et al.* 2018).
696 The internet of things (IoT) – enabled BIM platform (Zhong *et al.* 2017, Li, Xue, *et al.* 2018),
697 smart construction objects and RFID-enabled smart gateway (Li, Zhong, *et al.* 2017) work
698 effectively in ensuring data/information traceability, interoperability, visibility, exchange and
699 allows for proactive management of MiC schedule risks (Li, Zhong, *et al.* 2017). However, none
700 of the developed platforms incorporated fault-tolerant techniques which allow for effective
701 elimination errors caused by faulty operations and inputs. Thus, future studies would modify these
702 platforms to improve their performance.

703 5. Conclusions

704 Following the growing body of bespoke literature on the risks of MiC, this research conducted
705 a systematic review and synthesis of empirical studies on the risks of MiC from 1992 to 2019. It
706 is found that research publications on the risk of MiC only witnessed a steady growth within the
707 last decade. This suggests that risk of MiC is gaining attention in the CEM domain. Based on a
708 content analysis framework, it is found that existing studies focused more on identification and
709 assessment of perceived implementation risks, supply chain risks, schedule risks, investment risks,
710 structural risks, ergonomic risks, and MiC risk management strategies. These multiple forms of
711 risks suggest that MiC is associated with a host of risks and uncertainties. Based on the frequency
712 of occurrences, the paper identified nineteen (19) critical risk events (CREs) which were reported
713 in at least two (2) studies. The top 10 CREs include delay in modular delivery; supply chain
714 disruptions and disturbances; inefficient scheduling; design defects and change in project scope;
715 complex stakeholder composition; crane malfunction; insufficient information coordination
716 among project participants; modular installation error; and weather disruptions. These should be
717 carefully considered in the implementation of MiC.

718 Although significant research progress has been made on the risk of MiC, the paper identified
719 some areas that require further research. Future studies should (i) conduct quantitative assessment
720 and ranking of the CREs in the MiC supply chain, (ii) allocate risks among the various segments
721 of the MiC supply chain, (iii) examine the MiC supply chain resilience, (iv) develop a risk
722 evaluation index and decision support framework, (v) incorporate fault-tolerant techniques in the
723 Integration of RFID and BIM for MiC supply chain management, and (vi) develop a combined
724 strict-relaxed tolerance-based framework for management of geometric variability risk. As such,
725 this paper makes a unique contribution to the scholarly literature on the risk of OSC as it constitutes
726 the first exclusive review on the risks of MiC. The paper has delineated the boundaries of existing
727 studies, highlighted the gaps and deficiencies in current studies and proffered some directions for
728 future studies. The paper further developed an RBS of MiC and identified some CREs in the
729 implementation of MiC. The CREs contributes to the checklists of risk events associated with OSC
730 and may broaden the understanding of OSC researchers, project managers and practitioners on the
731 risks associated with MiC. The checklist of CREs may also be useful in risk planning in countries
732 where the MiC market is still fledgling, and fewer or no bespoke risk assessment exists. For
733 policymakers, the study highlighted the need for increased commitment to making MiC more
734 attractive as the approach continues to fight the historic stigma of prefabricated housing and risk
735 stereotyping. Finally, the proposed research framework provides a useful foundation for future
736 studies. However, the study has the following limitations. Firstly, a sample size of 54 is small but
737 considering that the MiC is now gaining attention, this review is timely and useful. Secondly,
738 although a comprehensive search was conducted, it is possible that some relevant articles may
739 have been missed.

740

741

742

743

744

745

746

747

748 **References**

- 749 Adekunle, T.O. and Nikolopoulou, M., 2016. Thermal comfort, summertime temperatures and
750 overheating in prefabricated timber housing. *Building and Environment*, 103, 21–35.
- 751 Assaf, S.A. and Al-Hejji, S., 2006. Causes of delay in large construction projects. *International*
752 *Journal of Project Management*, 24 (4), 349–357.
- 753 Azman, M.N.A., Ahamad, M.S.S., Majid, T.A., Yahaya, A.S., and Hanafi, M.H., 2013. Statistical
754 evaluation of pre-selection criteria for industrialized building system (IBS). *Journal of Civil*
755 *Engineering and Management*, 19 (sup1), S131–S140.
- 756 Baker, J.D., 2016. The Purpose, Process, and Methods of Writing a Literature Review. *AORN*
757 *Journal*, 103 (3), 265–269.
- 758 Baloi, D. and Price, A.D.F., 2003. Modelling global risk factors affecting construction cost
759 performance. *International Journal of Project Management*, 21 (4), 261–269.
- 760 Blismas, N.G., Pasquire, C., and Gibb, A.G.F., 2006. Benefit evaluation for off-site production in
761 construction. *Construction Management and Economics*, 24 (2), 121–130.
- 762 Blismas, N.G. and Wakefield, R., 2009. Drivers, constraints and the future of offsite manufacture
763 in Australia. *Construction Innovation*, 9 (1), 72–83.
- 764 Bortolini, R., Formoso, C.T., and Viana, D.D., 2019. Site logistics planning and control for
765 engineer-to-order prefabricated building systems using BIM 4D modeling. *Automation in*
766 *Construction*, 98 (February), 248–264.
- 767 Bureau of Labor Statistics, 2009. *Incidence rate and number of nonfatal occupational injuries by*
768 *industry and ownership, 2008*. Washington, D.C., United States.
- 769 Bureau of Labor Statistics, 2017. *Employer-Reported Workplace Injuries and Illnesses-2016*.
770 Washington, D.C., United States.
- 771 Chiang, Y.H., Hon-Wan Chan, E., and Ka-Leung Lok, L., 2006. Prefabrication and barriers to
772 entry-a case study of public housing and institutional buildings in Hong Kong. *Habitat*
773 *International*, 30 (3), 482–499.
- 774 Chiu, C.K., Chen, M.R., and Chiu, C.H., 2013. Financial and Environmental Payback Periods of
775 Seismic Retrofit Investments for Reinforced Concrete Buildings Estimated Using a Novel
776 Method. *Journal of Architectural Engineering*, 19 (2), 112–118.
- 777 Dawood, N.N., 1995a. An integrated bidding management expert system for the make-to-order
778 precast industry. *Construction Management and Economics*, 13 (2), 115–125.
- 779 Dawood, N.N., 1995b. Scheduling in the precast concrete industry using the simulation modelling
780 approach. *Building and Environment*, 30 (2), 197–207.
- 781 Egan, J., 1998. *Rethinking construction: The Report of the Construction Task Force*.
- 782 Enshassi, M.S.A., Walbridge, S., West, J.S., and Haas, C.T., 2019. Integrated Risk Management
783 Framework for Tolerance-Based Mitigation Strategy Decision Support in Modular

- 784 Construction Projects. *Journal of Management in Engineering*, 35 (4), 05019004.
- 785 Evans, D., 2004. The systematic review report. *Collegian: Journal of the Royal College of Nursing*
- 786 *Australia*, 11 (1), 8–11.
- 787 Fard, M.M., Terouhid, S.A., Kibert, C.J., and Hakim, H., 2017. Safety concerns related to
- 788 modular/prefabricated building construction. *International Journal of Injury Control and*
- 789 *Safety Promotion*, 24 (1), 10–23.
- 790 Finfgeld-Connett, D., 2014. Use of content analysis to conduct knowledge-building and theory-
- 791 generating qualitative systematic reviews. *Qualitative Research*, 14 (3), 341–352.
- 792 Gan, X., Chang, R., Zuo, J., Wen, T., and Zillante, G., 2018. Barriers to the transition towards off-
- 793 site construction in China: An Interpretive structural modeling approach. *Journal of Cleaner*
- 794 *Production*, 197, 8–18.
- 795 Gibb, A.G.F., 1999. *Off-site Fabrication: Prefabrication, Pre-assembly and Modularization*. 1st
- 796 ed. Latheronwheel: Whittles Publishing.
- 797 Gibb, A.G.F., 2001. Standardization and pre-assembly- distinguishing myth from reality using
- 798 case study research. *Construction Management and Economics*, 19 (3), 307–315.
- 799 Gibb, A.G.F. and Neale, R.H., 1997. Management of prefabrication for complex cladding: Case
- 800 study. *Journal of Architectural Engineering*, 3 (2), 60–69.
- 801 Gustavsson, P., Plato, N., Axelson, O., Brage, H.N., Hogstedt, C., Ringbäck, G., Tornling, G., and
- 802 Wingren, G., 1992. Lung cancer risk among workers exposed to man-made mineral fibers
- 803 (MMMF) in the swedish prefabricated house industry. *American Journal of Industrial*
- 804 *Medicine*, 21 (6), 825–834.
- 805 Hassim, S., Jaafar, M.S., and Sazalli, S.A.A.H., 2009. The Contractor Perception Towards
- 806 Industrialised Building System Risk in Construction Projects in Malaysia. *American Journal*
- 807 *of Applied Sciences*, 6 (5), 937–942.
- 808 Hassim, S., Sazalli, S.A.A.H., and Jaafar, M.S., 2008. Identification of sources of risk in IBS
- 809 project. *European Journal of Social Sciences*, 6 (3), 315–324.
- 810 Havinga, L. and Schellen, H., 2018. Applying internal insulation in post-war prefab housing:
- 811 Understanding and mitigating the hygrothermal risks. *Building and Environment*, 144
- 812 (August), 631–647.
- 813 Hong Kong Buildings Department, 2018. *Modular Integrated Construction*. Hong Kong.
- 814 Hong, W.-K., Kim, G., Lim, C., and Kim, S., 2017. Development of a steel-guide connection
- 815 method for composite precast concrete components. *Journal of Civil Engineering and*
- 816 *Management*, 23 (1), 59–66.
- 817 Hosseini, M.R., Martek, I., Zavadskas, E.K., Aibinu, A.A., Arashpour, M., and Chileshe, N., 2018.
- 818 Critical evaluation of off-site construction research: A Scientometric analysis. *Automation in*
- 819 *Construction*, 87 (January), 235–247.
- 820 Hsu, P.Y., Angeloudis, P., and Aurisicchio, M., 2018. Optimal logistics planning for modular
- 821 construction using two-stage stochastic programming. *Automation in Construction*, 94 (May),
- 822 47–61.
- 823 Hwang, B.-G., Shan, M., and Looi, K.-Y., 2018. Key constraints and mitigation strategies for
- 824 prefabricated prefinished volumetric construction. *Journal of Cleaner Production*, 183, 183–
- 825 193.
- 826 Ikuma, L.H., Nahmens, I., and James, J., 2011. Use of Safety and Lean Integrated Kaizen to

- 827 Improve Performance in Modular Homebuilding. *Journal of Construction Engineering and*
828 *Management*, 137 (7), 551–560.
- 829 Jaillon, L. and Poon, C.S., 2008. Sustainable construction aspects of using prefabrication in dense
830 urban environment: A Hong Kong case study. *Construction Management and Economics*, 26
831 (9), 953–966.
- 832 Jaillon, L., Poon, C.S., and Chiang, Y.H., 2009. Quantifying the waste reduction potential of using
833 prefabrication in building construction in Hong Kong. *Waste Management*, 29 (1), 309–320.
- 834 James, J., Ikuma, L.H., Nahmens, I., and Aghazadeh, F., 2014. The impact of Kaizen on safety in
835 modular home manufacturing. *International Journal of Advanced Manufacturing*
836 *Technology*, 70 (1–4), 725–734.
- 837 Ji, Y., Qi, L., Liu, Y., Liu, X., Li, H.X., and Li, Y., 2018. Assessing and prioritising delay factors
838 of prefabricated concrete building projects in China. *Applied Sciences (Switzerland)*, 8
839 (2324), 1–16.
- 840 Jiang, L., Li, Z., Li, L., and Gao, Y., 2018. Constraints on the promotion of prefabricated
841 construction in China. *Sustainability (Switzerland)*, 10 (7), 1–17.
- 842 Jiang, R., Mao, C., Hou, L., Wu, C., and Tan, J., 2017. A SWOT analysis for promoting off-site
843 construction under the backdrop of China’s new urbanisation. *Journal of Cleaner Production*,
844 173, 225–234.
- 845 Jiao, L. and Li, X.D., 2018. Application of Prefabricated Concrete in Residential Buildings and its
846 Safety Management. *Archives of Civil Engineering*, 64 (2), 21–35.
- 847 Kim, S., Nussbaum, M.A., and Jia, B., 2011. Low back injury risks during construction with
848 prefabricated (panelised) walls: Effects of task and design factors. *Ergonomics*, 54 (1), 60–
849 71.
- 850 Kim, S., Nussbaum, M.A., and Jia, B., 2012. The benefits of an additional worker are task-
851 dependent: Assessing low-back injury risks during prefabricated (panelized) wall
852 construction. *Applied Ergonomics*, 43 (5), 843–849.
- 853 Lee, J.S. and Kim, Y.S., 2017. Analysis of cost-increasing risk factors in modular construction in
854 Korea using FMEA. *KSCE Journal of Civil Engineering*, 21 (6), 1999–2010.
- 855 Levy, Y. and Ellis, T.J., 2006. A systems approach to conduct an effective literature review in
856 support of information systems research. *Informing Science Journal*, 9, 181–212.
- 857 Li, C.Z., Hong, J., Fan, C., Xu, X., and Shen, G.Q., 2018. Schedule delay analysis of prefabricated
858 housing production: A hybrid dynamic approach. *Journal of Cleaner Production*, 195, 1533–
859 1545.
- 860 Li, C.Z., Hong, J., Xue, F., Shen, G.Q., Xu, X., and Mok, M.K., 2016. Schedule risks in
861 prefabrication housing production in Hong Kong: a social network analysis. *Journal of*
862 *Cleaner Production*, 134 (Part B), 482–494.
- 863 Li, C.Z., Shen, G.Q., Xue, F., Luo, L., Xu, X., and Sommer, L., 2017. Schedule risk modeling in
864 prefabrication housing production. *Journal of Cleaner Production*, 153, 692–706.
- 865 Li, C.Z., Xu, X., Shen, G.Q., Fan, C., Li, X., and Hong, J., 2018. A model for simulating schedule
866 risks in prefabrication housing production: A case study of six-day cycle assembly activities
867 in Hong Kong. *Journal of Cleaner Production*, 185, 366–381.
- 868 Li, C.Z., Xue, F., Li, X., Hong, J., and Shen, G.Q., 2018. An Internet of Things-enabled BIM
869 platform for on-site assembly services in prefabricated construction. *Automation in*

- 870 *Construction*, 89 (February), 146–161.
- 871 Li, C.Z., Zhong, R.Y., Xue, F., Xu, G., Chen, K., Huang, G.G., and Shen, G.Q., 2017. Integrating
872 RFID and BIM technologies for mitigating risks and improving schedule performance of
873 prefabricated house construction. *Journal of Cleaner Production*, 165, 1048–1062.
- 874 Li, H.X., Al-Hussein, M., Lei, Z., and Ajweh, Z., 2013. Risk identification and assessment of
875 modular construction utilizing fuzzy analytic hierarchy process (AHP) and simulation.
876 *Canadian Journal of Civil Engineering*, 40 (12), 1184–1195.
- 877 Li, M., Li, G., Huang, Y., and Deng, L., 2017. Research on Investment Risk Management of
878 Chinese Prefabricated Construction Projects Based on a System Dynamics Model. *Buildings*,
879 7 (3), 83.
- 880 Li, X., Han, S.H., Gül, M., and Al-Hussein, M., 2019. Automated post-3D visualization ergonomic
881 analysis system for rapid workplace design in modular construction. *Automation in*
882 *Construction*, 98 (July 2018), 160–174.
- 883 Li, Z., Shen, G.Q.P., and Xue, X., 2014. Critical review of the research on the management of
884 prefabricated construction. *Habitat International*, 43, 240–249.
- 885 Lin, K., Lu, X., Li, Y., and Guan, H., 2018. Experimental study of a novel multi-hazard resistant
886 prefabricated concrete frame structure. *Soil Dynamics and Earthquake Engineering*, (March).
- 887 Love, P.E.D., Veli, S., Davis, P., Teo, P., and Morrison, J., 2017. See the Difference in a Precast
888 Facility: Changing Mindsets with an Experiential Safety Program. *Journal of Construction*
889 *Engineering and Management*, 143 (2), 05016021.
- 890 Lovell, H. and Smith, S.J., 2010. Agencement in housing markets: The case of the UK construction
891 industry. *Geoforum*, 41 (3), 457–468.
- 892 Luo, L., Mao, C., Shen, L., and Li, Z., 2015. Risk factors affecting practitioners' attitudes toward
893 the implementation of an industrialized building system a case study from China.
894 *Engineering, Construction and Architectural Management*, 22 (6), 622–643.
- 895 Luo, L., Shen, G.Q., Xu, G., Liu, Y., and Wang, Y., 2019. Stakeholder-associated Supply Chain
896 Risks and Their Interactions in a Prefabricated Building Project: A Case Study in Hong
897 Kong. *Journal of Management in Engineering*, 35 (2), 1–14.
- 898 Mao, C., Shen, Q., Pan, W., and Ye, K., 2014. Major Barriers to Off-Site Construction: The
899 Developer's Perspective in China. *Journal of Management in Engineering*, 31 (3), 04014043.
- 900 Mao, C., Shen, Q., Shen, L., and Tang, L., 2013. Comparative study of greenhouse gas emissions
901 between off-site prefabrication and conventional construction methods: Two case studies of
902 residential projects. *Energy and Buildings*, 66, 165–176.
- 903 McGraw Hill Construction, 2013. *Safety Management in the Construction Industry: Identifying*
904 *Risks and Reducing Accidents to Improve Site Productivity and Project ROI*. Smart Market
905 Report. Bedford, MA.
- 906 Murtaza, M.B., Fisher, D.J., and Skibniewski, M.J., 1993. Knowledge-Based Approach to
907 Modular Construction Decision Support. *Journal of Construction Engineering and*
908 *Management*, 119 (1), 115–130.
- 909 Nahmens, I. and Ikuma, L., 2009. An empirical examination of the relationship between lean
910 construction and safety in the industrialized housing industry. *Lean Construction Journal*, 1,
911 1–12.
- 912 Nam, C.H. and Tatum, C.B., 1997. Leaders and champions for construction innovation.

- 913 *Construction Management and Economics*, 15 (3), 259–270.
- 914 Newaz, M.T., Davis, P.R., Jefferies, M., and Pillay, M., 2018. Developing a safety climate factor
915 model in construction research and practice: A systematic review identifying future directions
916 for research. *Engineering, Construction and Architectural Management*, 25 (6), 738–757.
- 917 Nussbaum, M.A., Shewchuk, J.P., Kim, S., Seol, H., and Guo, C., 2009. Development of a decision
918 support system for residential construction using panellised walls: Approach and preliminary
919 results. *Ergonomics*, 52 (1), 87–103.
- 920 Pan, W. and Goodier, C., 2012. House-Building Business Models and Off-Site Construction Take-
921 Up. *Journal of Architectural Engineering*, 18 (June), 84–93.
- 922 Polat, G., 2008. Factors Affecting the Use of Precast Concrete Systems in the United States.
923 *Journal of Construction Engineering and Management*, 134 (3), 169–178.
- 924 Project Management Institute, 2017. *A Guide to the Project Management Body of Knowledge*
925 *(PMBOK Guide)*. 6th Editio. Newton Square, Pennsylvania: Project Management Institute.
- 926 Quale, J., Eckelman, M.J., Williams, K.W., Sloditskie, G., and Zimmerman, J.B., 2012.
927 Construction Matters: Comparing Environmental Impacts of Building Modular and
928 Conventional Homes in the United States. *Journal of Industrial Ecology*, 16 (2), 243–253.
- 929 Rahman, M.M., 2014. Barriers of Implementing Modern Methods of Construction. *Journal of*
930 *Management in Engineering*, 30 (1), 69–77.
- 931 Richard, R.B., 2005. Industrialised building systems: Reproduction before automation and
932 robotics. *Automation in Construction*, 14 (4), 442–451.
- 933 Saieg, P., Sotelino, E.D., Nascimento, D., and Caiado, R.G.G., 2018. Interactions of Building
934 Information Modeling, Lean and Sustainability on the Architectural, Engineering and
935 Construction industry: A systematic review. *Journal of Cleaner Production*, 174, 788–806.
- 936 Salama, T., Salah, A., Moselhi, O., and Al-Hussein, M., 2017. Near optimum selection of module
937 configuration for efficient modular construction. *Automation in Construction*, 83, 316–329.
- 938 Segura, I., Cavalaro, S., Fuente, A. de la, Aguado, A., and Alegre, V., 2016. Service-Life
939 Assessment of Existing Precast Concrete Structure Exposed to Severe Marine Conditions.
940 *Journal of Performance of Constructed Facilities*, 30 (3), 04015036.
- 941 Shahtaheri, Y., Rausch, C., West, J., Haas, C., and Nahangi, M., 2017. Managing risk in modular
942 construction using dimensional and geometric tolerance strategies. *Automation in*
943 *Construction*, 83, 303–315.
- 944 Slaughter, E.S., 1998. Models of Construction Innovation. *Journal of Construction Engineering*
945 *and Management*, 124 (3), 226–231.
- 946 Smith, R.E., 2016. Off-Site and Modular Construction Explained [online]. *National Institute of*
947 *Building Sciences*. Available from: [https://www.wbdg.org/resources/site-and-modular-](https://www.wbdg.org/resources/site-and-modular-construction-explained)
948 [construction-explained](https://www.wbdg.org/resources/site-and-modular-construction-explained) [Accessed 11 Nov 2018].
- 949 Taghaddos, H., Hermann, U., and Abbasi, A.B., 2018. Automated Crane Planning and
950 Optimization for modular construction. *Automation in Construction*, 95 (August), 219–232.
- 951 Valero, E., Sivanathan, A., Bosché, F., and Abdel-Wahab, M., 2016. Musculoskeletal disorders in
952 construction: A review and a novel system for activity tracking with body area network.
953 *Applied Ergonomics*, 54, 120–130.
- 954 Wang, Z., Hu, H., and Gong, J., 2018a. Simulation based multiple disturbances evaluation in the
955 precast supply chain for improved disturbance prevention. *Journal of Cleaner Production*,

- 956 177, 232–244.
- 957 Wang, Z., Hu, H., and Gong, J., 2018b. Framework for modeling operational uncertainty to
 958 optimize offsite production scheduling of precast components. *Automation in Construction*,
 959 86 (April), 69–80.
- 960 Webster, J. and Watson, R.T., 2002. Analyzing the Past To Prepare for the Future : Writing a
 961 Literature Review. *MIS Quarterly*, 26 (2), xiii–xxiii.
- 962 Wohlin, C., 2014. Guidelines for snowballing in systematic literature studies and a replication in
 963 software engineering. In: *Proceedings of the 18th International Conference on Evaluation
 964 and Assessment in Software Engineering - EASE '14*. London, England, United Kingdom:
 965 Association for Computing Machinery (ACM), 1–10.
- 966 Wu, P., Xu, Y., Jin, R., Lu, Q., Madgwick, D., and Hancock, C.M., 2019. Perceptions towards
 967 risks involved in off-site construction in the integrated design & construction project delivery.
 968 *Journal of Cleaner Production*, 213, 899–914.
- 969 Wuni, I.Y. and Shen, G.Q.P., 2019. Holistic Review and Conceptual Framework for the Drivers
 970 of Offsite Construction : A Total Interpretive Structural Modelling Approach. *Buildings*, 9
 971 (117), 1–24.
- 972 Wuni, I.Y., Shen, G.Q.P., and Mahmud, A.T., 2019. Critical risk factors in the application of
 973 modular integrated construction : a systematic review. *International Journal of Construction
 974 Management*, 1–15.
- 975 Wuni, I.Y., Shen, G.Q.P., and Osei-kyei, R., 2019. Scientometric Review of Global Research
 976 Trends on Green Buildings in Construction Journals from 1992 to 2018. *Energy & Buildings*,
 977 190 (May), 69–85.
- 978 Xue, H., Zhang, S., Su, Y., and Wu, Z., 2017. Factors affecting the capital cost of prefabrication-
 979 A case study of China. *Sustainability (Switzerland)*, 9 (9), 1–22.
- 980 Xue, H., Zhang, S., Su, Y., Wu, Z., and Yang, R.J., 2018. Effect of stakeholder collaborative
 981 management on off-site construction cost performance. *Journal of Cleaner Production*, 184,
 982 490–502.
- 983 Zhai, X., Reed, R., and Mills, A., 2014. Factors impeding the offsite production of housing
 984 construction in China: An investigation of current practice. *Construction Management and
 985 Economics*, 32 (1–2), 40–52.
- 986 Zhai, Y., Zhong, R.Y., and Huang, G.Q., 2015. Towards operational hedging for logistics
 987 uncertainty management in prefabrication construction. *IFAC-PapersOnLine*, 28 (3), 1128–
 988 1133.
- 989 Zhang, X., Skitmore, M., and Peng, Y., 2014. Exploring the challenges to industrialized residential
 990 building in China. *Habitat International*, 41, 176–184.
- 991 Zhong, R.Y., Peng, Y., Xue, F., Fang, J., Zou, W., Luo, H., Thomas Ng, S., Lu, W., Shen, G.Q.P.,
 992 and Huang, G.Q., 2017. Prefabricated construction enabled by the Internet-of-Things.
 993 *Automation in Construction*, 76, 59–70.